# MARITIME REPORTER

ENGINEERING NEWS

OUTSTANDING
OFFSHORE/SHALLOW-DRAFT VESSELS
OF 1983


Justin T. Rogers

WORKBOAT INDUSTRY ISSUE
JANUARY 1, 1984

# Start-up Savoir-faire








It's the start-up savoir-faire of installation crew members such as Clay Mouton that keeps shipyards and operators, large and small, coming back to GECO.


They know our start-up savoir-faire insures on-time deliveries for real-time utilization.



HARVEY 347-4326 / BATON ROUGE 926-2910 / LAFAYETTE 235-9076 / MORGAN CITY 384-4990

# The very best to you in 1984





Micro-Processor Control System, Model 1200A with gyro input . . . holds vessel's heading. System also accepts compatible NAV AIDS tore alt and slow-speed propulsion and positioning

#### MODULAR THRUSTER SYSTEM

OMNITHRUSTER ship control systems\* utilize individual module thrusters of up to 3000 HP in any combination to produce desired forward or lateral net thrust. Prime movers for the Modular Thruster System may be electric, hydraulic or diesel powered in conjunction with manual/automatic or integrated control networks ADVANTAGES FOR LARGE VESSELS...

- Incremental Thrust Capability
   Multiple Module Polisbility
- Multiple Module ReliabilityEasily Retrofitted or Installed in New
- Construction

  Minimum Maintenance
- \*\*Naval Architects: Robert Allan, Ltd. for Gulf Canada Resources, Inc.



\*Covered by U. S. Patents; Foreign Patents Pending

# **OMNITHRUSTER INC.**

9515 Sorenson Avenue, Dept. 31-1A-4 Santa Fe Springs, California 90670 213/802-1818 Telex 194265 OMNI SFES Cable Address OMNITHRUST

Circle 102 on Reader Service Card

# ON THE COVER

Cover Photo: DayPhoto St. Louis, Mo.

Outstanding Offshore/ Shallow-Draft Vessels Of 1983

PAGE 18

Weakening The Jones Act PAGE 6

Shipyards And The Jones Act PAGE 44

Modern Fuel Systems Symposium—A Report PAGE 10

# Triple A South Awarded \$10-Million Navy Contract For Overhaul Of AS-37

Triple A. South, San Diego, Calif., has been awarded a \$10,284,918 firm-fixed-price contract for the overhaul of submarine tender USS Dickson (AS-37). The Supervisor of Shipbuilding, Conversion and Repair, San Diego, Calif. is the contracting activity.

# Consafe Will Design And Build Accommodations Unit For A Tenneco Company

Consafe, Inc. of Houston will design and fabricate a 40-man offshore accommodations unit for a Tenneco production platform in South Timbalier, Block 27, Gulf of Mexico. Tenneco Oil Explorations and Productions, Eastern Gulf Division, awarded the contract. Completion of the quarters unit is expected in early 1984. It will contain approximately 5,000 square feet of living space.

The Consafe type of modular

The Consafe type of modular construction is used worldwide, but this project represents a breakthrough to Consafe design for the Gulf of Mexico. According to Consafe president Bertil Larsson: "Consafe provides heavy-duty steel construction in its units, which can be used for clustering as well as for temporary or permanent use. Total flexibility is a primary feature of Consafe design."

# MARITIME REPORTER and Engineering News

Editorial and Executive Offices 107 East 31st Street, New York, N.Y. 10016 (212) 689-3266 • ITT Telex: 424768 MARINTI

#### **PUBLISHERS**

John E. O'Malley Charles P. O'Malley

VICE PRESIDENT

John C. O'Malley

EDITORIAL DIRECTOR

Charles P. O'Malley

**EDITOR** 

Robert Ware

SENIOR EDITOR

Thomas H. Phillips

ASSOCIATE EDITOR

Kathleen Reagan

EDITORIAL COORDINATOR

Lillian Irvine

TECHNICAL EDITOR

L. Parke Adair, BSNA, PE

INTERNATIONAL EDITOR

Robin F. Burnett, MRINA, MNI, London, England

**BUSINESS MANAGER** 

John E. O'Malley

ADVERTISING SALES DIRECTOR

John C. O'Malley

ADVERTISING PRODUCTION MANAGER

Katherine St. Onge

ART DIRECTOR

Ellen Hemmer

CIRCULATION MANAGER

M. Sottile

#### SALES OFFICES

New York, New York

Maritime Reporter & Engineering News 107 East 31st Street New York, NY 10016 Telephone: (212) 689-3266

Houston, Texas

Robert Hawley Gary Lindenberger Mike Sullivan 11777 Katy Freeway, Suite 155 Houston, TX 77079 Telephone: (713) 870-0470

Italy

Mr. Vittorio F. Negrone Ediconsult Internazionale Piazza Fontane Marose 3-16123 Genova, Italy Telex: 211197 EDINT 1 Telephone: (010) 543.659-268.334-268.513

Scandinavia

Mr. Stephan R G Orn Ab Stephan R G Orn Box 184, S-271 00 Ystad, Sweden Telex: 33335 ORN S Telephone: 0411-184 00

MARITIME REPORTER ENGINEERING NEWS

(USPS) 016-750

No. 1

Volume 46

107 EAST 31st STREET NEW YORK, N.Y. 10016

(212) 689-3266
Telex: MARINTI 424768
ESTABLISHED 1939

lation postage paid at Waterbury, Connecticut 06701.

Postmaster send notification (Form 3579) regarding undeliverable

Postmaster send notification (Form 3579) regarding undeliverable magazines to Maritime Reporter/Engineering News, 107 East 31st Street, New York, N.Y. 10016.

Maritime Reporter/Engineering News is published the 1st and 15th

of each month by Maritime Activity Reports, Inc. Controlled Circu-

WBPA

Business Publications
Audit of Circulation, Inc.

Member

# Navy Contracts Totaling \$477 Million Awarded To Avondale Shipyards

The U.S. Navy recently exercised its option to have Avondale Shipyards, Inc., a subsidiary of Ogden Corporation, construct two additional fleet oilers at a total cost of \$231.9 million. The Navy also awarded Avondale a \$166million contract to build a landing ship dock.

The Navy has options to award Avondale up to four additional LSDs, two through January 1985 at a total cost of \$304 million, and two through January 1986 at a total cost of \$297 million. Both the fleet oiler and the landing ship dock contracts provide for escalation related to cost of labor and materials.

In November 1982 the Navy awarded Avondale a contract to build a first fleet oiler, scheduled for delivery in early 1986, and subsequently exercised an option for the construction of a second oiler for mid-1986 delivery. The two additional oilers awarded recently will be delivered at 4-month intervals after the mid-1986 delivery. Construction of the first oiler will begin in 1984 at Avondale's main yard near New Orleans.

# \$56.6-Million Award To Ingalls For Long-Lead Materials For LHD-1

Litton Systems Incorporated, Ingalls Shipbuilding Division, Pascagoula, Miss., has been awarded a \$59,607,882 face-value-increase to a previously awarded cost-plusfixed-fee contract for long-lead time material for the multi-purpose amphibious assault ship LHD-1, including one boat and aircraft crane, two deck edge elevators, five air conditioner chill water plants, main and emergency switchboards, exterior communications system, various power supplies, switchboards and control consoles, and four main feed booster pumps. The Naval Sea Systems Command, Washington, D.C., is the contracting activity.

# Marinette Marine Awarded \$1-Million Minesweeper Phase II Design Contract

Marinette Marine Corporation (MMC) has been notified by the Naval Sea System Command that it is being awarded one of two Phase II minesweeper hunter (MSH) design contracts. As a previous participant in the MSH Phase I preliminary design, MMC was one of four shipbuilders competing for the Phase II contracts. MMC completed Phase I earlier this year. and the resultant Phase II award was based upon the technical content of MMC's Phase I MSH design effort.

The MSH ship is a totally new

coastal water mine hunting and sweeping duty. MMC is developing this design through the efforts of its in-house engineering group, and such qualified teaming members as General Electric, Magnavox, Marconi, NKF Engineering and Research, Analysis and Management Corporation. MMC's design approach utilizes the glass reinforced plastic (GRP) hull technology of Intermarine, S.p.A. of It-

class of vessel designated for U.S. aly, a world-renowned producer of fiberglass minesweepers. Designed as a low-cost, highly effective multimission mine hunting and sweeping vessel, the MMC ship will provide the Navy with a greatly expanded U.S. defense capability.

Navy plans for the MSH program require MMC to complete the \$1,000,000 Phase II MSH contract design in  $8\frac{1}{2}$  months, with the anticipated award of the detail design and lead ship construction contract scheduled for August 1984. The Navy intends to obtain 17 vessels of the new MSH class over a multi-year procurement cycle. MMC currently has under contract the construction of the Navy's new Mine Countermeasure (MCM) class vessel. The continuation of the MSH design program provides MMC with the opportunity to become one of the leading producers of state-of-the-art minesweepers worldwide.



# Single NEW Source for All These Products

Radio-Holland U.S.A. has done it again! We are exclusive U.S. agents for the complete and spectacular Sailor radio line. Just about any VHF or SSB communications problem can be solved—and at the lowest prices this country has ever seen for these premium quality radios. And that's not all! We are also exclusive agents for the Philips

STB-750 Mkll SITOR and PACT-220 teleprinters. We also offer exclusively labelled Radio-Holland products, and the best part-more products to come. Dealerships—supported by generous discount, stocking, warranty, training, promotion, and other policies—are now available throughout the entire U.S. For more information, call Sal Berte, Distributor Products Division, at:

# RADIO-HOLLAND USA. INC.

6033 South Loop East, Houston, TX 77033 Tel. (713) 649-1048 / Telex 795438

Also in: The Netherlands, Caribbean, Venezuela, Singapore, Indonesia, Hong Kong, Shanghai, South Africa

# WEAKENING THE JONES ACT

# — A Threat To Our Competitive Position —

Joseph A. Farrell, President American Waterways Operators, Inc.



Joseph A. Farrell

Most of us in the water freight transportation industry do not often think of the Jones Act and related cabotage laws as having much to do with the inland segment of the barge and towing industry, although clearly the protection afforded by the Act is an integral part not only of the coastal but also the inland operations. The American Waterways Operators, Inc. (AWO) represents the interests of both the inland and coastal segments of the barge and towing industry, nationwide. In carrying out the AWO objectives, we have been giving an ever-increasing amount of attention to the effect various recent efforts to dilute the Jones Act will have on the barge and towing industry as a whole. If the Jones Act is breached in the coastal trade, it isn't much of a leap to have foreign vessels plying the rivers.

The sovereign right of every nation to reserve its domestic trade to its own nationals has been recognized for centuries by interna-

botage, to reserve domestic freight to domestic carriers is not unique to the United States. Nearly every major maritime country adheres to this principle today, recognizing the absolute necessity to national security of a merchant marine built, owned and manned by its own citizens. Two fundamental national interests are served by cabotage laws: first, the necessity of having a merchant marine of the best-equipped and most suitable types of vessels owned and operated by U.S. citizens sufficient to carry the greater portion of its foreign and domestic commerce; and second, the necessity of having a strong merchant fleet, both domestic and international, to serve as an adjunct to national security forces.

The declaration of these purposes was made in the Merchant Marine Act of 1920. The principle of cabotage as we know it today is set forth in Section 27 of that Act. commonly referred to as the Jones Act, which provides:

No merchandise shall be transported by water or by land and water, on penalty of forfeiture thereof, between points in the United States, including Districts, Territories, and possessions thereof embraced within the coastwise laws either directly or via a foreign port, or any part of the transportation, in any other vessel than a vessel built in and documented under the laws of the United States and owned by persons who are citizens of the United States.

The Congressional aim in mandating this section of the Act remains compelling today: to ensure American goods lies in American hands for the sake of our national security, and our general welfare.

Due to the recent worldwide recession, however, resulting in hundreds of idle tankers, bulk carriers and dry cargo ships around the world, there has been a great deal of interest on the part of various foreign-owned companies to enter the lucrative U.S. market. And, in addition, there is some interest on the part of various American factions to allow foreign operators into the domestic trade. It is argued that the short-term benefits of such a change in policy might be able to stimulate certain segments of the shipping industry here. But, the long-term damage that would occur by such weakening of the Jones Act principle would far outweigh the small value received now.

Perhaps the most highly publicized initiative in that direction is the Cunard bill, introduced in the last two Congresses, which would permit foreign-built vessels to enter the domestic passenger trade. Proponents of the bill argue that the U.S. maritime industry does not now offer and is not capable of offering U.S. cruiseship passenger service. Contrary to this claim, however, two shipping companies . . . Contessa Cruise Lines of Houston and American Flagships of New York . . . are making plans to build in U.S. shipyards large passenger vessels for the coastwise domestic cruise trade, rendering Cunard's argument invalid.

Another breach of the Jones Act is being proposed by Canadian Steamship Lines (CSL), which wants to top off colliers in Delaware Bay and other locations with foreign-built, self-unloading ships. tional custom. The principle of ca- that control of the shipment of Under the Jones Act, only vessels

that are built in the U.S. can move merchandise from one point or port in the U.S. to another, or to a vessel anchored in U.S. waters. Waivers for the Jones Act may be granted only on grounds of national security. CSL's first claim was that its topping-off services are important to U.S. security. and its second was that American coal destined ultimately for Europe and Japan cannot be regarded as U.S. domestic trade. Even a cursory look at the Jones Act reveals that both these points are not valid grounds for exception. However, along the same lines as Cunard, CSL argues that U.S. shipping companies cannot offer topping-off service, and in the event they could, would not be able to do so as economically as CSL. At least two American shipping companies are currently on their way to providing topping-off services: American Steamship in Buffalo, N.Y., and Energy Terminals in New York. That the American companies may not be able to do so as cheaply as the Canadian line is debatable at this time. However, it is not the economics, but the principle of cabotage that is being threatened here.

An Administration proposal would allow U.S. subsidy-built tankers to trade coastwise upon subsidy refund. While this is not a direct threat to the Jones Act, it flies in the face of Congressional intent as mandated in the Merchant Marine Act of 1936, which set up subsidy programs for U.S.built ships in the foreign trade. The 1936 Act recognizes the economic handicap under which U.S. ship construction operated in competition with foreign construction. It offered subsidies only to U.S.-

(continued on page 8)

# WorkBoats



# QuickBoat

MonArk Patrol boats are built to deliver speed without sacrificing durability. We can build the boat to get you there faster, safer and more economically.



# LoadBoat

At MonArk, we build boats and barges to fit any operation or certification requirement. We can build one to carry your load faster and more efficiently.



# **BusBoat**

Once your crew is on the boat, their time translates into money. MonArk builds crewboats that get them to the job quicker and more economically



# ToughBoat

MonArk boats are engineered and manufactured to perform under the harshest conditions, day in and day out. A MonArk boat puts a lot of protection between you and rough water.

MonArk makes boats that fill just about any job description you can think of Aluminum hull construction makes MonArk boats faster, tougher and more economical. We've been building tough workboats of all kinds for clients around the world for over twenty years. We've proven that a MonArk boat will provide durability through the years and a better price at resale time.

MonArk offers the industry's largest selection of stock designs, and we can custom design and build to meet your specifications, no matter what the demands of the job. Call us. We'd like to tell you more.

# MonArk

MonArk Boat Company
PO Box 210, Monticello, Arkansas 71655
501 367-5361 Telex 783028

WorkBoats.		HI K	
			MR
Name			
Address			
City	State	Zip	, , , , , , , , , , , , , , , , , , ,

See us at the Workboat Show, Booth #1353

(continued from page 6)

built ships operating in international trade, allowing those ships to compete on an equal basis with the foreign shipping trade. Domestic trade ships were guaranteed no such subsidies on the basis that domestic trade ships already enjoyed fair and thriving competition among themselves. Clearly, to allow subsidy-built ships into the domestic trade would give those subsidy-built ships an unfair competitive edge, one which was not intended by the Act of 1936, and which would disrupt the current

environment of fair competition in the Jones Act fleet.

Also under consideration by the Administration is a proposal to export Alaskan oil to Japan in return for Japan's allotment of Mideastern oil. Since the shipment of this oil would be considered foreign trade, it would no longer be

under the purview of the Jones Act, and would pave the way for foreign shippers to bid for the business. This of course, is perhaps secondary in importance to the fact that when domestic oil is available readily, it seems capricious to renew our dependence upon foreign oil sources.

Two other bills are currently in the Congressional works as well. One, the Frenzel bill, proposes to repeal the Jones Act altogether. Another would exempt Puerto Rico from cabotage restrictions on pas-

senger vessels.

But perhaps the most threatening assault of all on the Jones Act, in what seems like guerilla warfare, is Warren G. Leback's publication of a paper for presentation at the 1983 Annual Meeting of the Society of Naval Architect, which proposed that foreign-built, but U.S.-owned and registered vessels be allowed to carry cargo in the domestic coastwise trade. Mr. Leback is the Deputy Administrator for Maritime Transportation at the Department of Transportation. Although the Maritime Administration has stated that Mr. Leback's position does not reflect MarAd's views, this opinion coming as it does from the number two man who is charged with promoting our maritime industry is worrisome indeed.

What do all these threats on the Jones Act mean to the barge and towing industry? As long as they remain just threats, they mean relatively little. But any one of the initiatives, if put into being, would not merely alter the course of long-standing maritime policy, but would destroy forever any notion of the U.S. maintaining a competitive position in domestic or world ocean trade. The Jones Act is an essential piece of legislation which both protects and supports our nation's domestic transportation structure. U.S. coastal and inland vessels employ about 150,000 people. Shipbuilding, terminal operations and other allied industries sustain thousands of additional

If foreign-flag operators are allowed to participate in U.S. domestic waterborne commerce, American-flag vessels will ultimately be driven out of our own trade. The result would be an unparalleled vulnerability to the political and economic pressure of foreign powers controlling the domestic commerce of the United States. America has a heavy investment in and a dependence upon its merchant marine. We cannot afford to hand over the return on that investment to foreign corporations when by doing so would sacrifice our ability both to defend our country and to maintain our standard of living.



# We provide professional shipyard services

Todd Shipyards Corporation has been building and repairing ships since 1916 with expertise and guality second to none. Our five, well equipped, shipyards still offer a variety of services from minor voyage repairs to large conversion jobs.

We can provide the expertise and resources to respond effectively and economically to the needs of shipowners and operators with dependable around-the-clock service.


Our complete and upgraded facilities located in Galveston, New Orleans, San Francisco, Los Angeles and Seattle, enable us to perform any service, if it be a routine drydocking, diesel, propeller and tailshaft repairs, or even a major overhaul, with fast turn-around.

In short, we are shippard professionals in every sense of the word. If you want a professional job done - call on TODD.



# **Todd Shipyards Corporation**

One State Street Plaza, New York, New York 10004
Telephone: (212) 668-4700 Cable "Robin" New York Telex: WUI 620100
NEW ORLEANS/GALVESTON/LOS ANGELES/SAN FRANCISCO/SEATTLE



# Platform bodyguards.

# Our aluminum anodes offer predictable offshore performance.

Controlled rate of corrosion, a Kaiser Chemicals technological breakthrough, enables designers to predict performance and life of aluminum marine anodes KA90 and KA95 with a high degree of success.

Why two alloys? To give you a choice. KA90, Al-Zn-Sn type (without mercury) is tested to have an average current output of 1176 amphours/pound. Voltages range from 1.07v to 1.15v. Or KA95, Al-Zn-Hg type (with mercury), tested to have an average current output of 1285 amphours/pound and a voltage of over 1.05v.

Both KA90 and KA95 aluminum marine

anodes are available in sizes up to 1,100 pounds from a 10,000,000-pound/year manufacturing facility designed exclusively for anode production. And every heat must qualify for acceptance by going through our Q-7 seven-point quality-control

program.

Get our 20-page brochure which includes an anode-selection nomograph and other important design data. Write Kaiser Chemicals, 300 Lakeside Drive, Oakland, CA 94643, Room 1128 KB. Or call (415) 271-5580.



KAISER CHEMICALS

Circle 105 on Reader Service Card

# **Modern Fuel Systems Symposium**

# Exchanges Of Experiences—Problems And Solutions—Prove Use Of Heavy Fuels In Medium-Speed Diesel Engines Is Increasing And Economical

Two years ago Alfa-Laval, Inc. of Fort Lee, N.J. sponsored a symposium on modern fuel systems. This symposium was so successful that a second symposium on the same subject was held recently in St. Louis, Mo. This year's symposium was sponsored by both Alfa-Laval and *Diesel Progress*. It brought together engine builders, oil companies, shipyards, vessel owners and manufacturers of fueltreatment additives.

The program was oriented to the needs of inland and coastal waterways operators. The topics covered included basic fuel chemistry, fuel purification, additives, fuel blending, heavy-fuel burning, engine design and operating experience.

The following excerpts from the papers presented (in order of pre-

sentation) indicate the wide range of thoughts presented, including present and future problems with suggested solutions:

Cletus H. Jones, Belcher Oil Company of Miami Fla., presented comments on "The Quality and Availability of Blended Marine Fuels in 1983." He stated that his definition of quality is "if the product does the job it was intended to do, that's quality. It may not smell good or look good—the laboratory analysis may indicate major deficiencies, but if it passes the performance test in the engine, it is a quality product."

He went on to state: purchasing blended marine fuels has an element of art to it. First of all, insisting on the lowest possible price at all times assures you of one thing—if there is a problem fuel in the market place, you will get your share of the headaches. calls on blended-fuel quality and availability. Unlike No. 2 diesel, the specifications for blended fuels


Another simple rule is to avoid confusing a fuel-supply specification with an engine specification. The fuel coming over the rail, in most instances, is not the fuel injected into the combustion chamber. One is a treated fuel, the other is not. I realize this is basic stuff, but it amazes me how often sophisticated operators buy an expensive grade of blended fuel because, I suspect, they either don't know or don't trust their onboard treatment procedures.

In summary, the current highspeed diesel operator contemplating installation of medium-speed residual-burning diesel engines will have to make some judgement calls on blended-fuel quality and availability. Unlike No. 2 diesel, the specifications for blended fuels are vague and there is a lot of information missing. Progress on testing and the exchange of information is improving, but we still have a way to go.

Alternately, there are operators worldwide successfully using this type of equipment despite the aforementioned shortcomings. Practically speaking, medium-speed engines are in general use everywhere except the U.S. inland waterways.

Finally, let us keep in mind that the diesel engine originally was conceived to run using pulverized coal as fuel. It is a wonderfully adaptive and forgiving piece of equipment. Certainly in today's

(continued on page 12)



# The Choice is Markey

Wilmington Transportation co.'s newest tug the 95' "PHILIP W." joins the fleet in handling many ships in these harbors. Once again Wilmington selects Markey deck machinery to give the tug the capability of working her chores more efficiently. Her Hydraulic stern Capstan and Gypsy Bitt Windlass are "MARKEY." How about yours?



# MAIN IRON WORKS, INC.

SERVING TUGS, PUSHERS, TOWBOATS, CREWBOATS, SUPPLY BOATS, INLAND & OFFSHORE BARGES



3500 Ton Dock 200' x 100' 90' Between Wing Walls 1500 Ton Dock 160' x 80' 70' Between Wing Walls

#### HISTORY

Founded in 1948. Main Iron Works. Inc.'s current facilities are available for construction of new vessels ranging in size from 45' to 250 in length. Dry docking and a full range of repair services are also available, including a complete machine shop facility, sandblasting and painting services.

With over thirty years experience and our record of service to the towing industry, Main Iron Works, Inc. is ready to serve the needs of our past, present and future clients.

# GENERAL SERVICES

Air control mechanics
Electrical repairs, trouble shooting
Hydraulic mechanics
Piping and plumbing repairs
Sandblasting and Painting
Complete machine shop service
A.B.S. approved for stainless steel
Cladding on main shafts
Complete wood working shop

# Four Dry Docks:

Houma, Louisiana 70361

300-Ton Capacity 850-Ton Capacity 1500-Ton Capacity 3500-Ton Capacity completed 1st qtr. 84 850 Ton Dock 60' x 150' 50' Between Wing Walls 300 Ton Dock 50' x 80' 40' Between Wing Walls

#### Machine Shop:

Lathes: Capacity in feet — 36 Feet Swing in inches — 30 Inches

# Wet Slips:

Three slips available for your boats or barges to tie up while repairs or supplies are being completed

#### Shaft Storage Rack:

To avoid costly delay in waiting for transport of shafts, we provide our customers storage for their spare main shafts and rubber shafts.

#### Inventory:

Along with our parts inventory, we keep a stock of steel plates, pipe, angles, flat bars, and channels, all American Bureau of Shipping approved.

We also have a supply of forgings and bar castings which enable us to supply your needs efficiently.

# Crane Service:

100 Ton Fixed Stiffleg for Offloading and Loading Supplies

All of the services listed above are available on a 24-hour basis, seven days a week. Quotation and price schedules are available upon request.

Located at 50 Mile Marker
on Intracoastal Waterway
P.O. Box 1918



CONTACT:
LeRoy Molaison • Henry Brunet
Otto Hughes • Wayne Piazza
(504) 876-6302 • (504) 525-4020

# Built to Serve World Trade

Moran leads the way in New York harbor with powerful and efficient tugs, and a century of experience.

Moran Towing & Transportation Co., Inc.

"The Best in the Business"

One World Trade Center • Suite 5335 • New York, New York 10048

(continued from page 10) technological environment it will work in the heartland of the United States.

Nicholas H. Chavasse, Alfa-Laval, Inc., presented "The Alfa-Laval Line-Up Past and Present." He stated that the Alfa-Laval MAB-103 and MAB-104 are small, manually cleaned centrifuges used today for turbine lube oil and for lube and diesel fuel on small diesel engines. Benefits of the 100 series is that they are inexpensive, easy to install, simple to run, and the controls are simple. The drawbacks to the MAB-100 Series are that they have limited or small capacities and that their sludgeholding capacity is rather limited.

The Alfa-Laval MAB-200 Series of purifiers are similar to the 100 Series but with the following major differences. There are five units available. They are larger both in size and capacity. They have removable sludge liners and selfdraining bowls. They have paring disc pumps built into the bowl for pressurized discharge of the light

(oil) phase and all of these give the and lube oil application if sized following benefits: Longer runs between cleaning, easier to clean. and on the larger units (MAB-205 and up) built-on bowl cranes for lifting the bowl top and stack out of the unit and to the side. The benefit of the paring disc pump on the light phase is that back pressure can be applied to the oil outlet if required. The drawbacks to the MAB-200s are that they are more expensive, larger, heavier, still labor intensive if applied to a dirty product and limited in their application to diesel fuel, small engine diesel lube oil, turbine lube oil, hydraulics and other similar applications.

The next step in the Alfa-Laval line of marine purifiers (by-passing the nozzle machines) is the MAPX or MOPX line of self-cleaning purifiers. There are six sizes in the family ranging from the small 204 to the large 313 size unit. The MAPX/MOPX units solve the problems that exist with the MAB Series of units. They can handle just about any type of marine fuel

and installed properly and are a tried and proven piece of equipment.

The Alfa-Laval WHPX Series of purifiers, introduced in 1972-73, does not lose any oil in the shoot, requires no pressurized water or hot water, generates less sludge volume and requires less water. It has become the industry standard, and although more expensive than the conventional unit, has a payback in normally less than two

Last is the ALCAP FOPX Series of fuel oil purifiers. The FOPX is neither a purifier nor a clarifier but a combination of both is the best way to describe it. The FOPX was developed to solve the problem with the upper limits presently imposed on purifiers, to get rid of the problems presently associated with the gravity rings, to make the centrifuge less sensitive to temperature control, and primarily to give the marine industry a piece of equipment that the operators could feel a little bit happier with.

Nels J. Hendrickson, Drew Chemical Corporation, spoke on "The Role of Chemicals and Fuel Analysis in the Marine Industry.' He introduced his subject by stating that "Even though the price, quality and availability of marine fuels have not deteriorated as rapidly as forecasted, there still can be compelling economic reasons for vessel operators to consider burning heavy marine fuels. However, a hasty switch to a lowercost fuel without full consideration for the consequences of the switch to lower-quality fuels on equipment and the need for greater personnel attention and control can have quite the opposite desired cost outcome.'

The use of fuel additives has taken longer to be accepted than the use of chemicals in other systems and is an area of continued misunderstanding and controversy. Part of the problem is caused by the large number of additive manufacturers as well as by the lack of proper understanding by operators of the types of additives available and their role. Fuel additives have, however, been used successfully to solve many problems. Additives have been used in lube oils, as pour point depressants, ash modifiers and demulsifiers, as well as for many other applications. Drew AMEROID<sup>R</sup> Marine's products and services have also expanded and changed from one or two relatively simple products to our extensive present line. These products are being used worldwide on over 4,000 vessels.

It is our opinion that diesel engines can effectively burn today's fuels and those expected in the near future. This is especially important for operators who are considering burning blended fuels with engines capable of doing so. However, the operator, in order to realize the full cost benefit, must

take advantage of the treatment tools available (i.e., fuel analysis, mechanical and chemical treatment).

Ole Schnohr, MAN, B&W, Alpha Propulsion Systems, spoke on Engines on the River."

Basically, the quality of heavy fuel has not really changed since fuels entered the marine market. Any fuel considered of poor quality today for reasons of high viscosity, high Conradson Carbon content or high content of catalytic fines, etc., could be produced and was actually produced and found on the market in the early days of heavy fuel operation.

In recent years comprehensive test programs have been initiated by the engine industry in order to meet the challenge presented by an overall declining average fuel quality. The systematic accumulation of service results from those ships in service which, according to experience, would be more frequent users of such marginal fuel qualities also has been intensified.

The conclusion to be drawn from the combustion research carried out on full scale engines was the encouraging fact that all these socalled extreme fuel qualities, including coal derivatives, were fully usable in our diesel engines, as has been the case with the traditional heavy fuels in the past.

We are fully aware of the somewhat different modes of operation involved in river boat traffic versus oceangoing operation. The main difference is strongly related to manning requirements and the maintenance pattern.


With the rivers being the "freeways" for bulk cargo in this country the river tugs are operated as trucks on the road. As illustrated the complete propulsion package with its integrated control system allows such running of the engines "from the front seat", i.e., the bridge pilothouse.

The analogy to road transportation is expressing with strength that it is a natural requirement of the operator that maintenance is as fully predictable as when a truck needs service and fuel, but of course with much longer intervals.

With the stability in performance which is outlined and proven by our service experience, we can meet such requirements, meaning that unskilled personnel can operate the engines and actual service be left to shore gangs at "service stations.

Hugo Fiedler of MaK presented a paper entitled "Heavy Fuel Operation with MaK Diesel Engines for Multipurpose Application and Marine Propulsion.

The MaK diesel engine program consists of five engine lines with an overall range from 740 to 9,000 kw. Basically the engines are designed and built for marine applications, main propulsion and auxiliary service, as well as stationary application. Accordingly, economy, which means reliability, low fuel









High-performance products and worldwide service from factory-trained and certified chocking specialists. Chockfast Orange \* has earned a reputation for reliability ■ more than 15,000 main propulsion systems, plus ■ generators and auxiliary equipment ■ sterntube, strut, pintle, rudder and pedestal bearings ■ steering gears ■ engine-room and cargo pumps ■ anchor windlasses ■ bow thrusters ■ cable penetrations ■ stern winches.



P.O. Box 454 20 Commerce Drive. Montgomeryville. PA 18936 Telephone: (215) 855-8450 Telex 84-6342 Cable: Philres MMLL

and lube oil consumption as well as the capability of burning any kind of fuel, is the leading guideline for the design and development. Though for some engine types V-engines are available, the general tendency is to feature inline engines, especially for marine

application.

Low cylinder numbers or in-line engines mean a low number of moving parts. Though today, on account of improved materials and experience in design, a high reliability of the different parts can be achieved, there is no doubt that the all over reliability is directly related to the number of parts involved and bear a direct relation to maintenance and overhaul requirements.

The general trend for reduction of fuel consumption initiated by the increasing price of fuels has resulted in an extensive development work in this direction. Today MaK engines are of the highest efficiency and in particular cases leading in this field, achieving up

to 50 percent efficiency.

For more than 15 years the burning of heavy fuels in mediumspeed four-stroke engines has been developed with increasing success. Today even the highest viscosities can be burned without difficulties, not only at full but also at part load. Wear rates of parts exposed to combustion are in many cases even lower than experienced with older engines running on gas oil

Alan C. Barich and Edwin E. Hodges of Transamerica DeLaval presented a paper on "Exhaust Emission Control Techniques of Today's Large-Bore Medium-Speed Diesel Engines for Heavy-Fuel

Operation.

Although currently in the embryonic stage for marine application, exhaust emissions are in the process of being regulated for ship operation in our inland waterways, Great Lakes and major U.S. ports. Control of diesel exhaust emissions will include changes to the basic operation of the diesel engine through such means as to retard fuel injection timing, charge air manifold temperatures and use of exhaust gas recirculation.

The work discussed in this report revealed substantial results. Injection timing and intake air manifold cooling show clear reductions in NOx emissions, but the extent of the reductions is limited. Moreover, substantial fuel penalties associated with these techniques were demonstrated. Of the combustion control techniques tried, exhaust gas recirculation was the most effective in achieving significant NOx reductions with minimum fuel-consumption penalty. However, the hidden costs associated with this method are a major concern at this time. Further development work is needed to improve the EGR system and thus reduce fouling and related gas-handling problems. The effect of EGR on lube oil contamination also needs additional investigation.

Ammonia-injection catalytic reduction appears to work well in reducing NOx, but again needs further attention. It has not yet achieved expected percentage reductions, and additional work directed toward the control system and related hardware is necessary.

Based on results of the experimental program to date, it is apparent that both catalytic reduction and EGR are deserving of

and ultimately on engine wear further attention. No mechanical experiments with engine redesign are possible until completion of the present experimental program, but research can be directed at resolving the problems associated with EGR.

Until such a time as more work can be done, it is up to the engine manufacturer and owner alike to help reduce NOx by carefully and precisely sizing auxiliary equipment that will help reduce engine emissions.

C. E. Rosgren, design manager for Wartsila Diesel, spoke on "Reliable Heavy-Fuel Engine Component Designs." This paper deals with the design aspects of some critical components in heavy-fuelburning diesel engines. The theoretical considerations are described as well as the practical outcome of applied engine tests and field experience.

The heavy fuel experiences referred to were gained during the (continued on page 14)



ROLLING vs. SKIDDI

Circle 110 on Reader Service Card

**Marine Products Division** 

Absorption Core



(continued from page 13)

last five years and, consequently, on fuels refined by the latest secondary processes, which means cracking of different kinds. Such fuels have combustion properties which substantially differ from the heavy fuels available 10 years ago.

The evaluations are based on experiences of the purpose designed heavy fuel engines Vasa 32 and Vasa 22HF in a lot of different installation types such as main engines in ro-ro vessels, supply vessels, tugs, icebreakers, ferries and small tankers as well as a number of auxiliary engine applications.

The Vasa 32 engine was introduced in 1977 and has since then attracted much attention. At that time it was one of the first new engine designs developed after the 1973–74 oil crisis. It filled a gap between the heavy fuel burning 15.75-inch bore engines and small marine diesel engines. The Vasa 32 covers an output range of 2,010 to 9,180 bhp.

The Vasa 22HF engine, with the same basic features as the Vasa 32, was introduced in 1980. With the output range of 720 to 3,480 bhp it extends the range of Vasa 32 downwards. In the upper end of the output range it is, with its smaller size and higher speed, an attractive alternative in small vessels.

Practically, it can be said that the Vasa engines are well suited for all heavy fuels existing on the market today. They also form a stable base from which the development towards using further deteriorating future fuels can be continued.

A paper describing the Waukesha AT25 Series of diesel and

heavy fuel engines was presented during the second day of the symposium. The Waukesha AT25 Engine Series consists of a family of four engine models including six and eight-cylinder in-line, and 12 16-cylinder vee configurations. The engines have a common 250-mm bore with a 300-mm stroke and were designed and developed by Sulzer Brothers Limited of Winterthur, Switzerland. The Waukesha Engine Division of Dresser Industries Inc., is manufacturing and further developing this new engine family at Waukesha, Wis., under a license agreement with Sulzer for marketing throughout the world.

The engine series has been designed for both diesel and heavyfuel operation and covers a speed range of 720 to 1,000 rpm. The diesel (distillate) fuel maximum continuous power range covers 1,260 to 4,800 bhp, whereas the heavy-fuel (residual) rated power range covers 1,140 to 4,320 bhp.

This new AT 25 engine series combines the four-stroke diesel cycle with direct injection, turbocharging and intercooling. The design results in a high-density reciprocating power producing package including low fuel-oil and lube-oil consumption, high reliability and durability, and multifuel capability for cost effective operation. The first engine of this new series produced at Waukesha was a 12-cylinder model.

Over 3,000 engines of the A25 type have been applied by Sulzer and its licensees in universal applications including main marine propulsions (deep sea and inland waterways), ship auxiliary power generation, offshore oil-drilling platforms, railroad traction and stationary power generation.

R. Peter Spock, American

Commercial Barge Line Co., described "The ACBL Blended Fuel Program."

ACBL decided to pursue blended fuels after a lengthy discussion and study of the current technologies. Several other conservation methods were put into effect, but blended fuel was to be the major effort because it showed evidence of providing the greatest amount of savings potential. At that time, about 40 percent of ACBL's line haul towboats were equipped with Alco engines, which had undergone previous blended-fuel testing. Also in 1980, our future new vessel construction called for several vessels to be equipped with Alco engines. Thus in light of the pricing structure of diesel and blended fuels, it was determined that significant fuel cost savings could be obtained in these vessels.

Another factor which influenced the decision was that ACBL had previously purchased a tank farm in Memphis as a hedge against any future oil shortages. This would prove advantageous since the quality of blended fuels must be controlled in order to provide successful operation in diesel engines.

Over the long term, it is expected that diesel fuel prices will increase much more than residual. This is the most significant reason why blended fuel is a rational approach to controlling operating costs. This must obviously be tempered by the increased maintenance costs associated with blended fuel.

The author then described in detail the impact of these changes and how ACBL arrived at its current position. Finally, the paper takes a look at the most recent ACBL heavy-fuel project which involves the re-engining of the tri-

ple-screw towboat M/V Bill Elmer with three MaK engines equipped to burn 3,500-ssu fuel.

Kenneth Siegman of the Midland-Ross Company reported on "Midland's Heavy Fuel Oil Experience." He advised that in late 1981 Midland made the decision to build two boats capable of burning heavy fuel oils of varying viscosity and varying quality. This decision was based on many factors both within the Midland organization and external to the company. The external factors were many, but were primarily concerned with the present and future cost and supply of fuels.

In November 1982, Midland took delivery of the M/V Jim Ludwig from St. Louis Ship. In May 1983, Midland took delivery of the M/V Justin T. Rogers. Both of these boats came out of the yard burning an IF-80 (600-SRI) fuel and have continued to burn this blend. This paper covers Midland's experiences during design and construction, plus much of their operating experience to date. Much of the operating data is very recent. Each day a new or unexpected bit of information is learned and they expect the learning experience to continue.


Along with the decision to go to heavier blends of up to 2,100 SRI, there were questions raised on storage tank configuration. The original hull design had two large port/starboard tanks on each side. This was later changed to divide each of the large tanks in half to give four port/starboard tanks, each side. More but smaller capacity tanks were required for two reasons. The first and prime reason was the concern of possible fuel compatibility problems. The various bunkers if purchased from different suppliers could be kept separate.

An important part of the boat design once the hull configuration was chosen, was the choice of the main engines. After an extensive search and evaluation, it was decided to go with main engines designed and built by B&W Alpha of Frederikshaven, Denmark.

Much of the data and experience contained in this paper is based on the operating experience of the two boats. From what is known now, Midland feels that they can expect to meet or exceed their expectations of the move to burn heavy fuels.

M.H. Brinker, M.A. Cereno and W.H. Rice, Jr., Heartland Transportation Company, The Inland Waterways Division, Pott Industries Inc., described "The Inland Waterways Division, Pott Industries Inc. Blended Fuel Program."

The blended-fuel program of IWD began back in the mid 1950s when Federal Barge Line began operating four towboats on blended/heavy fuel oil. Federal Barge lines operated these four boats on heavy oil from 1956 through 1965 for two boats and 1972 for the other two



when, due to the expense of burning heavy oil versus diesel oil, the boats were converted back to diesel oil service and the heavy-oil equipment was removed.

Many lessons were learned from these years of operating on blended fuel oil and these lessons were thoroughly studied and considered when the Inland Waterways Division decided to build the M/V Robert A. Kyle and make it capable of burning blended fuels.

The M/V Robert A. Kyle had operated for approximately 950 hours on blended fuel when the decision was made to replace the power packs in the center engine. Since the first phase of the test was to be a shakedown of the fuel handling and delivery equipment, the power packs were not renewed prior to using heavy fuel even though EMD recommends chrome cylinder liners when using high-sulfur fuel. The performance of the cast-iron liners during the shakedown phase proved to be quite promising so that we and EMD decided to test both cast-iron and chrome liners in the wear evaluation phase of the test which is currently underway. Through the cooperation of EMD and the oil companies, the engines were thoroughly inspected and borescope photographs of the cylinder walls, exhaust valves and turbo screen were taken to record their condition before heavy fuel was introduced to the engine. There were no unexpected consequences attributable to the use of heavy fuel during the shakedown phase of the test. The Kyle has experienced no failures on the center engine due to blended fuel oil.

For further information and copies of the above presentations, circle the appropriate number on the Reader Service Card in the back of this issue.

Belcher Oil Company (Quality and Availability of Blended Marine Fuels in 1983)—Circle 51; Alfa Laval, Inc. ("The Alfa Laval Line-Up Past And Present")—Circle 52; Drew Chemical Company ("The Role Of Chemicals and Fuel Analysis in the Marine Industry")—Circle 53; MAN/B&W, Propulsion Alpha Systems ("Engines on the River")—Circle 54; MaK ("Heavy Fuel Operation with MaK Diesel Engines for Multipurpose Application and Marine Propulsion")—Circle 55; Transa-merica Delaval (Exhaust Emission Control Techniques of Today's Large-Bore Medium-Speed Diesel Engines for Heavy Fuel Operation")—Circle 56; Warstila Diesel (Reliable Heavy-Fuel Engine Component Designs")—Circle 57; Waukesha Engine (The Waukesha AT25 Series Diesel)—Circle 58; ACBL (The ACBL Blended Fuel Program")—Circle 59; Midland Ross ("Midland's Heavy Fuel Experience")—Circle Heartland Transportation ("The Inland Waterways Division Pott Industries Inc. Blended Fuel Program')—Circle 61.

Circle 113 on Reader Service Card ▶



# **CRUISES BEYOND EXPECTATION!**

Reach beyond your vacation expectations with a value-packed cruise from Exploration Cruise Lines®

or an extraordinary experience. take an extraordinary ship. Our Explorer Class® ships are in a class by themselves. They're small enough to cruise in close to the really interesting attractions — visiting deserted lagoons, primitive jungles, glaciers, and wildlife — even making bow landings so you can explore pristine beaches and uninhabited islands.

And, they're big enough to give you the solid comfort we know you wantspacious staterooms, comfortable cocktail lounge, picture - windowed dining room, expansive sundecks.

Enjoy hearty, exquisitely prepared meals. Be spoiled by a crew whose attentiveness and enthusiasm go beyond service. See places and do things only a few get a chance to experience. The friends, memories, excitement, and good cheer make your Explorer Class® cruise unforgettable.

Cruise the waters of TAHITI—the romantic jewel of the South Pacific. Experience the French Polynesian Islands, an incomparable vacation destination, or stopover enroute to or from Australia/New Zealand. Explore aquamarine lagoons, discover colorful villages on fascinating shore excursions, beachcomb, sun, swim, snorkel and enjoy cookouts on secluded beaches of uninhabited islands.

Discover PANAMA. TRANSIT the CANAL with the lowest cost fully deluxe Panama cruise. See Colonial Panama, Spanish Main Gold Ports, and primitive Indian cultures in the Darien Jungle and on the San Blas Islands. No other cruise offers so much of

exotic, colorful Panama Explore the colorful his-

tory, cultures and unforgettable scenery of ALASKA, with our unique Inside Passage itinerary. Visit more ports and view all of the National Parks and Monuments in Southeast Alaska.

PANAMA

ALASKA

Follow the historic Lewis and Clark route on the COLUMBIA & SNAKE RIVERS—Great Rivers of the West.


Retrace historic sternwheeler routes cruising the Sacramento and San Joaquin Rivers of the famous CALIFORNIA DELTA.

Reserve now for our Fall / Winter Tahiti and Panama Cruises, and start planning for our other spectacular Spring and Summer cruise offerings. See any travel agent or ask us.

YES, send me full color brochures on: ☐ ALASKA & INSIDE PASSAGE ☐ COLUMBIA & SNAKE RIVERS ☐ CALIFORNIA DELTA □ TAHIT! ☐ PANAMA & THE CANAL NAME ADDRESS MAIL TO: EXPLORATION CRUISE LINES 1500 Metropolitan Park Bidg., Dept. BYK, Seattle, WA 98101. Or CALL TOLL-FREE 1-800-426-0600 for brochures or information (in Seattle Call 624-8551).

# **ERFORMANCE** BEYOND COMPARE!

Unique vessels like the Explorer Class® ships require the kind of performance only Deutz can deliver. That's why Exploration Cruise Lines® specifies Deutz.



e are proud to have supplied the main engines for the entire Exploration Cruise Lines fleet. Fuel efficiency, low weight per horsepower and a two

year warranty, plus the performance and reliability of the Deutz engines in their first vessel (15,000 hours of uninterrupted service!) convinced Exploration Cruise Lines to select twin Deutz SBA12M 816 engines for installation in each of their latest vessels.


Your Deutz representative has all the details on our superior diesel technology. So call or write today.



USA:

Deutz Corporation, 7585 Ponce de Leon Circle, Atlanta, GA 30340 (404) 449-6140 · Telex 70-7407 Attn: Mr. Reinhart Kuntz

Deutz Corporation, 7809 Airline Hwy., Ste. 200, Metairie, LA 70003 (504) 737-6221 KHD Canada Inc., 180 Rue de Normandie, Boucherville, Quebec J4B 5S7 (514) 641-2680 · Telex: 05-268544 CANADA: MECICO: Peter Haring, Manuel M. Contreras 133 Of. 401, 06500 Mexico D.F. (905) 566-9411 or 546-5234 · Telex: 22-1773354





The M/V VALIANT, a deep-notch tug operating with the barge BULKFLEET PENNSYLVANIA, is powered by two Krupp MaK 6MU 551 AK 6-cylinder heavy fuel engines.

"When we designed the tug M/V. VALIANT, and her sistership M/V. VICTORY as deepnotch vessels to work in combination with the barges BULKFLEET PENNSYLVANIA and BULKFLEET TEXAS, we took a close look at the fuel situation for the future," says Barry Snyder, President of Bulkfleet Marine.

"It didn't take a crystal ball to see that No. 2 diesel was going to get more expensive, and tougher to find, in the not so distant future. That's why we specified heavy-fuel engines.

"Each tug is powered by two Krupp MaK 6MU 551 AK 6-cylinder engines, rated at 4,000 BHP at 420 RPM," he continues. We mix 15% No. 2 diesel with 85% bunker C to yield fuel of 1500 seconds Redwood 1 at 100°F, or 180 centistokes at 122°F.

"The MaK 551 engines are designed to be able to operate with a maximum fuel viscosity of 380 cSt, sulfur up to 4.3%, vanadium up to 400 ppm, alumina/silica up to 30 ppm



At the 10,000 hour inspection the cylinders showed virtually zero wear, the rings were clean and free. Lubrication in these engines is provided by Gulf Marine engine oils.

Bearing wear was minimal. Inspection of four main bearings showed them in excellent condition.

and sodium
up to 40 ppm. All
that's basically an
involved way of saying
these engines can save us
a lot of money on fuel."

James R. Colman, Bulk-fleet's Engineering head supervised the recent engine inspection and says, "The secret to burning this low grade fuel is the right oil to protect the engines. You don't save any money if you're eating up engines. We get the protection we need from Gulf Marine engine oil. The results of our 10,000 hour inspection of the VALIANT'S engines prove it.

Between the two engines, we looked into eight cylinder heads and piston assemblies. The piston skirts were clean and smooth with zero wear. Cylinder liner wear was measured at 'nil' except for two liners which indicated onetenth of a millimeter wear, well within acceptable boundaries. The piston rings were clean and free; maximum ring wear was two-tenths of a millimeter. We opened four main bearings and found them in excellent condition. That's a remarkable inspection for engines running this kind of fuel, and I think it's directly

> attributable to the Gulf lubricant."

"In fact,"
Colman concludes, "Gulf
provides a complete range of
lubricants for
these vessels.
And we get protection from
every product,
that makes for
efficient operation. I'm con-

vinced, these heavy fuel engines are the way to save money in bulk transport, and Gulf lubricants are the way to save these engines."

Ask your Gulf pro how Gulftow oils and other Gulf lubricants can help protect your investment. Or write, Gulf Oil Corporation, P.O. Box 1563, Houston, Texas 77251.



Everything we do makes business better for you.



Justin T. Rogers

# **OUTSTANDING** OFFSHORE/SHALLOW-DRAFT **VESSELS OF 1983**

# **ACTINIA** Hitachi Zosen

A portfolio of the most important offshore and shallow draft vessels constructed during 1983 . . . selected because of unusual and superior characteristics of design, purpose or performance.

The semi-submersible offshore drilling rig Actinia was delivered in 1983 to Actinia Shipping Corporation by the Ariake yard of Hitachi Zosen. The rig is Hitachi's SS-4000 type, based on an original design of Friede and Goldman of New Orleans. The unit is 270 feet long, 200 feet wide, 116 feet high, and has a variable deck load of 3,200 metric tons.

The Actinia is capable of oper-

high and winds of up to 100 knots. An 8-point mooring system keeps the rig in position during drilling; four thrusters provide back-up during adverse weather conditions. The rig complies fully with the rules and regulations for operation in the U.K. sector of the

# **AIR RIDE EXPRESS** Atlantic & Gulf **Boat Building**

Built under subcontract from ating in water up to 1,500 feet Air Ride Marine, Inc. of Miami by deep and of drilling to a maximum Atlantic & Gulf Boat Building, depth of 25,000 feet. It is designed Inc. of Port Everglades, Fla., the to withstand waves up to 100 feet 65-foot crew/supply boat Air Ride

Express entered service in mid-1983. The new vessel, which is owned by South Florida Offshore Services, Ltd. and operated out of Mobile to the offshore oil industry by Gulf Crew Transport of Pensacola, Fla., is a surface effect ship (SES) built to the proprietary Air Ride design that features a shallow pressurized air chamber under the hull.

Unlike other SES craft, the Air Ride Express has a rigid interconnected structure and requires no flexible seals. Above the waterline it looks similar to a conventional boat. The Air Ride design, which was developed by Air Ride Marine

(continued on page 20)

# STEM TO STERN STERN

Tug, trawler, or tanker. Fill all your auxiliary power needs with Cat Engines and Generator Sets. Your best power choice for lighting, communications, winches, pumps, compressors, thrusters... Auxiliary engines from 85-1600 hp (63-1194 kW) and marine generator sets from 55-1100 kW (60 Hz) or 50-930 kW (50 Hz). All certified for on-board use by every major marine society.

When you standardize on Cat power you gain the advantages of four-stroke diesel design. Including better fuel efficiency — typically 7.5% better than two-stroke units. And with a 185 kW (60 Hz) generator set, that can keep up to \$3,000 per year in your pocket. The larger your power requirements, the more you save.

Plus Cat Engines run quieter, emit less fumes, require less maintenance and last longer between overhauls — mainly because half as many power strokes are needed to produce the same power as

two-stroke diesels.

Caterpillar is also the only manufacturer offering a complete factorywarranted marine generator set package. Each with a Cat SR 4 Generator mounted directly on the flywheel housing in permanent alignment.

Count on good service, too.
Caterpillar Engines and
Generator Sets are backed
with superior parts and
service programs available
at more than 700 ports
worldwide.

Get full details from your Caterpillar Dealer . . . he's the best source for your marine power needs.

# CAT AUXILIARIES PROVIDE THE POWER

M sterials and specifications subject to change without notice



Caterpillar, Cat, and 🖪 are Trademarks of Caterpillar Tractor C

Circle 115 on Reader Service Card

#### Air Ride Express

(continued from page 18)

president Donald E. Burg, allows surface effect technology to be utilized at lower construction and maintenance costs.


During sea trials the new vessel, which has a dry weight of 60,000 pounds, operated at 30 knots with a payload of 25,000 pounds including fuel. With a payload of 35,000 pounds, the boat ran at 27

knots. It has operated in following and cross seas up to 10 feet and in head seas of 5 feet at speeds in the 25-knot range with good passenger comfort. It has a capacity for 32 passengers and a two-man crew in air conditioned or heated accommodations. The cargo deck aft has an area of more than 400 square feet.

Key Power, Inc. of Miami supplied the engines, which include two GM Detroit Diesel 12V71TI

diesels for main propulsion and a GM Detroit Diesel 6V53T engine to power the blower system. The main engines turn 34- by 44-inch Columbian propellers through Twin Disc 514 reduction gears having a ratio of 2.5:1. Fuel consumption is about 50 gallons per hour, giving the boat a normal operating range of 750 miles.

The Air Ride Express is the culmination of a three-year research and development effort conducted



by Air Ride Marine. The Miami company is currently working on the detailed design for a 50-knot. shallow-draft patrol boat; a 110foot crew/supply vessel, and a 120passenger ferry.

# **AIR RIDE EXPRESS**

Major Suppliers				
Main engines (2)	GM Detroit			
Lift engine	GM Detroit			
Reduction gears (2)	. Twin Disc			
Propellers (2)	.Columbian			
Generators				
Generator engines	Perkins			
Engine controls	Morse			
Steering system	Hynautic			
Fuel filters	Racor			
Radar	Furuno			
Loran C	i-Tex/Koden			
SSB radio	Raytheon			
VHF radio	Motorola			
Depth sounder	Datamarine			



# **BLANCHE V Iowa Marine Shipyard**

Iowa Marine Shipyard of Keokuk, Iowa, has delivered the towboat Blanche V to Gibbons Marine of Beardstown, Ill. She is an IM-60 Class vessel with an overall length of 60 feet, beam of 24 feet, depth of 8 feet and draft of 6 feet. Propulsion is by twin Cummins KTA-1150-M diesel engines with a total output of 940 bhp at 1,800 rpm. These drive 64- by 50-inch Kahlenberg stainless steel propellers through Twin Disc MG-518 reduction gears with a 6:1 ratio.

Generators are 30-kw Lima-Mac driven by John Deere 4219 diesels. Iowa Marine president Tom Edwards says, "One of the things we have always attempted to do is provide equipment that is easily serviceable, and this John Deere engine is an old-line, widely used engine. Parts and service are available in just about every town where there is a John Deere

dealer."

Steering is an Iowa Marine design, mechanical over hydraulic, full follow-up with each main engine driving a hydraulic gear pump. There are two steering and four flanking rudders, which give the

DESALINATORS AND SILENCERS FOR THE ENTIRE MARINE INDUSTRY. Equally, Maxim Silencers cover Few names have ever been better known for quality and dependthe waterfront with units ability than MAXIM. A standard designed for silencing or for silencing with heat recovery. that has stood for more than 50 years. Today Maxim furnishes And there are reliable Maxim desalinators, including reverse heat exchangers and deaerators: Become part of a legend... osmosis systems, to provide fresh insist on Maxim, the first name water for workboats, offshore in reliability and service. platforms, tankers, submarines and large vessels of all types... Maxim backs it up! Riley-Beaird, P.O. Box 31115, units designed for optimum space savings and operation Shreveport, LA 71130. Phone (318) 865-6351. economy. Nuclear submarine equi RILEY-BEAIRD with Maxim desalinat General Dynamics Photo

vessel exceptional handling capabilities.

The pilot house is equipped with a Regency MT-5500, all channel VHF radio, a Raytheon 400 hailerintercom, two Carlisle & Finch incandescent searchlights, and full instrumentation and alarm sys-

Twin Nabrico 20-ton winches are enclosed in the forward deck locker for protection and to provide an unobstructed deck area. A raised deck is fitted to facilitate access to empty barges.

The vessel is equipped with a 12-volt automatic Jabsco bilge pump that discharges to stuffing box drains directly overboard, a Humphrey sanitary system, and a Dayton air compressor. The hull is constructed of 3/8-inch steel plate, with 3/4-inch rounded corners and ½-inch plate over the stern sections.

The bilge system is designed to allow any compartment on the vessel to be pumped, and allows for discharge overboard, to the slop tank, or to the stern ballast tanks. By utilizing the sea cock, the engine room and the entire exterior of the boat can be washed down.

# CHAMPION EXPRESS Leevac Shipyards

offshore supply Champion Express was delivered by Leevac Shipyards of Jennings, La., to Offshore Express, Inc. of Houston. This is the first of two sister vessels ordered from Leevac by the owner, the second being the Diamond Express.

The Champion Express has an overall length of 165 feet, beam of 38 feet, and depth of 13 feet. She is powered by twin GM Detroit Diesel 16V149 engines providing a

Shown below, the Actinia built by Hitachi Zosen. See page 18 of this issue.



Circle 117 on Reader Service Card ▶



total of 1,350 bhp at 1,800 rpm. The engines drive two 74-inch. 4bladed, Avondale stainless steel propellers through Twin Disc MG 540 reduction gears having a ratio

Two 230-bhp, 8V71 Detroit Diesel engines power the 99-kw General Electric generators. The vessel is equipped with a 200-hp Jastram bow thruster providing a (continued on page 22)

# 12 reasons why workboat and fishboat skippers are changing to Raytheon 3500 MKII Radars.

Compare the 3500 MKII with other 7-inch radars. None matches Raytheon's total performance. None does the job so well day-in and day-out, on every kind of hard-working boat.

# 10 ranges out to 72 miles.



- ½, ½, ¾, 1, 1½, 3,6,12,48, and 72 miles.
- 27 yards  $(25^{\circ}m)$ minimum

# Four pulse 🚄 lengths.

 Automatically selects best pulse length for clearest and sharpest picture on all ranges.

# Ideal 10-kW power.

- Produces maximum signal efficiency with four different pulse lengths.
- Punches through rain and fog.

Eliminates interference from other

STC control eliminates wave clutter. FTC control eliminates rain and

with LED readout.

Variable Range Marker

Gives precise

Supplied as

standard.

Optional RAYMARK

ranges of targets.

radars.

snow clutter.

- Sector guard.
- Gives a second VRM. Adjustable guard ring.
- Automatic detection of targets from 1/8 to 6 miles.
- Audible and visible alarms.

# **8** Adjustable Inner Bearing Scale.

• Fast, accurate relative and true bearings.


# 12-inch Magnifier.

- 12-inch viewing without distortion.
- Supplied as standard.

# Performance metering.

 Front-panel visual check of ship's power, transmitter

and receiver performance. Supplied as standard.



# Easy installation.

- Tabletop, bulkhead, or overhead.
- Single, plug-in cable to Antenna/ Transceiver Unit.

# Two-year warranty unmatched by competition.

Any doubt that this is the best radar for you? Just compare our warranty with any other. Only Raytheon gives you a limited 2-year parts warranty with one year free labor within 50 miles of any of our U.S. dealers and worldwide service network.

For more information see your local dealer or contact:

# RAYTHEON MARINE

**RAYTHEON COMPANY** 


676 Island Pond Road, Manchester, New Hampshire 03103 U.S.A. (603) 668-1600

# **High-resolution** 6-foot antenna.




- Narrow horizontal beam ensures sharper pictures.
- Wide vertical beam compensates for pitching and rolling.
- Wind rated to 101 knots.


# Best interference and clutter suppression.



Interference rejection off.



Interference rejection on.



½ mile range. Typical guard ring setting during anchor watch.



6 mile range. Typical guard ring setting while underway.

## **Champion Express**

(continued from page 21)

thrust of 4,000 pounds. The steer-

ing system is by SSI.

The vessel's capacities include 44,000 gallons of fuel oil, 12,000 gallons of potable water, 132,000 gallons of ballast water, 3,000 cubic feet of dry mud, and 1,500 barrels of liquid mud. The cargo deck area measures 96 by 28 feet. Accommodations are provided for 17 persons.

Main engines (2)	Detroit Diesel
Reduction gears (2)	Twin Disc
Propellers (2)	Avondale
Bearings	Johnson
Generators (2)	eneral Electric
Generator engines (2)	Detroit Diesel
Panels	Treco
Engine monitors, steering	SS
Bow thruster	
Pumps	
Air compressors	
Radars (2)	Furunc
SSB radio	Sailo
Loran C Tex	kas Instrument
Autopilot	Sperry

# ARTHUR FOSS Tacoma Boat Building

The tractor tug Arthur Foss, final vessel in a series of four built by Tacoma Boat Building Company of Tacoma, Wash., for Foss Launch & Tug Company of Seattle, was commissioned during 1983. Like the three sister vessels, the 3,900-bhp Arthur Foss features a cycloidal propulsion system that enables it to produce thrust in any



direction without changing its

The new boat can move sideways, turn a full circle in very limited space, and come to a complete stop in approximately its own length. The capabilities allow the tug to assist ships and tows in a minimum of time and with maximum safety.

The Arthur Foss has an overall length of 106 feet, beam of 38 feet, and draft of 17 feet 4 inches. Propulsion is provided by twin GM Electro-Motive Division 16-645-E6 diesel engines, each rated 1,950 bhp at 900 rpm. The two Voith-Schneider, vertically oriented cycloidal propellers have a blade orbit diameter of 3,200 mm (126 inches); each of the five blades is 2.006 mm (79 inches) long. The Voith-Schneider units were chosen after an in-depth, 2½ year study by Foss. The conceptual design for the tractor tugs was by the Foss design committee; The Glosten Associates of Seattle was the naval architect.

The tug's capacities include 50,550 gallons of fuel oil, 4,500 gallons of lube and hydraulic oil, and 5,400 gallons of fresh water. A crew of six operates the vessel.

Main engines (2) EMD Propellers, engine controls, and
steering systems Voith-Schneider
Generator engines (2) Detroit
Engine monitors Sea-Land
Sanitation system Red Fox
Radar Furuno
VHF radios (2) Raytheon
Winches (2) Intercon
Coatings International
Fendering Schuyler

# EL AUDAZ Bender Shipbuilding

Bender Shipbuilding and Repair of Mobile, Ala., has delivered the 225-foot El Audaz, the yard's fourth big tuna purse seiner in a four-boat order for Mexico. Immediately following her outfitting the El Audaz cast off with her sister ship Centauro Del Norte for fishing in the Pacific.

Main propulsion is provided by a medium-speed, Electro-Motive Diesel 20-645-E7 engine producing 3,600 bhp at 900 rpm. Power is transmitted to a 4-bladed, highly skewed Rice propeller through a Falk reduction gear. Main engine controls were supplied by Mathers.

Auxiliary power is provided by three Caterpillar D3408 diesels, each producing 285 kw at 1,800 rpm. The main hydraulic power source is also a Cat D3408, which develops 500 bhp at 2,100 rpm.


(continued on page 24)

# Tough Marine Chemicals for Tough Marine Operations

At Magnus Maritec, we have been developing and supplying hardworking, cost-effective chemical products to the marine industry for over 25 years. Our diverse line of innovative products is backed by dedicated, on-time service, which owners depend on for efficient operations.

High performance and dependability is why COLORCOOL ™ is popular for freshwater-cooled diesel engines. A liquid nitrite-chelate water conditioner, COLORCOOL ™ inhibits corrosion and

scale formation on all internals of the cooling system. Color indicator warns when the pH level drops to an unsafe level. Work boat operators also depend on our heavy-duty fuel oil additive, COM-BUSTION CATALYST. This advanced, highly concentrated liquid catalyst dramatically improves fuel oil combustion characteristics in diesel engines. Our MAGNAKOTE® rust-retarding tank and void space coating has proven itself superior for steel corrosion protection.









nique Compounds

# Colorcool ™ Engine Corrosion Protection

Prevents scale formation. Conditions metal to resist rust. Full protective action while engine is in operation or shutdown. Scale-causing minerals held in solution for complete bleed-off procedure. Convenient to use liquid contains pH color indicator.

# Combustion Catalyst Increase Combustion Efficiency

Liquid blend of hydrocarbon solvents and organometallics increases fuel oil combustion efficiency in diesel engines. Complete combustion can result in decreasing fuel consumption, smoking, soot accumulation and sparking.

# Magnakote® Rust Retarding Compound

Minimum surface preparation required. Easy to apply: spray or float method. Nontoxic during application. Does not generate explosive gases. High flash point. Easily removed—work area need only be cleaned for repairs. This unique formula carries a U.S. patent.



A Subsidiary of


# Leaders in the Science of Marine Chemistry

150 Roosevelt Place, PO Box 150 Palisades Park, NJ USA 07650 NJ (201) 592-0700 Telex 135-377; 21-9190

For a copy of our technical literature contact your local Magnus Maritec representative or our world headquarters.

■ Circle 118 on Reader Service Card

# Now haul in those big ones within days of placing your order...



# and that's no fish story!

Gator-Laid™ cable-laid wirerope slings are the best big slings in the world made right here in the United States, so we can rush them to your on-shore or Gulf site months ahead of our overseas competitors. Why waste three, even four months waiting for your big sling to arrive from Europe, when you can have an

when you can have an even better one — at a competitive price — within just a few days?

But you want more
than just fast delivery and
low price. So Gator-Laid™
bodies are also more
flexible, to assure you of
easier handling. As a matter of fact,
their loops are the most compact
ever developed in a large lift sling,
and they develop a 1/1 D to d body

pin ratio. They can be made in shorter lengths too, and since each specified length is identical, their length tolerance is an unbeatable 0"

Finally, as you can see for yourself, Gator-Laid™ slings are neater in appearance, which also makes them easier to store, ship and maintain.





THEIR'S


GATOR-LAID™

So don't let this big one get away from you. For dealer nearest you, call toll-free 1-800-TRI-FLEX.

(REPRESENTATIVES COAST TO COAST)

Free Maritime Riggers Manual Just fill out this coupon and mail it in for a valuable pocket-size manual you'll use over and over again.
Name
Company
Address
City State Zip
Business phone
P.O. Box 2068 Dept. D Aston, PA 19014 215/485-8500 Call toll-free: 1-800-TRI FLEX TELEX: 845-261
Company

23



The El Audaz (foreground) underway with the Centauro Del Norte.

# El Audaz

(continued from page 22)

Steering gear is hydraulic, a Wagner LAZ-16-35 furnished by W.E. Hough.

Four 100-hp Vilter compressors power the ammonia refrigeration system. The bow thruster is a Michigan/Jastram BU60 with a 49-inch propeller, powered by a Detroit 12V71 diesel engine with an output of 400 bhp at 2,100 rpm.

The main hydraulic systems were furnished by Marco. They include the WS 454 Super Seiner II seine winch, 3020 cork line winches, WO 332 brailing winch, and B56A power block. Miscellaneous Gearmatic winches are provided for vanging, topping, choking, and strapping.

Incorporated into the hydraulic system is a Slattery Alaska Marine deck crane on the forward deck and a Morris Whaley ring stripper. Navigation aids include a Sperry 8T autopilot and a Mark 37 gyrocompass.

Electronics, furnished by Honor Marine of San Diego and installed by Sassman Electronics of Mobile, include two Furuno FR1011 radars, Whelen strobe light, Furuno FE8130F echosounder, Taiyo ADF,

Furuno VHF/ADF, Navidyne ESZP-3000 satellite navigation, Hull 2320A radiotelephone, Morrow SSB radio, Hull 922R/5 radio, Raytheon VHF radiotelephone system, Honor Marine public address system, Furuno FAX143 facsimile recorder, Bear Cat 300 scanning receiver, Sea Temp seawater temperature monitor, and Telcor windspeed indicator. A Krupp-Atlas sonar model 950 was also included in the electronics package.

Other equipment includes Crane Deming pumps, Buffalo Forge fans, Red Fox sewage treatment system, Westphalia (Centrico) centrifuges, Quincy air compressors, Argur alarm systems, Ansul engine room Halon fire suppression system, Cutler Hammer controllers, Waukesha stern bearings and seals, Hose McCann navigation light systems, International Paint coating systems, Engelhard Chloropacs, Everpure chlorinators, and Micros fresh water distillers.

The Bender-built tuna seiners have steel hulls and pilot houses of aluminum, reinforced for helicopter landings. Each boat is capable of carrying 1,200 tons of fish, 85,000/200,000 gallons of fuel, and 8,500 gallons of fresh water at a speed of 16 knots.

# AMIR EXPRESS Master Boat Builders

Saudi Tug Services, a joint venture company of McAllister Towing and Transportation and Olayan Financing Company, has taken delivery of four offshore supply vessels built by Master Boat Builders, Inc. of Bayou LaBatre, Ala.

The four new vessels—Amir Express, Khalifah Express, Malik Express, and Sultan Express—are on long-term charter to ARAMCO. Each has an overall length of 110 feet, molded beam of 26 feet, and molded depth of 10 feet 6 inches.

Main propulsion power is supplied by twin GM Detroit Diesel 16V71 engines, each with an output of 455 bhp at 1,800 rpm, driving through Twin Disc MG 518 reduction gears having a ratio of 5:1. Two 50-kw, 208/120-volt, 4-wire 60-cycle generators are driven by Detroit Diesel 4-71 engines at 1,200 rpm.

Each vessel is equipped with 60-inch-diameter, 4-bladed bronze propellers, Cutlass rubber stern tube bearings, and dual Electrol hydraulic steering system. Engine controls are by KoBelt Pneumatic Controls.

Deck machinery includes a Nau-



tike 220 hydraulic pedestal crane and an electric, single-drum Mc-Elroy anchor-handling winch.

Electronic gear includes Furuno 701 radar, Hull 922 20-channel SSB radio, Datamarine Digital 3000 fathometer, Texas Instrument 9900 Loran C, and two Sailor 144 MAC VHF radios. Coatings were supplied by Devoe Coatings.



# FRANK CANDIES Champion Swiftships


Champion Swiftships, Inc. of Pass Christian, Miss., in the spring of 1983 delivered the first of a two-tug order, the 3,900-bhp Frank Candies, to Otto Candies, Inc. of Des Allemandes, La. The sister vessel, the Ben Candies, followed a few months later.

The Frank Candies has an overall length of 117 feet, beam of 34 feet, and depth of 17 feet. The tug's main propulsion plant comprises two GM Electro-Motive Diesel 16-645-E6 engines, each rated 1,950 bhp at 900 rpm, driving two 117- by 86.1-inch Coolidge propellers through two Reintjes model 2650 reduction gears having a ratio of 5:1.


Electronic equipment includes two Furuno FR711 radars, a Raytheon Ray 350 loudhailer, a Furuno LC70 Loran C, a Panasonic RF4900 shortwave receiver, two Apelco Clipper 82 VHF radios, a Hull 255 SSB radio, an Okeanos RS5000 satellite navigation unit, and a Datamarine 2650 depth sounder

Other equipment includes a single-wildcat windlass by Markey, a TDSD32 Markey towing winch, and a Halon fixed fire-fighting system. Coatings were supplied by Ameron.

Main engines (2) E	MD
Reduction gears (2) Rein	tjes
Propellers (2) Coolie	dge
Shafts	
Bearings Goodr	rich
Generator engines Detroit Die	esel



# **Now haul** inthose big ones within days of placing your order...



# and that's no fish story!

Gator-Laid™ cable-laid wirerope slings are the best big slings in the world made right here in the United States, so we can rush them to your on-shore or Gulf site months ahead of our overseas competitors. Why waste three, even four months waiting for your big sling to arrive from Europe, when you can have an even better one — at a competitive price — within just a few days?

But you want more than just fast delivery and low price. So Gator-Laid™ bodies are also more flexible, to assure you of easier handling. As a matter of fact, their loops are the most compact ever developed in a large lift sling, and they develop a 1/1 D to d bodypin ratio. They can be made in shorter lengths too, and since each specified length is identical, their length tolerance is an unbeatable 0"

Finally, as you can see for yourself, Gator-Laid™ slings are neater in appearance, which also makes them easier to store, ship and maintain.





THEIR'S

GATOR-LAID™

So don't let this big one get away from you. For dealer nearest you, call toll-free 1-800-TRI-FLEX.

(REPRESENTATIVES COAST TO COAST)

# Free Maritime Riggers Manual

Just fill out this coupon and mail it in for a valuable pocket-size manual you'll use over and over again.

Name		
Company		
Address		
City	State	Zip
Business phone		

P.O. Box 2068 Dept. D Aston, PA 19014 215/485-8500 Call toll-free: 1-800-TRI FLEX TELEX: 845-261





The El Audaz (foreground) underway with the Centauro Del Norte

# El Audaz

(continued from page 22)

Steering gear is hydraulic, a Wagner LAZ-16-35 furnished by W.E.

Four 100-hp Vilter compressors power the ammonia refrigeration system. The bow thruster is a Michigan/Jastram BU60 with a 49-inch propeller, powered by a Detroit 12V71 diesel engine with an output of 400 bhp at 2,100 rpm.

The main hydraulic systems were furnished by Marco. They include the WS 454 Super Seiner II seine winch, 3020 cork line winches, WO 332 brailing winch, and B56A power block. Miscellaneous Gearmatic winches are provided for vanging, topping, choking, and strapping.

Incorporated into the hydraulic system is a Slattery Alaska Marine deck crane on the forward deck and a Morris Whaley ring stripper. Navigation aids include a Sperry 8T autopilot and a Mark 37 gyrocompass.

Electronics, furnished by Honor Marine of San Diego and installed by Sassman Electronics of Mobile, include two Furuno FR1011 radars, Whelen strobe light, Furuno FE8130F echosounder, Taiyo ADF,

Furuno VHF/ADF, Navidyne ESZP-3000 satellite navigation, Hull 2320A radiotelephone, Morrow SSB radio, Hull 922R/5 radio, Raytheon VHF radiotelephone system, Honor Marine public address system, Furuno FAX143 facsimile recorder, Bear Cat 300 scanning receiver, Sea Temp seawater temperature monitor, and Telcor windspeed indicator. A Krupp-Atlas sonar model 950 was also included in the electronics package.

Other equipment includes Crane Deming pumps, Buffalo Forge fans, Red Fox sewage treatment system, Westphalia (Centrico) centrifuges, Quincy air compressors, Argur alarm systems, Ansul engine room Halon fire suppression system, Cutler Hammer controllers, Waukesha stern bearings and seals, Hose McCann navigation light systems, International Paint coating systems, Engelhard Chloropacs, Everpure chlorinators, and Micros fresh water distillers.

The Bender-built tuna seiners have steel hulls and pilot houses of aluminum, reinforced for helicopter landings. Each boat is capable of carrying 1,200 tons of fish, 85,000/200,000 gallons of fuel, and 8,500 gallons of fresh water at a speed of 16 knots.

# AMIR EXPRESS Master Boat Builders

Saudi Tug Services, a joint venture company of McAllister Towing and Transportation and Olayan Financing Company, has taken delivery of four offshore supply vessels built by Master Boat Builders, Inc. of Bayou LaBatre, Ala.

The four new vessels—Amir Express, Khalifah Express, Malik Express, and Sultan Express—are on long-term charter to ARAMCO. Each has an overall length of 110 feet, molded beam of 26 feet, and molded depth of 10 feet 6 inches.

Main propulsion power is supplied by twin GM Detroit Diesel 16V71 engines, each with an output of 455 bhp at 1,800 rpm, driving through Twin Disc MG 518 reduction gears having a ratio of 5:1. Two 50-kw, 208/120-volt, 4-wire 60-cycle generators are driven by Detroit Diesel 4-71 engines at 1,200 rpm

Each vessel is equipped with 60-inch-diameter, 4-bladed bronze propellers, Cutlass rubber stern tube bearings, and dual Electrol hydraulic steering system. Engine controls are by KoBelt Pneumatic Controls.

Deck machinery includes a Nau-



tike 220 hydraulic pedestal crane and an electric, single-drum Mc-Elroy anchor-handling winch.

Electronic gear includes Furuno 701 radar, Hull 922 20-channel SSB radio, Datamarine Digital 3000 fathometer, Texas Instrument 9900 Loran C, and two Sailor 144 MAC VHF radios. Coatings were supplied by Devoe Coatings.



# FRANK CANDIES Champion Swiftships

Champion Swiftships, Inc. of Pass Christian, Miss., in the spring of 1983 delivered the first of a two-tug order, the 3,900-bhp Frank Candies, to Otto Candies, Inc. of Des Allemandes, La. The sister vessel, the Ben Candies, followed a few months later.

The Frank Candies has an overall length of 117 feet, beam of 34 feet, and depth of 17 feet. The tug's main propulsion plant comprises two GM Electro-Motive Diesel 16-645-E6 engines, each rated 1,950 bhp at 900 rpm, driving two 117- by 86.1-inch Coolidge propellers through two Reintjes model 2650 reduction gears having a ratio of 5:1.

Electronic equipment includes two Furuno FR711 radars, a Raytheon Ray 350 loudhailer, a Furuno LC70 Loran C, a Panasonic RF4900 shortwave receiver, two Apelco Clipper 82 VHF radios, a Hull 255 SSB radio, an Okeanos RS5000 satellite navigation unit, and a Datamarine 2650 depth sounder.

Other equipment includes a single-wildcat windlass by Markey, a TDSD32 Markey towing winch, and a Halon fixed fire-fighting system. Coatings were supplied by Ameron.

Main engines (2) . Reduction gears (2) . . . . . . . . . Propellers (2) . . . . . . . . . . . . . . . Bearings Goodrich Generator engines Detroit Diesel Engine controls Wabco Steering system Sperry Pumps Marlow Fire-fighting system Halon Sanitation system . . . . Red Fox Radars (2) Furuno Shortwave receiver . . . . Panasonic SSB radio VHF radios (2) Apelco Furuno . Datamarine Loudhailer Satnav system Okeanos Windlass & winch . . . . . Markey Coatings . Ameron

(continued on page 28)

# If you see two towing companies here, you're right!



# **FURUNO**

# Where the Plot Started

What you see in the illustration is our GD-170 color video plotter . . . what you don't see is that Furuno introduced video plotting to the U.S. back in 1979 and has probably delivered more of them than everyone else combined.

Today, Furuno helps you navigate better with a broad range of paper and video plotters. While these will interface with many navigational systems, Furuno can also provide a complete package with loran, sat nav, omega, or hybrid navigation receivers.

Furuno has a nav system for just about any size vessel, commercial or recreational. At the top end, a system that provides color radar overlayed on color plotting with operator control of a huge number of variables. At the other end, Furuno can supply a loran/paper plotter package that fits just about any pilothouse and budget.

See the whole Furuno line at any of our more than 200 authorized dealer outlets all over the U.S., or write for complete literature to



271 Harbor Way, PO. Box 2343 South San Francisco, CA. 94083 Tel 415-873-9393/Telex 331419

Furuno. Choice of the professionals.





**BOOTH #624** 

0000000000



# Every day, EMD Diesel engines leave

Day after day, year after year, EMD Diesel engines prove their reliability where it counts. improving to make our marine Diesels as efficient and dependable as they are today.


Out on the water.

Through years of research and

improving to make our marine Die-sels as efficient and dependable as complicated. And they've succeeded on both counts.

Today's EMD marine Diesel en-And that's not just a stroke of luck. It took decades of refining and worked hard to make our engines run at the same time, their simple de-

See the fuel efficient EMD engine



# unmistakable signs of their reliability.

sign makes them easy to repair and service. In fact, our customers tell benefit that can be described in us that EMD engines consistently post the best in-service records of any engines in their fleets.

simple terms: superior performance and superior economy. So contact us at the Electro-Motive Division, La Taken together, the advantages Grange, Illinois 60525. Telex: 270041. in its wake.

And ask us for more details.

Then, get an EMD. The marine Diesel engine that leaves everything else



t the Work Boat Show - Booth 874

# **GLOMAR ROBERT F. BAUER** and WESTERN PACESETTER IV Far East Levingston

Far East Levingston Shipbuilding, Ltd. of Singapore in 1983 delivered a semi-submersible offshore drilling rig and a drillship. The drilling rig Western Pacesetter IV, said to be one of the largest to American Bureau of Shipping exploration rigs in the world, was delivered to Western Oceanic Inc. of Houston. This semi is 260 feet long, 203 feet wide, and 116 feet deep. Twin ship-shaped pontoons support six caissons and the rectangular deck. The self-propelled rig has single-level machinery houses, two-level living quarters with helideck, and a substructure for the derrick.


This Friede and Goldman Pacesetter/North Sea Class rig is built

classification. It is designed to operate in water depths from 150 to 2,000 feet, and has accommodations for 90 persons.


The drillship Glomar Robert F.

Bauer was delivered to Global Marine Drilling Company of Houston. Built to Global's design and American Bureau classification, the ship

is 445 feet long, 35 feet wide, and 35 feet deep, with a deadweight of about 7,100 tons. Full-load design draft is 24.5 feet. The Bauer is de-



signed to operate in water depths of up to 2,000 feet. Accommodations are provided for 97 persons; facilities include a six-bed hospital.



# **GRAND REPUBLIC** Offshore Shipbuilding

The Bridgeport & Port Jefferson Steamboat Company of Port Jefferson, N.Y., highlighted the celebration of its 100th anniversary in 1983 with the introduction of its new passenger/auto ferry Grand Republic. The 16-knot, 280-foot vessel was built by Offshore Shipbuilding of Palatka, Fla.

The new Grand Republic is built to the latest requirements of the American Bureau of Shipping and the U.S. Coast Guard. No wood or other flammable materials were used in the construction of the vessel, which is fitted with a Halon automatic fire-fighting system and a Wormald sprinkler installation for maximum safety.

McAllister vice president of engineering Donald C. Hankin designed the vessel, and working drawings were provided by Bold Craft Engineering of Jacksonville, Fla. In addition to carrying 1,000 passengers, 85 automobiles, and/or a combination of trucks and recreational vehicles, the Grand Republic is fitted out with a large cocktail area and bar as well as full restaurant facilities.

The two main engines for the twin-screw vessel are the latest model Caterpillar 3516TA diesels, fitted with 5:1 Reintjes reduction gears delivering 1,500 bhp to each shaft. Propellers are Columbian Bronze 82-inch-diameter, 4-bladed stainless steel. Ship's service and emergency generators are also powered by Caterpillar diesels.

The Grand Republic is fitted with a Schottel bow thruster with a 48-inch-diameter propeller, pow-(continued on page 30)

**◄** Circle 122 on Reader Service Card



# Take Confidence Aboard

# ACR is all the safety gear you need

With ACR safety and rescue equipment stowed, you release lines with a good feeling. Like plenty of fuel in your tanks, or the right sails. You're ready for any situation.

ACR equipment is made by boating people like yourself. It's first class all the way. We even build our own batteries to satisfy our extra-high standards.

ACR makes everything you're looking for - marker and rescue lights, EPIRBs (Emergency Position Indicating Radio Beacons), water-activated lights, strobes, handheld radiotelephones and RDFs, survival kits, and more. Most are USCG and/or FCC approved. All offer outstanding dependability and performance. See ACR equipment at better marine dealers. Or write for catalog.



# AMERICA'S COMPLETE INLAND SHOPE TO THE PROPERTY OF THE PROPERT

# SERVES YOU BEST FOR NEW CONSTRUCTION AND REPAIRS

Since 1933, St. Louis Ship has been known throughout the Inland Waterways System for its Versatility and Performance, as well as for its Quality Construction and Quality Repairs. Long known for pioneering shallow draft marine technology, the company has been the leader in design improvements for river towboats

and barges. The Hydrodyne Hull, introduced in 1963, has been continuously improved through the years to attain the optimum in fuel efficiency. Today, St. Louis Ship maintains the people and the equipment to do your next job the way you want it done—right. Please contact us at (314) 638-4000, today.



29

# **ADVERTISE IN THESE** SPECIAL EMPHASIS ISSUES

TWICE EACH MONTH **BEST READ BECAUSE EVERY ISSUE** IS CURRENT



\* BONUS DISTRIBUTION AT MEETINGS & SHOWS

SPECIAL NAVY

# FOR MORE MARINE SALES

#### **FEBRUARY 1**

Closing Date January 12

• 1984 NAVY ANNUAL

Latest developments in the 5-year multi-billion dollar Navy construction program

• NAVY SUPPLIERS GUIDE \_\_\_\_\_

An exclusive directory of leading suppliers of products and equipment to the world's Navies.

PLUS — A wealth of current marine business and technical information first — weeks before the slower monthlies.

# **FEBRUARY 15**

Closing Date January 26

\* • AWO ANNUAL MEETING ISSUE (American Waterways Operators)

Special AWO INDUSTRY Reports

• U.S. INLAND WATERWAYS YARDS

- A Review -

PLUS — A wealth of current marine business and technical information first — weeks before the slower monthlies.

#### MARCH 1

Advertising Closing Date February 8

\* • EXPO-SHIP NORTH AMERICA '84

(International Maritime Exhibition) New York City — March 19 - 23

\* • In conjunction with the MONEY AND SHIPS CONFERENCE

PLUS = A wealth of current marine business and technical information first = weeks before the slower monthlies

#### MARCH 15

Advertising February 23

\* SNAME SPRING MEETING/ STAR SYMPOSIUM

Los Angeles, Calif. — April 11 - 14 Preview of technical program of the Society of Naval Architects and Marine Engineers annual Spring Meeting and Symposium

Special NAVY Article

PLUS — A wealth of current marine business and technical information first — weeks before the slower monthlies.

#### **APRIL 1**

Advertising Closing Date March 9 \* • OTC '84

**Annual Offshore Technology** Conference Preview

Houston, Texas — May 7 · 9

• OFFSHORE UPDATE Special NAVY \* A.S.N.E. DAY

(American Society of Naval Engineers) Washington, D.C. — May 3 · 4

 NATIONAL MARITIME SHOW AND CONFERENCE

Houston, Texas — April 25 - 27

PLUS — A wealth of current marine business and technical information first — weeks before the slower monthlies.

#### **APRIL 15**

Advertising Closing Date March 26

\* • A.P.I. TANKER CONFERENCE

(American Petroleum Institute) Boca Raton, Florida — May 6 - 9

\* • RO/RO '84

(Seventh International Conference & Exposition on Marine Transport) Nice, France - May 9 - 11

SURVIVAL AT SEA

Survival and safety systems and equipment review

PLUS — A wealth of current marine business and technical information first — weeks before the slower monthlies.

# TWICE EACH MONTH - FIRST WITH THE NEWS - FIRST IN READER INTEREST

Published TWICE each month . . . 24 times a year . . . MARITIME REPORTER delivers the latest and most important industry information FIRST and sometimes months before the same information, often with the same photos, appears in the slower monthly magazines.

Here is unequalled editorial performance . . . providing the industry's only source for complete, current and fresh reports on all important marine developments . . . FIRST

As a result, MARITIME REPORTER is the industry's most wanted magazine . . . 100% requested, in writing, by the world's largest audience of marine management readers . . . thousands more than any other marine magazine

Every one of the 1983 special emphasis issues listed in this calendar will also contain a full measure of regular current industry news . . . . the key to the consistently unequalled reader interest enjoyed by all 24 issues of M.R. Your advertising is bound to work harder for you . . . produce better results and more sales . . . in the high-intensity reader interest atmosphere created only

MARITIME REPORTER is the best read marine magazine . . . thousands more marine management readers have acknowledged and confirmed it . . . by requesting MARITIME REPORTER year after year.

**Total circulation** 100% REQUESTED in writing



107 EAST 31st STREET NEW YORK, N.Y. 10016 (212) 689-3266

**Grand Republic** 


(continued from page 28)

ered by a 400-bhp Cat diesel through a Twin Disc reduction gear. All of the Caterpillar equipment, the Tug Mate machinery monitoring system, and the air controls with Reintjes and WABCO components were supplied by H.O. Penn Machinery Company.

Steering equipment consists of an SSI 4-station, electro-hydraulic system. The SKF OK shaft couplings were supplied by Bird-Johnson; shaft bearings were manufactured by Johnson Rubber and Cooper Bearing. Radars and VHF radio are by Raytheon, and the fathometer is from Datamarine.

#### **GRAND REPUBLIC** Major Suppliers

Main engines (2) Caterpillar Reduction gears (2) Reintjes Propellers (2) Columbian Shaft bearings Johnson/Cooper Shaft couplings SKF Bow thruster Schottel Steering SSI Machinery monitoring Tug Mate Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Propellers (2) Columbian Shaft bearings Johnson/Cooper Shaft couplings SKF Bow thruster Schottel Steering SSI Machinery monitoring Tug Mate Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Shaft couplings SKF Bow thruster Schottel Steering SSI Machinery monitoring Tug Mate Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Bow thruster Schottel Steering SSI Machinery monitoring Tug Mate Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Steering SSI Machinery monitoring Tug Mate Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Machinery monitoring Tug Mate Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Generators Cat/Kato Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Fire protection Wormold Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Pumps Goulds/Viking Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Cathodic protection Engelhard Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Sewage treatment Omnipure Air controls Reintjes/WABCO Radars (2) & VHF Raytheon Fathometer Datamarine Deck crane Alaska Marine (Slattery)
Air controls
Radars (2) & VHF
Fathometer Deck crane Alaska Marine (Slattery)
Deck crane Alaska Marine (Slattery)
Capstans & windlass McElroy
Anchor
Searchlight Carlisle & Finch



# **IKALUK/MISCAROO** Nippon Kokan K.K./ Vancouver Shipyards

Beaudrill Ltd., a subsidiary of Gulf Canada Resources Inc. of Calgary, Alberta, took delivery at mid-1983 of the Ikaluk, first of two 14,900-bhp Arctic Class 4 icebreaking anchor-handling/supply vessels for operations in the Canadian Arctic. She was built at the Tsurumi Shipyard of Nippon Kokan K.K. in Yokahama to a design by Robert Allan Ltd. of Vancouver, B.C. The sister ship, Miscaroo, was delivered about three months later by Vancouver Shipyards Company Ltd. of North Vancouver, B.C. Both vessels will constitute a vital part of Gulf Canada's drilling operations in the Beautort Sea.

The new vessels are among the most powerful of their type in the world, and are said to be the first commercial vessels constructed to

by MARITIME REPORTER

the Canadian Coast Guard's high Arctic Class 4 Regulations. Designed to operate in conditions of minus 50 C, they will break level ice up to 1.2 meters (almost 4 feet) thick at a continuous speed of about 3 knots.

The propulsion plant consists of a geared diesel/C-P propeller combination. The four main engines are Wartsila Vasa 8R32 diesels rated 3,725 bhp each at 750 rpm. These engines, in pairs, drive two 3,750-mm (12.3-foot) Lips controllable-pitch, stainless steel propellers through two Lohmann & Stolterfohtt dual-input/single-output reduction gearboxes, model GVA 1400 SO, with a ratio of 4.5:1. Each gearbox incorporates an auxiliary drive for a 1,200-kva alternator.

Several unusual features enhance performance in ice. Among these are a hull form incorporating a forefoot wedge designed to deflect ice from the path of the vessel, and large bossings over the propeller nozzles and rudders to protect them from ice.

Maneuverability is improved by electrically driven thrusters located fore and aft. The bow thruster is a 1,200-hp Omnithruster model JT 1300, and the stern thruster is an 800-hp KaMeWa model 1650 B/AS with controllable-pitch propeller. The Omnithruster has been modified to incorporate an ice/hull lubrication system that ejects an air/water mixture along the forward half-length of the hull, which is coated with an epoxy paint, Inerta 160, to reduce hull/ice friction.

The Ikaluk and Miscaroo have an overall length of 78.85 meters, molded beam of 17.22 meters, molded depth of 9.70 meters, and design draft of 7.50 meters (258.7/56.5/31.8/24.6 feet).

A spacious wrap-around wheel-house provides maximum visibility for both anchor-handling and icebreaking operations. Full ship control consoles are located center forward, in the forward wings, and center aft. Wing controls are located at the wheelhouse aft station and in a separate control room located above the main winch. Winch and anchor-handling operations are monitored by closed-circuit television.

Deck machinery includes a Burrard Iron Works HLQW quadruple-drum, anchor-handling/towing winch with a line pull of 150 tons; two Hydralift cargo cranes; three Burrard Iron Works CH6 deck capstans; and two Gearmatic 66 tugger winches, each with a line pull of 15 tons.

In addition, there are two Burrard Iron H7V anchor windlasses rated 20 tons at 10 meters per minute, and two Burrard HE hydraulic-driven pennant storage winches.

Ship's service electric power is provided by two Caterpillar 3412T diesel generator sets rated 395 kw at 1,800 rpm; a Cat 3404 diesel generator set rated 100 kw at 1,800 rpm provides harbor service.

Navigation and communications equipment includes: two Decca radars, model TM 1628 with 12-inch slave unit, and model TM 1266C; two Sperry gyrocompasses, MK 37; Wagner MK 4 autopilot; Honeywell Elas LAZ-72 fathometer; Magnavox MX 1105 satellite/Omega navigator; and a JMC 2215 automatic direction finder.

In addition, there are Marconi CH150S SSB radios, a Spilsbury FMX-95S VHF-FM radio, Wulfsberg WCS-300 VHF-AM radios, Sperry SRD-301B doppler log, Alden Marinefax IV weatherfax, and Simrad RW 105 and Marconi SM100 watch receivers.

Accommodations are provided for a crew of 22 persons, all in private cabins, as well as spacious lounges, recreation areas, and a sauna. Particular attention to reduction of vibration and noise has resulted in noise levels of less than 63 decibels throughout the accommodations while under full power.

# KODIAK I Halter Marine

The largest, most powerful, diesel-electric, anchor-handling tug/ supply boat ever built in the U.S. was delivered in 1983 by Halter Marine, Inc. of New Orleans to the Penrod Drilling Corporation of Dallas. The Kodiak I is the first of two 12,280-bhp sister ships that are 225 feet long overall, with a beam of 52 feet, depth of 24 feet, and draft of 20 feet. She is also the first of Halter's new Sea Titan Class vessels that are designed to work just about anywhere in the world from the Arctic to the tropics. The Sea Titan design not only meets the requirements imposed by harsh, icy environments, but provides 35 tons of air condition-

Main engines (4) Main generators (4) Reduction gears (4) Propulsion motors (4) Propellers (2) & shafts Bearings Generator Panels Engine controls	Electro-Motive Philadelphia Reliance Coolidge Johnson International General Electric
Engine alarms	EMI
Steering system	SSI
Bow thrusters (2)	Schottel
Stern thruster	Schottel
Thruster motors (3)	
Separators	
	(Centrico)
Pumps	Aurora, Magnum,
	Mission, Viking
Fire monitor	Elkhart
Fire-fighting system	
Air compressors	
Sanitation system	
Air conditioning	
Distiller	Sweetwater
Lighting Aqua-Signal	. Carlisle & Finch
RDF	Pauluhn, Phoenix
RDF	Si-Tex
Radar	Decca
SSB radio	Harris
VHF radio	Sailor
Satellite navigator	Decca
Gyrocompass, autopilot .	Sperry
Loudhailer	Ravtheon
Rudder angle indicator	<i></i> SSI
Winches	Smatco, Beebe
Capstan, tuggers	
Windlass	
Coatings	Elinca, Porter

Navigation and communications ing to improve habitability in hot guipment includes: two Decca racilimates.

The design of the Kodiak I, which was tested before construction at the Maritime Research Institute in the Netherlands, features a molded hull rather than the traditional chine type. The molded hull is said to pound less and have better seakeeping characteristics. The high, tapered bow also helps to reduce pounding because of its reduced flare, which gives it a smoother entry into the sea without slamming and with a subsequent easy recovery.

The Kodiak I represents an entirely new design, including higher horsepower and kilowattage, increased cargo and pumping capacity, long range, rig anchor chain stowage, higher speed, fire-fighting and rescue capabilities, and excellent sea-keeping ability. All this was achieved while keeping the vessel under 500 gross tons.

Kodiak I's propulsion plant comprises four GM Electro-Motive Division 16-645-E7B diesel engines driving four 2,100-kw EMD generators. Together they produce 12,280



bhp at 900 rpm, or 8,400 kw. The generators feed ac power into a Ross-Hill silicon controlled rectifier unit, which converts the ac power into dc to power the four Reliance 2,500-hp propulsion motors. The power pool created allows the captain to draw as much power as is put in, and the power can be distributed wherever needed.

As the Kodiak I is designed for (continued on page 36)

# *(ENERGY INDEPENDENCE)*

# has insured watertight integrity with W. conveyor belt doors



The self-unloading Energy Inde-General Dynamics Quincy Shipbuilding Division Collier Co., is the first coal-fired collier built in the years. All eight conveyor belt doors are by Walz & Krenzer. pendence, built by for New England U.S. for more than 50

Watertight integrity for subdivision bulkheads is always assured with patented WK systems. Simple pneumatic or hydraulic operation and high reliability meet the requirements of all regulatory bodies. Unique design offers generous vertical and side clearance to eliminate conveyor belt damage and insure long, trouble-free life.

CALL, TELEX, OR WRITE For FREE DESCRIPTIVE LITERATURE




400 Trabold Road, Rochester, NY 14624 716/247-4330/Telex 64-6874 20 Vesey Street, New York, NY 10007 212/732-7863/Telex 12-6075

# BRONZE HORIZONTAL 10HLV INGERSOLL-RAND CARGO PUMP



Ingersoll-Rand 10HLV — 14"x10". Bunker Fuel: 5150 GPM — 370' head — 1885 RPM. Sea Water: 6000 GPM — 352' head — 1885 RPM. Reduction Gears: G.E. type 5-233 — Form AE — 700 HP — 6002/1685 RPM. TURBINE: G.E. D.P. 25 Class 4 — 700 HP — 6002 RPM — PSIG 775 lbs — 825 — inlet temp. 560° - 600° max. Exhaust pressure 179" Hg absolute.

# NEW CLARK 500BHP DIESEL 4-CYL. — AIR STARTING



500 BHP @ 400 RPM. 4-Cylinder straight inline type — 12½" X 16" — 2-stroke single acting — liquid cooled — direct reversible — CW rotation. With standard shaft-connected starting air compressor. 46,000 lbs., net weight—228" long—98" wide—132" high. Designed for heavy duty, rugged use, its extreme simplicity will result in lower operating and maintenance costs.

# LOUIS-ALLIS M.G. SETS

2.5 KW 120 Volt Single Phase 60 Cycle Output 120 Volt D.C. Input — 1800 RPM

> 230 Volt D.C. Input – 1800 RPM NEW - UNUSED EX - U.S.N.




2½ KW—115 volts single phase A.C. output. GENERATOR: Type GNA—class 1G— Frame 28A—Form A—1800 RPM—5 KVA—2.5 KW 115 volts AC— 60 cycle—50% PF—43.4 amps. MOTOR: Louis Allis—Type GNA—Class E—Frame 25A—Form A—1800 RPM—115 volts DC—32 amps—shunt wound (with attached Wardleonard frequency regulator).

CAN FURNISH WITH 230 VOLT DC INPUT

#### **STEAM MOORING WINCHES**

12" x 14" — STEAM OR AIR DRIVEN with foot brake & declutchable gypsy head 20,000 LBS @ 100 FPM—FIRST LAYER



# ALSO HANDLES 16,000 LBS @ 150 FPM OR 50,000 LBS @ 8 FPM

Drum will show 1500 ft of  $1\frac{1}{2}$ " wire in 9 layers. Steam inlet  $3\frac{1}{2}$ "-4" exhaust — 171 PSI working pressure. BASE DIMENSIONS:  $6' \times 6' \cdot 3\frac{1}{2}$ " — overall  $8' \cdot 4\frac{1}{2}$ " wide  $\times$  9' long. Mfg. by Friedrich Kocks — Bremen, Germany. Recently removed from ARCO "Challenger." Suitable for vessels 75000/200000 tons.

#### **ALSO IN STOCK**


12" x 14" Double Gypsy Unit

ALL UNITS CAN BE DEMONSTRATED RUNNING

#### NEW — UNUSED — LARGE

# BALDT-TYPE ANCHORS

WITH CERTIFICATES




- (1) Stockless 5050 kilograms (11,133 lbs.)
- (1) Stockless 5100 kilograms (11,243 lbs.)



# DANFORTH TYPE ANCHORS

WITH CERTIFICATES 1000 LBS.


700 GPM @ 150 PSI
NEW — EX-USN
DE LAVAL MOTOR DRIVEN ROTARY
HORIZONTAL PUMPS
WITH 4-SPEED 440/3/60 MOTOR



Inlet 8" — outlet 6". Powered by 4-speed 440/3/60 motor — 100/75/50/37.5 HP — 1200/900/600/350 RPM — with Cutler-Hammer control. Weight 10,000 lbs. Inquire for complete details.

# ALLIS-CHALMERS BRONZE BALLAST OR CARGO OIL PUMP

PUMP: 12" x 10" — 6000 GPM — 180' head — 340 HP — 1225 RPM. Impeller diameter 19.75". GE GEAR: Type 5-233 — 5022/1225 RPM. GE TURBINE: GE Model 7TDPY125MR41 — 340 HP — 5022 RPM — inlet pressure 775 lbs. — 825 PSIG maximum — 600°TT.



DEAN BROS.
ALL BRONZE
STRIPPING PUMP —
BILGE & BALLAST
12 x 10 x 18

Max. pressure 730 GPM @ 200 lbs — steam end 250 lbs. Serial 67735 — OA Dimensions: 43" wide — 39' deep — 104" high. Complete with spare unused bronze valve deck & spare liquid lines piston, steam end spares, rods, etc. This pump ready for immediate use — equal to new — little if any use.

# (SEE OUR CLASSIFIED AC



#### 24" I.D. MAN-WAY 3-DOG HATCHES

18" Coaming. Available with T socket wrench or removable handwheel (can be welded in place) for top opening. Springloaded lid w/inside handwheel. Coaming 12mm thick, top 11mm. Bosmet drawing #67/56



#### 20" ROUND HATCH

18" Coaming — 3 brass dog drop bolts. Coaming 12mm thick — top 11mm. Bosmet #68



#### QUICK-ACTING 4-DOG HATCHES

Heavily constructed. Handwheel operated. Handwheels top & bottom. Size A: 27" x 21" w/12mm coaming & 11mm top. Size B: 31" x 31" w/12" coaming. For oceangoing barges, tugs, etc.

## GENERAL PURPOSE HATCH



15" X 23" X 5" WITH 4 STEEL DOGS



TAN EXPANSIC





CARGO

69" x 75" x 12" 72" x 74" x 12"



QUICK-OPEN Handwheel top & bo 24" with 5" coaming



FRONT



BACK

# 500 KW AC GE DIESEL GENERATOR



G.E. ATI — 985Y — 500KW — 625 KVA — 480 volts — 800 amps—3-phase 60-cycle—720 RPM. Self-ventilated — totally enclosed — water-cooled — directly connected to Cooper-Bessemer model G.S.B. 8-cyinder diesel engine — 10½" X 13½" — four cycle — 720 RPM. Air starting — 300 PSI — with Ross water and oil coolers. Total weight 48,700 lbs.



# **D** DOORS IN STOCK FOR MORE DOORS)



**TRUNK** oaming — 7-Dog 5/26



48" x 48" x 9" 36" x 30" x 8"



3 HATCH ı. 4 Dogs. 16" awing #60-40

#### **STORES** OADING **PORT**

side port uble door and me. Clear open-: 7'6" high X wide, 24 Dog fitted with bar angback. Made 3/8" steel. refully removed m Alcoa "Sea-



#### 21" I.D. MAN-WAY **3-DOG HATCHES**

10" Coaming. Available with T socket wrench or removable handwheel (can be welded in place) for top opening. Coam-ing 12mm thick, top 11mm. Bosmet #64/55



#### **FLUSH HATCHES**

24" x 30" x 30" x 30" 4 Dags bottom — T-key top opener. 4" Maximum coaming. Coaming 8mm thick — top 7mm.



#### 25" ROUND HATCH

25" Diameter with 18" coaming, 4-Dog handwheel top and bottom. Quick-acting dogs. 11 mm x 12 mm steel.



#### NEW 18" & 24" **HATCH COVERS**

Flush mounting watertight hatch with machined steel mounting ring. T-Handle is recessed and hand tightens against a strangback across mounting ring. Approx. weights, including mounting ring: 18" 60 | bs — 24" 100 | bs.

#### **GENERAL PURPOSE WINCH** 3500 LBS AT 200 FPM






A.C. Motor drive-25/12.5 HP-GE 440/3/60-40°C AB -1750 RPM-type KR-full load amps 32. Motor drives winch through Falk reduction gear. Has compressor hand brake.

BALTIMORE, MD. 21202

00 Marine Dept.: (301) 752-1077

). U.S.A. TWX 710-234-1637

#### **WORTHINGTON 16" X 14" X 18"** VERTICAL DUPLEX STRIPPING PUMP



1400 GPM @ 110 PSI — suction lift 11.5 ft. — steam back pressure 15 lbs. 14" Suction -- 10" discharge - 2½" steam - 4" exhaust. Overall width 6'8" overall height 9'1½" — depth 3'91/2". Wt. approx. 10,000 lbs.

**RECONDITIONED 1980** ABS - READY TO GO

# **NEW U.S. MARAD-TYPE AXIAL FLOW FANS**




(3) 10,500 CFM Model AF-100, "Baldor" 5 HP motor -440/3/60 - 40° - 1750 RPM - 7 amps.

(2) 40,665 CFM — size 43AF — 60 HP Baldor Motor — 440/3/60 - 1760 RPM - 75 amps - 50° rise - Frame 364TZ Ins. F

# NEW NAVY 12,000 CFM **EXPLOSION PROOF AXIAL FLOW FANS**

Model A12A4X6 with 10/3 HP 2 speed motor.

# 7x12 10,000 LB AH&D **CARGO WINCHES**



2-Speed — single drum — reverse throttle operation. LINE PULL: low gear 10,000 lbs — high gear 5,000. LINE SPEED: low gear 125 FPM based on 1st layer of 7/8" diam. rope — high gear 250 FPM based on 1st layer of 5/8" diam. rope. DRUM: 26" diam. — 20" long — 26" flange diam. Rope capacity of drum: 7/8" diam. rope in 6 layers — 650'; 5/8" diam: rope in 8 layers 1200'. Steam pressure at throttle 115 lbs. Operating weight 6450 lbs.

# **NEW CHOCKS-CLEATS-BITTS**



# **OPEN CHOCKS**

Overall length 2' 3¾" — top opening 6" — width 9"






10" DOUBLE POLE BITTS

# **50 HP VARIABLE SPEED ELECTRO-HYDRAULIC** SINGLE DRUM **CARGO WINCH**

with deck controls **SELF-CONTAINED WITH PUMP MOTOR & RESERVOIR IN BASE** 




Made by Lakeshore. DUTY: 7400 lbs SLP - 220 FPM drum size 24" diameter - 15" wide. Complete with ratchet & pawl. CAPACITY: 600 ft. of 34" wire. MOTOR: 50 HP — 440 volts — 66.3 amps — 3-phase 60 cycle squirrel cage — 1200 RPM constant — Frame CC-445-N - 1 hour duty. Motor drives Waterbury size 5 "A" end — size 5K heavy duty remote servo control 1150 RPM - WP 1900# - test 3000#. "B" End motor type 5K heavy duty — size 5 1150 RPM. Originally built for U.S. Navy refueling at sea. AVAILABILITY: Some with double gypsy; some with single gypsy; some with no gypsys. Ex-U.S.N.

PLANS ON REQUEST

# LARGE STEAM **TOWING ENGINE**

9 X 10 TWIN ENGINE DRIVE Air or Steam - 125/250 PSI




Heavy-duty Clyde with 36" diameter X 51" Face single drum. Flanges 68". CAPACITY: Up to 2800' of 2" wire rope. Normal line pull 40,000 lbs@ 50 FPM. Steam or air pressure required 125 to 250 PSI. Can be adapted to electric drive or increased steam or air pressure to a capacity of 82,000 lbs @ 20 FPM. Pawl holds 270,000 lb. pull from any layer. Equipped with level wind device. Approximate weight 30,000. DIMENSIONS: 12'6" wide—6'6" high. Write for details.

# ALSO AVAILABLE

Large towing ring - 36" I.D.

# 900HP GM 12-567A PORT DIESEL ENGINE

WITH FALK **REVERSE** AND REDUCTION **GEAR** 



ENGINE: GM 12-567A-81/2 X 10-V-type-2-cycle-747 RPM — electric starting. GEAR: Falk AirFlex — reverse & reduction — 2.48:1 forward — 2.52:1 reverse.

# MARITIME REPORTER CARRIED MORE AD

MR's LEAD INCREASED AGAIN...TO A RECORD 2,072 PAGES OF FULL-RATE



# MARITIME REPORTER IS THE ADVERTISING LEAD


The world's leading and most successful marine advertisers prefer MARITIME REPORTER because ... they report ... MR produces far better results than any of the other marine magazines.

## **'ERTISING ...FROM MORE ADVERTISERS**

PAID ADVERTISING...695 MORE PAGES THAN NO. 2



TWICE EACH MONTH BEST READ BECAUSE EVERY ISSUE IS CURRENT



## R...BECAUSE IT PRODUCES THE BEST RESULTS

Let us <u>prove</u> we can do a better advertising job for you. Send for a special report on the actual results produced by MR for other advertisers in your marine product or service area.



107 East 31st Street New York, New York 10016 (212) 689-3266

#### Kodiak I

(continued from page 31)

long voyage towing, she is fitted with a full complement of Smatco/Norwich deck machinery, including an electro-hydraulic, double-drum waterfall towing winch with a combined pull of 500 tons; two tugger winches, two double cable storage reels, two electro-hydraulic capstans, and an anchor windlass.

Maneuverability and stationkeeping is enhanced by two bow thrusters and a stern thruster, all provided by Schottel and driven by Reliance electric motors. Kort nozzles surround the two 142-inch-diameter, 5-bladed stainless steel main propellers. A Flume passive stabilization system is installed to improve the vessel's stability.

## JUSTIN T. ROGERS St. Louis Ship

The river towboat Justin T. Rogers, built by the St. Louis Ship Division of Pott Industries for Midland Affiliated Company of



Cincinnati, was delivered in early 1983. She is powered by a pair of M.A.N.-B&W 16U28L 4-stroke, medium-speed diesel engines that are capable of burning heavy blended fuels up to 2,100 seconds Redwood. While burning No. 2 diesel oil, the two engines develop a total of 8,364 bhp at 775 rpm; total output is 7,524 bhp at 750 rpm while burning heavy fuel.

Second of its class built by St. Louis Ship for Midland, the Rogers, along with sister vessel Jim Ludwig, are said to be the first modern U.S. river towboats built from the keel up to burn heavy fuel. Both vessels feature a state-of-the-art heavy fuel handling and cleaning system designed by Midland in conjunction with M.A.N.-B&W and Marine Consultants & Designers, Inc., naval architects and marine engineers of Cleveland.


The engines are connected through the new Falk MQR configuration 4,086:1 reverse/reduction gears to Coolidge 120- by 130-inch, 5-bladed, stainless steel propellers mounted in Kort nozzles. Engine controls are by Mather, and engine monitoring equipment was supplied by Pan American Systems. Electric power is supplied by two International Electric 200-kw generators driven by Detroit Diesel 8V92 engines.

An interesting feature of the Rogers is its exhaust waste heat recovery system, used to heat fuel bunkers and crew quarters, designed by the Engineering Controls Division of St. Louis Ship. The shipyard also supplied the F.A.S.T. sanitation system.

Electronic and other navigation equipment includes two Decca radars, RR1226 and RR1216A, Honeywell Elac depth sounder, Rivertronics swing indicator, Perko navigation lights, R.L. Drake MRT-55 VHF radio, Northern N55A SSB radio, three Carlisle & Finch searchlights, and Kahlenberg air horn.

Pumps were supplied by Aurora (fire), Gorman-Rupp (bilge), and Viking (FO transfer). Alfa-Laval provided the centrifugal separators, Va-Power the oil-fired boiler, and A. O. Smith the water heaters. Deck equipment includes a Schoellhorn-Albrecht capstan and four Patterson winches. Air compressors are by Quincy.

pressors are by Quincy.
The St. Louis Ship "Hydrodyne"
hull of the Justin T. Rogers has an
overall length of 187 feet, a beam
(continued on page 38)





# Marine Insurance. If it's Greek to your company, you could be in for a big surprise.

Understanding insurance—especially marine insurance—is a full-time job. So if you're at the helm of your own company how can you be expected to keep up with the ins and outs?

At Adams & Porter, we know every bend, shoal and snag in the business. Marine insurance brokerage is where we made a name for ourselves 75 years ago.

Adams & Porter professionals can help pilot you through any dangerous waters fully protected by the right amount of coverage for your business.

It's custom coverage. From indemnity agreements and deductibles, to risk management at an efficient cost. With fast claims settlement. In other words, everything that it takes to keep your firm afloat.

Combine all this with our unique knowledge of cargo, hulls, oil industry risks, crew and other liabilities. Now you have the solid experience of a company that has the ability to steer you clear of the big surprises. Adams & Porter Associates, Inc., 1819 St. James Place, Houston, Texas 77056, (713) 960-9990. Also in New York and Bermuda.



We take the mythout of comorate insurance

37

Justin T. Rogers

(continued from page 36)

of 47.8 feet, and a depth of 12 feet. Operating draft is just over 9 feet.

Midland's decision to build heavy-fuel boats was based purely on economics. The price and availability of fuels are two major factors in moving cargo competitively. Midland operates the Rogers on the lower Mississippi River between Cairo, Ill., and New Orleans. The new vessel is used to transport coal, grain, and other dry bulk commodities.

## KALVIK/TERRY FOX **Burrard Yarrows**

Burrard Yarrows Corporation headquartered in North Vancouver, B.C., Canada's biggest West Coast shipbuilder, in 1983 delivered two identical icebreaking, anchor-handling/tug-supply sels to Gulf Canada Resources Inc. of Calgary, Alberta. Named Kalvik and Terry Fox, these vessels are reported to be the most pow-



erful of their type in the free world. Kavlik was built at Burrard's Victoria Division on Vancouver Island and the Terry Fox was built at the Vancouver Division in North Vancouver. Design and supervision of construction was carried out by naval architects German & Milne Inc. of

The 2,200-dwt vessels have an overall length of 288.7 feet, beam of 57.4 feet, depth of 32.8 feet, and operating draft of 26.25 feet. They carry crews of 18 persons and are designed for optimum performance in both open and ice-covered wa-

Each vessel is powered by twin TM510 Stork Werkspoor diesels with a total output of 23,200 bhp, driving through Lohmann & Stolterfoht single-reduction gearboxes to open, controllable-pitch Lips propellers. A 1,000-kw generator is clutched off each gearbox; in the icebreaking mode, these generators are dedicated to driving the Wartsila air bubbler system. Main engine controls are by ASEA. Ship's service electric power is provided by two 750-kw ac generators driven by Caterpillar diesels. A 200-kw emergency generator is also installed.

In addition to the large centerline rudder, steering is assisted by a 500-hp stern thruster supplied by Maritime Industries. The air bubbler system also functions as a bow thruster. A special coating, Inerta 160, covers the hull up to the main deck, protecting the hull and reducing hull-ice friction.

Particular attention has been given to the form of the forward part of the vessels to prevent ice from flowing under the hull and being ingested into the propellers. In addition, the bow design has been developed to maximize both level ice and ridge ice penetration performance. Special attention has been given to directional stability in the ice-ramming mode.

The hull is of double chine form and incorporates a semi-spoon bow, forward ice plow, and raked transom stern. A double skin arrangement provides both protection and the ability to operate at a constant draft by adjustment of the quantity of ballast in relation to quantites of fuel, cargo, etc. being carried.

To simplify construction, the hull is of fully developable form. This is particularly advantageous as the shell plating and hull support structure are of EH36 modified special quality steel.


A sophisticated towing and anchor-handling system has equipment arranged under cover for protection from Arctic weather.

The towing system includes an 80-ton Van der Giessen towing winch and a friction brake capable of up to 390 tons of holding power. Anchor handling will be carried out with a double-drum, waterfall type winch, each drum capable of 200 tons pull.

The Kalvik and Terry Fox have been built to the highest class of Lloyd's Register of Shipping and to the Arctic Shipping Pollution Prevention Regulations for an Arctic Class 4 vessel, all to the approval of the Canadian Coast Guard.

## KALVIK/TERRY FOX

Major Suppliers
Main engines (2) Stork Werkspoor
Reduction gears (2) Lohmann &
Stolterfoht
Propellers (2) Lips
Engine controls ASEA
Steering, autopilot Wagner
Stern thruster Maritime Industries
Bubbler system Wartsila
Generator engines Caterpillar
Pumps Pumps & Power
Winches Van der Giessen
Radar Decca
Satnav
Doppler log, gyrocompass Sperry



System capacities range from 39 to 1,320 GPH

Our Microphor/Taiko Oily Water Separators use stateof-the-art technology to separate oil from bilge water. Compact, easily-installed devices utilize straight coalescing method to remove oil. Separation is by gravity through a series of chambers. Low purchase price, minimum maintenance and economical operation mean our oily water separators are your best buy. Corrosion, oxidation resistant. Longer service life. Eliminate scheduled filter changes. Exceed IMO and USCG discharge requirements.

Microphor, Inc. P.O. Box 490 Willits, CA 95490 U//459-5563 Telex: 330470

Forest Lodge West, Fawley Road Hythe, Southampton, S046ZZ England Telex: 477580 HOVCON G

Microphor<sup>®</sup> is a registered trademark for certain products manufactured by Microphor, Inc., Willits, California Subsidiary of the Harrow Corporation

## NAVASOTA Patti Shipbuilding

Patti Shipbuilding of Pensacola, Fla., in early 1983 delivered the 100-foot oceangoing tug Navasota to Brazosport Towing Company of Freeport, Texas. Classed + Al + AMS Loadline, All Ocean Towing Service by the American Bureau of Shipping, the new vessel brings to 14 boats owned and operated by Brazosport Towing in coastal and international service.

The Navasota is powered by twin Caterpillar D-399 diesels, each with a rated output of 1,125 bhp at 1,225 rpm, driving through Reintjes WAV 1400 4.95:1 reduction gears to Columbian 82- by 84-inch stainless steel propellers installed in Kort nozzles. The vessel recorded an impressive 13 knots on sea trials.

Electric power is supplied by two 55-kw generators driven by Caterpillar diesels. The main electrical panel was provided by Con-Select. Other equipment includes two Ingersoll Rand 242 air compressors with 80-gallon receivers, Cacor 75-1000 fuel filters, Custom mahogany Mathers AD 12 air controls and SB 22 shaft brakes, a Gould fuel transfer pump with meter, two Gould bilge pumps, two Peabody




Barnes fresh water pump systems, a Walker Electric Service alarm system, SSI Nav/Lite panel, Mc-Elroy anchor winch, and Smatco 46/34 DAW 100 towing winch.

Electronics include one 64-mile Si-Tex radar, a 24-mile Si-Tex radar, Plath Navigator VIII autopilot, two Horizon 78 VHF radios, Raytheon Ray 350 loudhailer, Si-Tex 757 Loran C, Motorola Triton 40 SSB radio with Necode digital encoder/decoder, Magnavox satellite navigator, and Benmar RDF.

The Navasota's interior outfit has been constructed to a high standard, including mahogany trim in the pilothouse, staterooms, and galley as well as custom-built tables, uesks, Hydraulic steering system with cabinets. General workmanship throughout the vessel reflects this same high quality and attention to detail.

(continued on page 40)



## **ROLLING ON THE RIVER**

Alpha heavy fuel engines are the most reliable and economical engines rolling on the river today. Built exclusively for marine propulsion, they burn cheaper, lower quality fuel and less of it.

Tests conducted by Midland/Ohio River Company on its four big Alpha-powered towboats proved considerable fuel savings when using No. 2 Diesel compared to the latest versions of conventional two-stroke engines in its fleet. Beyond that, the Alpha engines are routinely used for heavy fuel **up to 3500 seconds Redwood No. 1.** 

Service and parts are readily available for these engines at strategic locations along the inland waterways, with immediate delivery on most items from our warehouse in Paducah, Kentucky.

Get the straight story from the people with the experience. Alpha — the right engines for today. And tomorrow.

ALPHA HEAVY FUEL ENGINES



INLAND WATER PROPULSION SYSTEMS, INC.

1400-580 Building, Cincinnati, Ohio 45201 (513) 721-4747 • TWX 810-461-2811



## **NEWPORT CLIPPER** Jeffboat

Jeffboat, Incorporated of Jeffersonville, Ind., recently completed the luxury cruise vessel Newport Clipper, first of its type ever built at the Indiana yard. Constructed for Clipper Cruise Line of St. Louis at a cost of about \$9 million, the vessel will operate on seven-day cruises in areas along the U.S. Eastern Seaboard.

The hull of the Newport Clipper is constructed of ½-inch steel plate throughout except for the bow and stern which are 3/8-inch plate. Gross tonnage is 100 and displacement 1,000 long tons. Overall length is 207 feet, beam amidships is 37 feet, and draft is  $7\frac{1}{2}$  feet.

Propulsion power is provided by two GM Detroit Diesel 12V-71 engines, each rated 480 bhp at 2,300 rpm, providing an average cruising speed of 10 mph. The engines drive, through two Twin Disc 4.13:1 reverse/reduction gears, two Columbian four-bladed, stainless steel propellers having a diameter of 48 inches and 39-inch pitch. The console-mounted steering system supplied by SSI has full follow-up control. An Omnithruster bow thruster is powered by a 200-hp electric motor.

Electric power is supplied by three 225-kw generators driven by Detroit Diesel 12V-71 engines. The sanitation system is an Omnipure model RM812-27 type II. Raw water heat exchangers for engine cooling are mounted on each propulsion and generator unit.

In addition to the usual VHF and SSB communications equipment, the vessel is fitted with two radars, satellite navigator, and Loran C, all manufactured by

Furuno.

The Newport Clipper's four passenger decks contain 51 staterooms, all outside and with large windows.

## **NICOR CLIPPER Moss Point Marine**

The Nicor Clipper, believed to be the largest offshore workboat ever built in the U.S., was delivered in the summer of 1983 by Moss Point Marine of Escatawpa, Miss., to Nicor Marine Inc. of New Orleans. The vessel has an overall length of 254 feet, beam of 44 feet, and depth of 16 feet. A unique stern ramp fabricated by the builder gives her roll-on/roll-off capability for carrying containers.

The vessel is powered by twin GM Electro-Motive Division 12-567C diesels, each with an output of 1,400 bhp at 835 rpm, linked to Falk reduction gears having a ratio of 2.968:1. Engine controls are by WABCO and engine monitoring by EMI. A Harbormaster BT-550 bow thruster will provide extra maneuverability around offshore structures. Electric power is provided by a set of 150-kw Delco generators supplied by George Engine Company.
The Clipper's capacities include

242,430 gallons of fuel oil, 24,780 gallons of fresh water, 1,300 barrels of liquid mud, and 6,000 cubic feet of dry bulk mud.

Electronic equipment, supplied nd installed by Marine Electron ics, include Furuno FR-1011 radars, Stephens SEA 106 and Sailor RT-144 radiotelephones, Texas Instrument TI 9000 Loran C, a Decca 801 satellite navigator, and Sperry gyrocompass and autopilot.





Deck equipment includes two McElroy towing winches and an HBL anchor windlass. Carlisle & Finch supplied the searchlights, Kalhenberg the air horns, and Hubbel the running and navigation lights.

The Nicor Clipper is classed by the American Bureau of Shipping and certified by the U.S. Coast Guard.



## NORTH SOUNDER **Gladding Hearn**

The North Sounder, said to be the largest self-propelled oil-spill skimmer in the U.S., was delivered in early 1983 by Gladding Hearn Shipbuilding Corporation of Somerset, Mass. The vessel is owned by Clean Sound, a nonprofit joint venture of 13 oil and oil transportation companies that was founded in 1971 to protect the waters of Puget Sound.

The vessel has an overall length of 73 feet, beam of 20 feet, fullload draft of 6 feet 3 inches, and displacement of 130 long tons. She is powered by twin Caterpillar 3408 DITA diesel engines, each rated 365 bhp at 2,000 rpm, linked to Twin Disc 3:1 reduction gears. Built at a cost of \$1.6 million, the vessel joins a fleet of smaller skimmers, auxiliary boats, and barges that Clean Sound has stationed at ports throughout Puget Sound. The latest addition to the fleet is stationed at Bellingham, Wash.

Main engines (2)	Caterpillar
Reduction gears (2)	Twin Disc
Propellers (2)	
Engine controls	. , WABCO
Generators	Northern Lights
Generator engines	John Deere
Steering system	Char-Lynn
Sanitation system	Microphor
Radar	Furuno
VHF radiotelephone	Cybernet
Depth indicator	Sandpiper
Crane	Scott
Windlass	Pine Hill
Oil-handling pump	Moyno
Coatings Cat	hacote, Devran

to recover 90 percent of an oil spill at rates up to 500 gpm. Its onboard recovered oil capacity is 12,000 gallons. When operating in the oil-spill recovery mode, the vessel's bow opens to reveal an escalator-like ramp leading from under the water surface and into the mid-hull area of the boat.

Several design changes developed by the Clean Sound staff have been incorporated into the Sound's new skimmer is a JBF

The North Sounder is designed North Sounder. The most signifi- model DIP 5001A. cant is an improved method of recovering oily debris. This system was designed to cope with materials such as logs, branches, kelp, eel grass, and other floating debris.

The North Sounder was designed by JBF Scientific Corporation of Wilmington, Mass. JBF has designed more than 100 oil-skimming vessels, including 50 harbor skimmers for the U.S. Navy. Clean

Because of her traditional hull design, the vessel can respond to oil spills at speeds up to 10.6 knots. During normal skimming operations, she runs at 1 to 2 knots in conditions up to Sea State 3. The vessel can work alone or with long containment booms attached to the bow in a "V" configuration to funnel oil slicks to the recovery system.

(continued on page 42)

## SEA CUSHIONS. The tough foam filled fenders with the soft touch. Whether you're a vessel owner or a

terminal operator, you need a fender that's not only tough, but soft enough to cushion and absorb the high energy impact of



ship to ship transfer or ship to quay berthing without hull damage or overloading of dock structures. That fender is appropriately named SEA CUSHION. And it's tough because we make it that way It's unsink-

able even if punctured. It's abrasion-resistant and extremely durable, because of its rugged elastomer skin. So if you have the need for some tough protection with a soft touch, SEA CUSHION is it. Sizes available for fishing vessels to ULCC's.

For more information contact Seaward International: Corporate Office, 6269 Leesburg Pike, Falls Church, Virginia 22044, USA. (703) 534-3500, Telex: 899-455. SEAWARD



#### North Sounder

(continued from page 41)

The recovery system consists of two conveyor units. The debris collection unit is a stainless steel conveyor that leads up to the debris collection equipment. The oilhandling unit is a powered, 37½foot-long by 6-foot-wide PVC belt that loads oil into the vessel's cargo tanks. The belt is driven by a Char-Lynn hydraulic motor. The dynamic inclined plane (DIP) conveyor is located in the forward half of the hull, behind the debris conveyor.

## **PEMEX 652** Matsumoto Shipyards

The aluminum-hulled fireboat Pemex 652 was delivered at mid-1983 by Matsumoto Shipyards of Vancouver, B.C., Canada to Pemex, Mexico's national oil company. This is the first of two sister ships of a new design ordered by Pemex for use in the extensive Gulf of Mexico oil tracts owned and managed by the company.



These two Pemex fireboats are among the largest in the world. Each contains about 170 tons of aluminum plate and 30 tons of aluminum extrusions supplied by Alcan Canada Products, Ltd.

The 500-gt Pemex 652 has an overall length of 150 feet, a beam of 32 feet and a height from the deck to the top monitor of 40 feet. Operating draft is 11.8 feet, cruising range is 250 miles, and top speed is 16 knots.

The vessel is powered by two MTU diesel engines, each with an output of 1,725 bhp at 1,400 rpm. Two Reintjes reduction gears transmit the power to the two Osborne propellers.

Twin Worthington pumps pow-

ered by separate 1,200-bhp MTU diesels are capable of drawing sea water, mixing it with a 3-percent AFFF foam solution, and spraying it onto fires at a rate of up to 25,000 gpm. The three main monitors (nozzles) manufactured by the Swedish Foam Fire Extinguishing Company can each handle 5,200 gpm. Cranes can position two more Stang monitors 75 feet above the water surface to handle 2,600 more gpm. The vessel carries 6,000 gallons of foam concentrate to mix with the water.

The hull of the fireboat is constructed of a special Alcan alloy that includes magnesium and manganese. Pemex specified aluminum because of its light weight and because the high superstructure of the vessel would have been impossible without it. Aluminum is also corrosion-resistant, even in salt water, so maintenance can be kept to a minimum.


In use, the fire-fighting power of the Pemex 652 is controlled from the bridge, which also contains the latest in navigation equipment,

radiotelephone, depth sounder, radar, loudhailer, engine controls, and hydraulic steering controls.

Schottel bow and stern thrusters enable the vessel to maneuver with ease. This permits precise station-keeping and allows the firefighting equipment to be positioned quickly and to the best advantage.

## **PEMEX 652**

Major Suppliers
Main engines (2) MTU
Reduction gears (2) Reintjes
Propellers (2) Osborne
Engine controls Kobelt
Pumping engines (2) MTU
Generator sets (2) Caterpillar
Thrusters (2) Schottel
Steering gear Wagner
Cranes & davits Kingsway
Anchor windlasses Harrison & Robbins
Pumps Jabsco, Paramount
Rotoking, Worthington
Internal fire-fighting (Halon) Svenska
Inflatable rafts Beaufort
Radar, echosounder, gyrocompass .Sperry
VHF & SSB Canadian Marconi
Fenders Seaward
Coatings International Paint



## **ROWAN GORILLA I** Marathon LeTourneau

The Rowan Gorilla I, largest offshore jackup drilling rig ever built, was delivered in December 1983 by Marathon LeTourneau to Rowan Companies, Inc. of Houston. Designed by Marathon and built at its Marine Division in Vicksburg, Miss., it is the first of the new Gorilla Class jackup designed for operating in hostile offshore


Because of restrictive bridge clearances, the rig was towed from Vicksburg to Belle Chasse, La., minus its full length of legs and its drilling derrick. After final outfitting the rig left Belle Chasse under tow of the Chignecto Bay and the Mahome Bay (photo), 11,000-bhp vessels that will serve the rig as both tugs and supply

The Rowan Gorilla I is scheduled to begin its first drilling assignment offshore eastern Canada in mid-January for a consortium of Canada-based oil companies including ATS Exploration Ltd., Bow Valley Industries, Ltd., and Husky Oil Operations Ltd.

Fully outfitted with its three (continued on page 46)

## **Proved Engineering and Dependability**

stand behind the world's finest shipboard windows, windshield wipers and doors by...



De-icing,

Window

Kearfott products are quality constructed to meet requirements of A.B.S., U.S.C.G. and Navy standards.

Kearfott windows and doors can be manufactured in various sizes, shapes and materials.

Catalog showing complete line of marine products furnished upon request.

Kearfott

a division of The SINGER Company

550 S. Fulton Ave., Mount Vernon, N.Y. 10550 Phone 914-664-6033 Telex 133440

Circle 134 on Reader Service Card

**24 HRS** 

Hinged Portlight

## IPR JIM'S PUMP REPAIR INC.



48-55 36th STREET, LONG ISLAND CITY, NEW YORK 11101

JIM LAGONIKOS, President Established 1974 Bob Mooney, Sales & Service Mgr.

**Reconditioned Coffin & Pacific Feed Pumps** 

A-1 Condition Service

Clear View


Parts Available TYPE • F-CG - DE - DEB - IND - T TLX-TWX

212-392-4444 TBA • 12 - 16 - 16½ **710-5824847JPRNYK** SERVICE - GULF AND WEST COAST

24 Hrs. Service

VI-CORE INC. - Ivo Dabelic

713-643-7715



# Set your sights on Southwest Marine

The very moment you select Southwest Marine for your ship's repair or modernization project, we will assign a Personalized Project Coordinator to you and your ship. His sights are set on accelerating the Southwest Marine repair team into action and coordinating all of the elements to assure a ready ship on time and on budget.

We have three yards on the west coast to serve you. Each location provides total service capability including full shop services. Southwest Marine has dry docks up to 45,000 DWT, pier service up to 1500' and mobile gantry cranes with up to 65 ton capacity.


Our full service program includes

our unique "we'll come to you" and our "ride along" services, meaning we can perform most of our yard services at your site or we can work on ship while at sea. Our experienced and dedicated team has solved every conceivable repair problem and has designed and delivered thousands of unusual modernization projects. So whatever unique or normal situations you may have, the Southwest team has probably done it before.

Find out more about Southwest Marine and send in for our series of capability and indepth yard brochures, or call our Manager of Sales and Marketing, Al Shapiro, at (619) 238-1000 today.

Yes, please send me your series of capability and indepth yard brochures.

Name		Title
Company		
Address		STATE OF THE PARTY
City	State	Zip
Phone		
Mail to: Southwest Mari	ing Ing DO Box 19909 San Diag	CX 02112



501年刊记言ST MARINE, INC.

SPECIALISTS IN THE REPAIR, MODERNIZATION & MAINTENANCE OF SEAGOING VESSELS

SAH DIEGO YARD Southwest Marine, Inc. Foot of Sampson Street P.O. Box 13308 San Diego, CA 921 (619) 238-1000 TWX 910-335-1167

SAH PEOBO YARD Southwest Marine, Inc. 985 S. Seaside P.O. Box 3347 Terminal Island, CA 90731 (213) 519-0600 TWX 910-345-6638

SAN FRANCISCO YARD Southwest Marine of San Francisco, Inc. P.O. Box 7644 (Pier 28) San Francisco, CA 94120 (415) 543-0499

## **SHIPYARDS** AND THE JONES ACT

Herman J. Molzahn, Vice President—Shipyard Operations **American Waterways Shipyards Conference of the American Waterways Operators, Inc.** 



Herman J. Molzahn

When President Reagan was campaigning for office in 1980, he said, "Should our shipbuilding capacity continue to decline, American mobilization potential will be seriously undermined because a large reduction in a skilled shipbuilding workforce today makes any increase tomorrow very difficult. This is a dangerous threat to our national security, jobs, and a key U.S. industry.

Sitting on the President's desk when he took office was a report from the conservative Heritage Foundation addressing national maritime policy. Among the suggestions made by this group was a recommendation to acquire foreign ships for subsidized U.S. operation. It further suggested that Jones Act trades be opened to foreign-flag ships.

The first suggestion, to allow subsidized U.S. operators to acquire foreign-built vessels, has been implemented and the damaging result to the major shipyards is all ported overseas.

other promise from the Adminis-

tration. The then Secretary of Transportation, Drew Lewis, announced the initial elements of the Reagan Administration's National Maritime Policy, and therein, the sanctity of the Jones Act was affirmed. Everyone hoped that this statement would introduce a new element of long-term stability into the Jones Act, which is extremely important to those who serve the domestic trades.

This stability is again being threatened, for at the November 1983 Annual Meeting of the Society of Naval Architects and Marine Engineers (SNAME), Warren G. Leback, Deputy Administrator of the Maritime Administration, Department of Transportation, coauthored a heavily annotated paper titled "The Jones Act: Foreign Built Vessels and the Domestic Shipping Industry." The paper os-tensibly expresses the personal views of the authors that foreignbuilt ships be allowed to participate freely in the U.S. domestic trades. The authors argue that .. if the domestic ship-building industry is competitive with foreign shipyards, (the entry of foreign-built ships into the Jones Act) would have no adverse effect on that industry.'

Further, they propose constructing a fleet of break-bulk vessels over a ten-year period to sustain the shipbuilding base. They recommend that: "A program for constructing twenty vessels per year for the ten-year period would support four major shipyards. These, coupled with the five major shipyards in naval construction, would provide the shipbuilding base.'

Edward Renshaw, Chairman of the Board, St. Louis Ship, and a past Chairman of the American Waterways Shipyard Conference too clear-that segment of the (AWSC), challenged these propos- we often lose sight of the basics shipbuilding industry has been ex- als. In his discussion paper which which are necessary for our naorted overseas.

he presented at the SNAME Antional survival. The shipbuilding on May 20, 1982, we heard antiher promise from the Administration of the shipbuilding which provide the stated, "During World War II, St." which are necessary for our national survival. The shipbuilding industry must take a stand to presented at the SNAME Antional survival. The shipbuilding industry must take a stand to presented at the SNAME Antional survival. The shipbuilding industry must take a stand to presented at the SNAME Antional survival.

Louis Ship built L.S.T.'s and tugs for the war effort. We were but one of the scores of small inland. river, coastal, and Great Lakes shipyards deeply involved.

This was not the only attack on the Jones Act in recent years. Legislators on Capitol Hill have been barraged by various interests to give legislative exemptions from the Jones Act for the carriage of passengers, iron ore, coal, petroleum, liquid natural gas, lumber, and other commodities on foreignflag ships. Applications for waivers have been submitted to the federal agencies so that foreignflag ships could operate on a temporary basis. And the AWSC has uncovered and blocked attempts to bring foreign-built barge sections into the United States for final assembly.

The "Jones Act" is used inaccurately to refer to the entire body of U.S. cabotage or coastwise laws which limit, in various ways, the right to engage in the maritime commerce of the United States. However, the Jones Act applies only to the transportation of "mer-chandise," not people. Other coastwise laws pertain to the carriage of passengers and to towing, fishing, and offshore services on the outer continental shelf.

From the very beginnings of our existence as an independent nation, the United States has adopted a policy of reserving its domestic trade for its own ships. The basic principles that guided our forefathers are still valid today. A strong domestic merchant marine and shipbuilding base should be promoted for the economic good of the country and as an adjunct to national security forces.

Special interests are pulling this country in so many directions that

cornerstone for its existence. This cannot be done by the actions of several companies acting individually. It must be accomplished, if at all, by those companies joining forces to take coordinated actions against attacks on the industry.

One such organization exists for the smaller U.S. shipbuilders. It is the American Waterways Shipyard Conference, formed in 1976 by a group of shipyard executives. After the 1972 amendments to the Longshore Act were passed, they were convinced that the days of 'each yard for itself" were over.

The smaller or second tier shipvards have the most to lose if the U.S. built provisions of the Jones Act are abolished. Not another tugboat, towboat, crewboat, supply boat, barge or any other small vessel would be built in the United

This complex network of laws makes this second tier of the shipbuilding industry possible in today's climate of foreign-subsidized or government-owned shipyards. A quote from Theodore Roosevelt never had more meaning than it does today for this segment of the shipbuilding industry represented by the American Waterways Shipyard Conference: "Every man owes a part of his time and money to the business or industry in which he is engaged. No man has a moral right to withhold his support from an organization that is striving to improve conditions within his sphere.

The major shipyards have lost their commercial business. Will the same thing happen to the smaller yards? Not if the ship-yards realize that there is strength in numbers and support their trade association which is waging the battles to preserve the industry.



## George Curry Appointed President Of Henschel



George U. Curry

Henschel Corporation of Amesbury, Mass., a unit of General Signal, has announced the appointment of George U. Curry as president. He succeeds George E. Coorssen, who has retired.

Mr. Curry is a graduate of Purdue University and joined Henschel in 1954. He is an electrical engineer and has held several positions with the company, including vice president of engineering since 1966. He is a member of The Society of Naval Architects and Marine Engineers, American Society of Naval Engineers, and the Marine Transportation Committee of the IEEE.

Henschel Corporation is a leader in the design, development, and manufacture of ship control and interior communications equipment and systems.

## New Brochure Available From IMO Pump Division Of Transamerica Delaval



IMO Pump Division of Transamerica Delaval Inc., has just published a new 14-page illustrated brochure on their line of IMO® three-screw and GTS® geared, twinscrew marine cargo pumps.

IMO three-screw pumps are intended for dedicated barges and tankers. They can handle cargoes from JP-5 and light diesel oil to molasses, tars, and heavy asphalts, with flows up to 3,500 gpm (5,000 bbl/hr).

GTS (Geared Twin Screw) pumps are designed for multi-cargo vessels where maximum cargo versatility is required and tanks are frequently Butterworthed. Cargoes can range from water solutions and other chemicals with the lightest viscosity to heavy asphalts and tars. Capacities range upwards to 8,500 gpm (12,000 bbl/hr)

For a free copy of the new brochure,

Circle 39 on Reader Service Card

Circle 137 on Reader Service Card ▶

## Southwest Marine Gets \$20.8-Million Contract For Navy Oiler Maintenance

Southwest Marine, San Francisco, Calif., is being awarded a \$20,852,111 cost-plus-award-fee contract for the AOR-1 Class phased maintenance program. The Naval Sea Systems Command, Washington, D.C., is the contracting activity.

## Krupp MaK Establishes Canadian Subsidiary In Halifax And Montreal

Krupp MaK Maschinenbau GmbH, a leading diesel engine builder, recently established Krupp MaK Canada Inc. in Dartmouth near Halifax, Nova Scotia. This is the company's second subsidiary in North America; the other is Krupp MaK Diesel Inc. in Glenview, 1ll., near Chicago.


Krupp MaK has gained such a market share of medium-speed diesels for marine propulsion sold in Canada that the company decided to expand its service and spare parts organization. Nearly 150 MaK engines are operated in Canada, mainly on the East Coast; in 1983 alone 24 engines were delivered to that area.

In addition to the service center in Halifax, MaK will establish a sales office in Montreal.

## FOR WORK BOATS

## longer engine life... lower running costs





# Workboat engines shouldn't have to retire early. With Westfalia Oil Purifiers, they don't.

Westfalia Oil Purifiers remove abrasive solids and corrosive liquids—including seawater—from fuel oil. So they stay out of your engine, and your engine stays out of trouble. With clean fuel, you get optimum combustion and reduced wear…longer engine life.


Same thing for lube oil. Westfalia Oil Purifiers clean out metal particles, dust, water, carbon, acids—all harmful contaminants. Engine

downtime drops...plus you can recyle your lube oil over and over again.

Add it up, Longer engine life, reduced maintenance, re-usable lube oil—a major saving in running costs.

Westfalia Take-Down and Self-Cleaning Oil Purifiers give you highest reliability, top performance. For work boat engines especially, check out our low-cost OTA Take-Down models—for economy, efficiency, and ease of cleaning that can't be matched. Not in your engine's lifetime.

Call us for details.




#### Rowan Gorilla I

(continued from page 42)

507-feet-tall legs and 160-feet-tall drilling derrick, a Gorilla rig comprises approximately 16,000 tons of steel. Its triangular hull is 297 feet long, 292 feet wide, and 30 feet deep. The rig's large size provides nearly one acre of deck space for storage of consumables used during drilling. This ample storage capacity along with certain design features make the rig compatable with hostile offshore areas where it can continue to drill even if the flow of supplies from shore were interrupted.

Classed +A1 by the American Bureau of Shipping and built in accordance with Mobile Offshore Drilling Unit Regulations established by the U.S. Coast Guard, Canadian Coast Guard, U.K. Department of Energy, and Netherlands Department of Mines, the Gorilla rig is designed to survive up to 90-foot waves and 82-knot winds while drilling in 328 feet of water.

The rig has power to spare, with seven Caterpillar D399 diesel engines with a total output of 11,080



bhp at 1,225 rpm driving seven generators producing a total of 7,210 kw. Power for the Gorilla's propulsion assist system is provided by eight electric motors with a total output of 6,800 hp connected through gearboxes to two 112-inch propellers in Kort nozzles. These motors are mounted on the machinery deck on either side of the drilling slot. When using a 10,000-bhp tug, the assist thrusters will increase the towing speed by about two knots.

Living accommodations are provided for 80 persons, as well as a six-bed hospital, dual galley, dining room, and recreation facilities. The rig's survival system consists of two 50-man and two 34-man Whittaker enclosed capsules, U.S. Coast Guard approved and fitted with internal communications systems. A heliport cantilevered out over the bow has a diameter of 83 feet and 52,500-pound impact load.

Two other Gorilla Class rigs are now under construction, one at Marathon's rig yard in Singapore and one at the Vicksburg yard.

## SANTA FE RIGS Daewoo Shipbuilding

Daewoo Shipbuilding and Heavy Machinery Ltd. in Korea delivered in the last quarter of 1983 a second semi-submersible drilling rig to Santa Fe Drilling Company of Orange, Calif. Both Santa Fe rigs self-propelled, Friede and Goldman L-907 Pacesetter types, and were constructed at a price of \$80 million each. These rigs are capable of 25,000 feet in water depths up to 1,500 feet. Living quarters are provided for 96 persons.

Since opening a little more than 170 by 170 feet. It has living quar-

two years ago, Daewoo's Okpo Shipyard has delivered eight drilling rigs of two types. In addition to the two built for Santa Fe Drilling, the yard has constructed two semi-submersibles for Reading & Bates Drilling Company of Houston, and one each for Houlder Offshore Drilling Company and Atlantic Drilling Company, both of the U.K.

A semi-submersible rig for Korea Drilling Company is now under construction at the Okpo yard. With this rig's delivery in the spring of 1984, Korea Drilling will be the first Korean company to own a drilling rig it operates. The rig will be used to explore Korea's continental shelf and other national coastlines.

## **SEDCO 602 Promet Private Ltd.**

A medium-sized, semi-submersible drilling rig, the Sedco 602, was delivered recently by Promet Private Limited shipyard in Singapore. The rig is owned jointly by Sedco, Inc. of Dallas and Occidental Exploration & Production Company of Bakersfield, Calif., and Houston.

Designed by Earl & Wright, the Sedco 602 can operate in water depths of 25 to 180 feet. The mooring tensioner riser and drill fluid systems have been designed for exploratory and development drilling to 20,000 feet. The design of this semi-submersible makes it particularly useful in parts of the world where drillships are inefficient and the cost of using huge semi-submersibles uneconomical.

The rig's main deck measures



ters for 88 personnel; other accommodations include a hospital and a recreation room with cinema area. Sophisticated equipment on board includes a closed circuit television system and a satellite communications installation. The rig is fitted with two cranes having booms of 100 feet and lifting capacities of 50 tons. A helideck can support the weight of a fully loaded Sikorsky S-61N helicopter.

The Sedco 602 is classed by the American Bureau of Shipping and is built to requirements of the U.S. Coast Guard and the Intergovernmental Maritime Organization. It began operating in the Philippines and will then go to China. This rig is the third semi-submersible built by Promet; in the first half of 1983 the Singapore yard delivered two similar rigs of the Sedco 600 series.



## SEDCO 712/714 Hyundai Heavy Industries

Seven semi-submersible drilling rigs were delivered to Sedco Inc. of Dallas between November 1982 and July 1983. Delivery of these new offshore rigs brought the Sedco drilling fleet up to 42 units; the company reported that all rigs were under contract.

Four of the Sedco 700 Class and three of the Sedco 600 Class were delivered by three shipyards in the Far East. The first of the new deliveries, the Sedco 711, was completed in November 1982, just 24 months after the order was placed with Hyundai Heavy Industries of Ulsan, Korea. The Sedco 712 and the Sedco 714 were also built at Hyundai—the first time in Sedco's history that three of its rigs have been under construction at one shipyard at the same time.

Total contract value for the three (continued on page 48)

## NOW IN STOCK

· MIL-C-2212 Motor Starters · MIL-S-17773 Automatic Bus Transfer Switches Commercial Marine Motor Controls - Contactors, Relays & Replacement Parts

Now there's no need to put up with long factory deliveries on A.C. Motor Starters and Bus Transfers for shipboard use. Our Navy/Marine Control Distributors now stock a larger assortment of popular sizes to meet MIL and I.E.E.E. 45 specs. They also carry a wide selection of control relays and replacement parts for magnetic contactors.

So make it easy... just call our nearest Stocking Navy/Marine Distributor in your area.

Emeryville Beck Electric Supply National City Potter Electric Inc San Leandro Benkiser Electric Motors Wilmington California Marine Supply	415-652-5665 714-474-8171 415-638-8262 213-435-8224
Jacksonville Ace Electric Supply Co	904-396-5101
New Orleans Long Electric Supply Co	504-524-8383
Iron Mountain Z & R Electric Service	906-774-0468


New York Argo International Corp	212-431-1700
Portland Apollo Marine Service Inc	503-286-3693
Charleston Ace Electric Supply Co	803-552-7342
Virginia BeachB & D Electric Supply Inc.	804-460-2479
Seattle Beck Electric Supply	206-763-2011







## HORSEPOWER



#### SEDCO 712/714

(continued from page 46)

rigs was \$330 million. Upon delivery each of these three rigs began five-year drilling contracts; the Sedco 711 is working for British Petroleum.

The Sedco 700 Class rig is designed to withstand the harsh conditions of the upper North Sea where drilling operations continue in 40-foot waves and 50-knot winds. These self-propelled units can withstand 100-foot waves.

Of the remaining four Sedco semi-submersibles, three were built by Promet (Pte.) Ltd. in Singapore and one at Mitsui Engineering & Shipbuilding Company in Japan.

## TRINITY RIVER Eastern Marine

Eastern Marine, Inc. of Panama City, Fla., in early 1983 delivered the supply vessel Trinity River to Transportation Resources, Inc. of Houma, La. The vessel is the fourth in a five-vessel contract; the sister



River, Roaring River, and Tellico

The Trinity River has an overall length of 166 feet, beam of 38 feet, depth of 13 feet, and loaded draft of 11 feet. A clear deck cargo area 110 by 28 feet can carry up to 550 long tons of supplies.

The vessel is powered by two GM Detroit Diesel 16V-149 engines delivering a total of 1,800

vessels are the Leaf River, Pine bhp at 1,800 rpm through Twin Disc reduction gears. She can achieve a speed of more than 12 knots. A Schottel S-152L bow thruster is driven by a GM Detroit Diesel 8V71 engine with an ouput of 230 bhp at 1,800 rpm.

Electric power is provided by two Delco 85-kw generators driven by Detroit Diesel 6V71 engines. Electronic equipment includes Furuno radar, Stephens SSB radio, Cybernet International VHF radio, Micrologistics Loran C, and Impulse depth indicator.

Eastern Marine is a growing company that has earned a reputation in recent years as a builder of high-quality vessels. The company opened its Panama City yard in 1978. This 13-acre facility has more than 1,300 feet of water frontage, and is used primarily to construct small- to medium-sized boats. In 1981 Eastern Marine opened another yard in Allanton, Fla., 15 miles east of Panama City. This second yard, with 135 acres and 5,200 feet of water frontage, is used to build larger vessels.

In addition to the Transportation Resources vessels, Eastern Marine received a contract from Seahorse Inc. of Morgan City, La., to build eight 192-foot anchor-handling/tug-supply vessels at the Allanton yard.

## **Bell Aerospace Awarded** \$4.8 Million By Navy To Speed LCAC-1 Delivery

Bell Aerospace Textron, New Orleans, has been awarded a \$4,822,852 face value increase to a previously awarded cost-plus award-fee contract for acceleration in delivery of an air cushion landing craft (LCAC-1) by two and one half months. The Naval Sea Systems Command, Washington, D.C., is the contracting activity.

## Charles Garman Named Western Sales Manager For Stork-Werkspoor

Charles A. Garman has been named as Western area sales manager for the U.S. by Stork-Werkspoor Diesel by (SWD). Mr. Garman has opened an office in Seattle and will cover the Western U.S. and Alaska for the firm. SWDiesel engines are offered in models ranging from 300 to 2,000 bhp specially designed to operate on both high grade distillate fuels, and on heavy and lower grade fuels.

SWDiesel began operating in the U.S. in 1983, establishing a sales and service office in New Orleans and assigning an SWDiesel executive, Joop Zwart, as sales manager for the North American continent. Mr. Zwart is dividing his time between the U.S. and the SWDiesel home office in Zwolle, Netherlands.

Mr. Garman, who was educated in engineering and business at Everett Community College and the University of Washington, previously was West Coast sales manager for Wartsila Power U.S.A., and director of marketing from Tacoma Boat Building, Inc.

The SWDiesel office has been established at 2405 N.W. Market Street, Seattle, Wash. 98107; telephone (206) 789-8383.



**FUEL MANAGEMENT SYSTEM** For \$5500.00

Includes Powerpack, CRT, keyboard, all hardware and Designed for vessels up to 12,000 BHP REMOTE **DEPTH SOUNDER** 

For \$2800.00 w/o speed


\$3300.00 w/speed

Transmitter Box plugs into 115v AC or 12v DC at the front of the tow

2100 N. HWY. 360 ● GRAND PRAIRIE, TEXAS 75050 ● 214/660-1106 ● Telex 79 5551

Circle 141 on Reader Service Card





## Omnithruster Establishes New Manufacturing Facility In Canada —Literature Available



PV/JT1100, 1,000-hp module thruster.

Omnithruster Inc. has recently established a Canadian manufacturing facility in Sarnia, Ontario. The new Mark II Omnithruster series and Omnithruster ice lubrication systems will be fabricated at that plant.

Omnithruster president Charles M. Aker said: "The equipment is to be produced from Canadian raw materials and with Canadian labor. The only components to be furnished from our plant in Santa Fe Springs, Calif., are the control systems. These will be installed during the final assembly and the complete system will be tested prior to shipment from the Sarnia facility."

Omnithruster manufactures a complete line of hydrojet maneuvering, propulsion, and ice management systems ranging from 50 to 3,000 horsepower in single units. Systems are installed in ships worldwide, including tankers operated by Shell Canada, Imperial Oil, and Exxon; in barges operated by Chevron Canada and A.B. McLean; in Gulf Canada icebreakers; and in geophysical vessels, fishing boats, etc.

Omnithruster-Canada will coordinate its



manufacturing, installation, and repair activities through commercial offices located in Sarnia as well as in Montreal and Vancouver.


For further information and free literature,

Circle 36 on Reader Service Card

## Propulsion Systems Introduces New Line Of Trawl Winches— Literature Available

Propulsion Systems, Inc. of Kent, Wash., recently introduced six new trawl winch models. The new product line includes net reels and fully automated electronic controls.

The winches start at model R-625 for 1,000 fathoms of 5/8-inch cable and extend up to model R-1250 for 1,000 fathoms of I<sup>1</sup>/4-inch cable. The automated controls feature synchronized cable tension monitoring between the



two winches to maintain optimum net position during conditions such as heavy seas, vessel maneuvers, and in the presence of underwater currents.

For further information and free literature,

Circle 38 on Reader Service Card



爾

Around the clock. Turecamo's modern fleet of fast, powerful tugs stand ready to instantly provide you with the very best in towing services. Added to this are the years of invaluable experience docking and undocking ships of all sizes and in every phase of towing operations.

When you want fast, efficient and economical service...Call Turecamo First.

DOCKING • UNDOCKING — harbor, sound, coastwise, canal and lake towing

## TURECAMO COASTAL & HARBOR TOWING CORP.

P.O. BOX 201 OF STAT TEL: (212) 442-7400

ONE EDGEWATER STREET STATEN ISLAND, N.Y. 10305

MATTON TRANSPORTATION CO. INC TURECAMO TRANSPORTATION CORP

MATTON SHIPYARD CO., INC. TURECAMO TANKERS INC

January 1, 1984

Circle 140 on Reader Service Card

49

## **PROFESSIONAL**

**NAVAL ARCHITECTS** 

MARINE ENGINEERS



#### **TUG BARGE CONNECTION EQUIPMENT**

344 Camp Street Suite 1000 New Orleans, LA 70130

Tel: (504) 524-6777 Telex: 584248 Int'l Telex: 6821166

A Division of ACB Industries, Inc.

## **Adams & Chute**

**NAVAL ARCHITECTS & MARINE ENGINEERS** 

203-426-7135 HUNTINGTOWN ROAD, NEWTOWN, CT 06470



naval architecture management sciences marine and ocean engineering

> 1725 jefferson davis highway arlington, va 22202 (703) 979-9200

san diego, ca (619) 223-5396

virginia beach, va (804) 490-2359

philadelphia, pa (609) 482-2620

## ~AmSEC

## AMERICAN SYSTEMS ENGINEERING CORPORATION

Marine Engineers = Port Engineer Services
Systems Analysts = Propulsion Plant Training
Qualified Manufacturer's Field Representatives

P.O. Box 4265 - Virginia Beach, VA 23454 - 804/463-6010 Philadelphia, PA - Pascagoula, MS - Virginia Beach, VA Rosslyn, VA - San Francisco, CA

## AMIRIKIAN ENGINEERING CO.

HARBOR AND DRYDOCKING FACILITIES FLOATING LIFT DOCK AND SHORE TRANSFER CONCEPTS, DESIGN, INVESTIGATIONS

Chevy Chase Center Office Bldg. Suite 505, 35 Wisconsin Circle Chevy Chase, Md. 20015 (301) 652-6903

NAVAL ARCHITECTS MARINE ENGINEERS



## ART ANDERSON ASSOCIATES

Bremerton, WA

(206) 479-5600 Washington, D.C.

Captain Astad Company, Inc. Complete Marine Services - Full Broker Service Owners Representative Service Purchase & Sale of All Types of Vessels CAPTAIN A. J. ASTAD P.O. BOX 53434 NEW ORLEANS, LA 70153 PHONE (504) 529-4171 (24 HRS.)

## Ocean Engineering Centre SHIP-MODEL TESTING

- Resistance Tests
   Wake Surveys
   Towed Directional Stability Evaluations
   Seakeeping



### B.C. Research **Ocean Engineering Centre**

## DEL BREIT INC.

MARINE ENGINEERING CONSULTANT

326 Picayune Place Suite 201 New Orleans, La. 70130

(504) 523-2801

#### coi marine company



#### **NAVAL ARCHITECTS** MARINE ENGINEERS

CHARLESTON, S.C. (803) 554-5580

JACKSONVILLE, FL (904) 724-9700

HAMPTON, VA (804) 627-4384

SAN DIEGO, CA (714) 474-3317

WASHINGTON, D.C. (703) 521-2452 PHILADELPHIA, PA (609) 772-0800

BOSTON, MA (617) 878-8340 SEATTLE, WA (206) 575-3065 CHESAPEAKE, VA (804) 543-4211 PASCAGOULA, MS (601) 762-0098



## **C.T. MARINE**

NAVAL ARCHITECT . MARINE ENGINEER

18 Church Street, Georgetown, CT 06829 TUGS Telephone: 203-544-8110 Telex: ITT 4994761 TOWBOATS

## CADCOM® a division of ManTech International Corp.

COMPUTER-AIDED DESIGN AND CONSTRUCTION ENGINEERING SERVICES AND SYSTEMS 107 Ridgely Avenue, Annapolis, Maryland 21401 (301) 268-9010 (Wash.) 261-1070

## Phillips Cartner & Co., Inc. Marine & Naval Engineering and Consulting

- Economic Analysis
- Feasibility Assessment
- Surveys and Investigations
- Strategic Planning
- Engineering and Design Market & Trade Evaluations
- Owner and Investor
  - Representation
- Technology Evaluation

203 South Union Street 703/684-2060

Alexandria, VA 22314 Telex: 89-2407

## Century Engineering, Inc.

CONSULTING ENGINEERS

PLANNERS

#### INTERNATIONAL EXPERIENCE

SHIPYAROS • PORT FACILITIES • DREDGING • GRAVING OOCKS CERTIFICATION . INSPECTION . CONSTRUCTION MANAGEMENT

## BALTIMORE :

32 WEST ROAD TDWSON, MARYLAND 21204 301-823-8070 TELEX 8-7491

## ANCHORAGE:

500 L. STREET. SUITE 200 ANCHORAGE. ALASKA 99501 907-276-1248 907-276-0051 TELECOPIER



#### CHILDS ENGINEERING CORPORATION

Waterfront & Structural Engineering • Diving Inspection Box 333/Medfield/MA 02052

(617) 359-8945

## ihomas Coudon **Associates**

Marine Equipment Sales 6655 Amberton Drive Baltimore, Md. 21227 (301) 796-2525



#### CRANDALL

DRY DOCK ENGINEERS, INC. Railway and Floating Dry Docks Waterfront Structures ● Consulting
Design ● Inspection

Dry Dock Hardware and Equipment Pottery Lane Dedham, MA. 02026 Tel. (617) 329-3240 Telex: 924406 21 Pottery Lane

## *crane*

15301 1st Ave. So. Seattle, Washington 98148 (206) 246-7962 TWX 910-444-2085 Crane, hoist, materials handling specialists



#### FRANCIS B. CROCCO, INC.

Marine Consultants, Marine & Cargo Surveyors "Forty years of Surveying Experience in the Caribbean" Phone: (809) 723-0769 BOX 1411, SAN JUAN, PUERTO RICO 00903 Telex RCA 325 2634 PRCA 385 9005

## C. R. GUSHING & CO., INC.

NAVAL ARCHITECTS, MARINE ENGINEERS & TRANSPORTATION CONSULTANTS ONE WORLD TRADE CENTER NEW YORK, N.Y. 10048

TEL: (212) 432-0033

ENGINEERING

#### MARINE **VIBRATION ANALYSIS NOISE CONTROL**

253 Winslow Way West, Bainbridge Island, WA 98110 (206) 842-7656

Measurement, recording and analysis of mechanical, structural and electrical phenomena.



CABLE: CUSHINGCO

## DESIGN ASSOCIATES, INC.

M. KAWASAKI

14360 Chef Menteur Highway New Orleans, Louisiana 70129

Naval Architects Morine Management Phone: (504) 254-2012

Marine Engineers Transportation Consultants TWX 810-951-5317



Maritime Reporter/Engineering News



## **DESIGNERS & PLANNERS, INC.**

**NAVAL ARCHITECTS • MARINE ENGINEERS** 

1725 JEFFERSON DAVIS HGWY (Suite 700) ARLINGTON, VA 22202 (703) 892-8200

701 B Street (Suite 320) San Diego, CA 92111

(619) 238-0666

1415 Route 70E (Suite 106) Cherry Hill, NJ 08034 (609) 795-1170



## ENGINEERING COMPUTER OPTECNOMICS

Ship Design and Engineering Ports, Waterways and Offshore Facilities Military and Defense Systems Economic and Environmental Analysis Computer Analysis and Data Management Ship Simulation Ship Brokerage & Owner Representative

## ECO Inc.

1036 Cape St. Claire Center, Annapolis, Md. 21401 \_(301) 757-3245\_



CONSULTANT SERVICES

Marine Structures • Engineering Analysis • Marine Survey Project Management . Loss Prevention . Naval Architecture

> P.O. Box 7760 • Beaumont, Texas 77706 (409) 866-9158



## EXPRESS

ENGINEERING INC. Background & ingenuity equals solid engineering Marine Engineering • Ocean Engineering Naval Architects

4122 87th Ave. N.W.

(206) 265-3044

CHRISTOPHER J. FOSTER, INC. WORLD-WIDE EXPERIENCE AS DESIGNERS OF
GRAVING DOCKS • MARINE STRUCTURES
SHIPYARDS • MODERNIZATION • PORT FACILITIES
OFFSHORE TERMINALS • FLOATING DRYDOCKS
MARINE ENGINEERS • NAVAL ARCHITECTS
CONSULTING ENGINEERS
PORT WASHINGTON NEW YORK 11050
(516) 883-2830 TELEX 14-4674 CABLE: "CEFOSTA"

FRIEDE AND GOLDMAN, LTD. Naval Architects & Marine Engineers SUITE 2100, 935 GRAVIER STREET NEW ORLEANS, LA. 70112

## GIANNOTTI & ASSOCIATES, INC.

523-4621

NAVAL ARCHITECTS • MARINE & OCEAN ENGINEERS



(301) 268-0030

Berkeley, California (415) 841-5875

Arlington, Virginia (703) 892-2360

Houston, Texas (713) 987-0117

## GIBBS & COX INC

### **NAVAL ARCHITECTS & MARINE ENGINEERS**

119 West 31st Street . New York, N.Y. 10001 (212) 613-1300

### JOHN W. GILBERT ASSOCIATES, INC.

Naval Architects



Marine Engineers

66 LONG WHARF

Brokerage BOSTON, MASS. 02110

(617) 523-8370

Naval Architects Marine Engineers Ocean Engineers

Seattle, WA 206-624-7850 Telex: 32-1226

#### THE GLOSTEN ASSOCIATES, inc

Phillip Gresser Associates Ltd.


MARINE ENGINEERS CONSULTANTS & SURVEYORS

3250 SOUTH OCEAN BLVD

TEL: (305) 586-0813 PALM BEACH FLORIDA 33480

#### MORRIS GURALNICK ASSOCIATES, INC.

Naval Architects and Marine Engineers San Francisco, California (415) 543-8650



Naval Architects - Marine Engineers - Marine Consultants

TWO WORLD TRADE CENTER Suite 9528 • New York, N.Y. 10048 212-938-2100

Moorestown, N.J. 609-234-3880 Cohasset. Mass. 617-383-9200 Arlington, Va. 703-920-3435 Portsmouth, Va. 804-399-4097 San Diego, Ca. 619-283-2319



P.O. Box 226

Buckingham, Virginia 23921 (804) 969-4264

- Underwater Explosion Shock Testing (MIL-S-901) Fixture Design and
- Fabrication R & D Support
- East & West Coast
- Test Program Management
- Field Testing with Craft & Engineering Support
- Pitch and Roll Simulation to

HOFFMAN MARITIME CONSULTANTS INC.
NAVAL ARCHITECTS & MARINE ENGINEERS-SPECIALIZING IN

Helm® Onboard Monitoring & Guidance Systems • Vessel
Performance & Route Analysis • Wave Data Analysis & Climatology • Port Vessel Traffic Management Systems • Vessel
Casualty Simulation & Analysis 9 GLEN HEAD ROAD, GLEN HEAD, NY 11545 (516) 676-8499 TWX 510 223-0646





## R. D. Jacobs and Associates

Naval Architects • Marine Engineers Consulting Engineers

MARINE AND STATIONARY PROJECTS

Marine Surveyors; Project Specifications and Designs; **Energy Efficient Concepts** 

> Owner Representation Services; Machinery Casualty Investigations; Practical Engineering Economics Analyses

11405 MAIN ST., ROSCOE, IL 61073 815-623-6760

#### Jantzen Engineering Co., Inc.

**Consulting Engineers** Ocean Mining and Dredging (301) 796-8585

6655 Amberton Dr.

Baltimore, Md.

## FRANK JEFFREY & ASSOC.

Specializing In:

MARINE ELECTRICAL DESIGNS,

CONSULTING & SURVEYING

FRANK JEFFREY — Phone: (504) 348-7168

5201 Westbank Exp., Suite 206 • P.O. Box 1517 • Marrero, LA 70073

## JAMES S. KROGEN & CO., INC.

NAVAL ARCHITECTS & MARINE ENGINEERS

Tel. (305) 448-8169

3333 Rice Street,

Miami, Fla. 33133

## RODNEY E. LAY & ASSOCIATES NAVAL ARCHITECTS

NAVAL ARCHITECTS · MARINE ENGINEERS 13891 Atlantic Blvd. Jacksonville, Florida 32225

(904) 246-6438

TWX 810-828-6094



### Alan C. McClure Associates, Inc. NAVAL ARCHITECTS . ENGINEERS

2600 South Gessner • Suite 504 • Houston, Texas 77063 (713) 789-1840 • Telex 792397

## John J. McMullen Associates, Inc.



Naval Architects • Marine Engineers • Transportation Consultants

New York, NY • Arlington, Va. • Newport News, Va. • Houston, Tx Ventura, Ca. • Bath, Me. • Seattle, Wa. • Pascagoula, Ms

One World Trade Center/Suite 3000/New York, New York 10048/(212) 466-2200

#### MACLEAR & HARRIS, INC.

28 WEST 44 STREET **NEW YORK, N.Y. 10036** 212-869-3443

NA & ME ADVANCED DESIGNS



Speed & Propulsion Power Policy

FENDALL MARBURY NAVAL ARCHITECT

1933 LINCOLN DRIVE

ANNAPOLIS, MARYLAND 21401

(301) 268-6168

#### MARINE CONSULTANTS & DESIGNERS, INC.

Naval Architects

Marine Engineers

Telex: 98-5587 

MARINE DESIGN INC NAVAL ARCHITECTS & MARINE ENGINEERS Formerly Toms Inc., Established 1865 401 BROAD HOLLOW ROAD (Rt. 110) MELVILLE, L.I., NEW YORK 11746 516 293-4336 TUGS, BARGES, WORK BOATS & CONVERSIONS



#### THE PROFESSIONALS

Investigations • Representation · Consultation · Survey · Design

4475 Mission Blvd., Suite 235, P.O. Box 99546 San Diego, CA 92109, (619) 272-9922

#### Marine Technical Associates, Inc. MARINE ENGINEERS/ELECTRICAL CONSULTANTS USCG AND IMCO REGULATIONS

(201) 798-0689

95 River Street Hoboken, NJ 07030

## **PROFESSIONAL**

(CONTINUED)

#### GEORGE E. MEESE

NAVAL ARCHITECTS CONSULTANTS

MARINE ENGINEERS

SURVEYORS DESIGNS FOR YACHTS AND COMMERCIAL VESSELS WOOD—ALUMINUM—STEEL—PLASTIC

TELEPHONE COLONIAL 3-4054

194 ACTION ROAD ANNAPOLIS, MARYLAND

## Metritape

Liquid Level & Temperature Gauging

for Cargo • Ballast • Draft • Crude Oil • Products • Chemicals Central & deck-mounted readouts & alarms P.O. Box 2366, Littleton, MA 01460, U.S.A.

617 369-7500

Telex 92-3492

## R. CARTER MORRELL

MARINE CONSULTANT

715 S. CHEROKEE BARTLESVILLE, OK 74003

918-336-8306

TELEPHONES | 943-7070 thr: (212) | 943-7073

MOWBRAY'S

TUG AND BARGE SALES CORP. 21 WEST STREET, NEW YORK, N. Y. 10006

YOUR MARINE CONSULTANTS



#### NKF' ENGINEERING ASSOCIATES, INC.

• NAVAL ARCHITECTURE & MARINE ENGINEERING •ACOUSTICS, VIBRATION & SHOCK (DYNAMICS) \*NAVAL SHIP & SUBMARINE SURVIVABILITY

•SAFETY, DAMAGE CONTROL & FIRE FIGHTING



8150 LEESBURG PIKE SUITE 700 VIENNA, VIRGINIA 22180 (703) 442-8900 CABLE: NKFEA

#### **NELSON & ASSOCIATES, INC.**

MARINE

SURVEYORS **ENGINEERS** 

CONSULTANTS APPRAISERS

1405 N.W. 167 St., Miami, Fla. 33169 (305) 625-1043 Cable: NELSURVEY

Telex: 51-5704

lickum & Spaulding Associates, Inc



naval architects marine engineers

2701 first avenue, suite 350, seattle wa. 98121 (206) 382-4444 • tlx: 320053 new toll free number: 1-800-258-4444

#### **NORTHERN MARINE**

Naval Architecture - Marine Engineering Marine Surveying (616) 946-5959

P.O. Box 1169

Traverse City, MI 49685

## OCEAN-OIL INTERNATIONAL ENGINEERING CORPORATION

3019 Mercedes Blvd., New Orleans, Louisiana 70114, U.S.A. NAVAL ARCHITECTS . MARINE SURVEYORS SALVAGE ENGINEERS



Westinghouse Enterprise
Naval Architects/Marine Engineers
Marine Design & Modeling
7960 Arlington Expressway
Jacksonville, Florida 32211
724-7700 Telex: 568406 (904) 724-7700

NAVAL ARCHITECTS & MARINE ENGINEERS

#### prc

5252 Balboa Avenue, San Diego, California 92117 Telephone (714) 292-9102 PRC Guralnick

## S. L. PETCHUL, INC.

Naval Architect 1380 S W 57th AVENUE

FORT LAUDERDALE. FLA 33317 (305) 583-0962

## PILOTAGE CONSULTANTS, INC.

Capt. Jim Stillwaggon 516-742-2467

P.O. Box 2046 New Hyde Park, NY 11040

#### IM. ROSENBLATT & SON, INC.

NAVAL ARCHITECTS AND MARINE ENGINEERS

New York City 350 Broadway (212) 431 6900

San Francisco 415) 777 0500

Charleston Heights, S. C. 3370 Rivers Aver 803: 144 1586

San Diego

1007 Fifth Ave | 714| 238 1300

Arlington, Va. 2341 Jefferson Davis Highway 1031892 5680

ROSENBLATT & SON, INC.

## STV/sanders & thomas

Marine Engineering • Systems Analysis Consulting/Design Engineering

1745 Jefferson Davis Highway Arlington, VA 22202

703/521-5416

#### SCHMAHL and SCHMAHL INC.

Since 1961

Surveyors - Naval Architects - Claims Agents Consultants - In-House Maritime Attorneys

Representing Classification Societies, U.S. and Foreign Underwriters & Government Agencies Multilingual

Members: United States Maritime Law Association Southeastern Admiralty Law Institute Offices: In All Principal Areas of U.S. & Abroad

#### SCHMAHL BUILDING

1209 Southeast Third Avenue Fort Lauderdale, Florida 33316

Toll Free Fla. Line 800-432-0656 305-522-0689

Telex: 51-4489 (Intrepid) Cable: INTREPID



#### Marine Engineers **Propulsion System Analysis** Energy Reduction • Fuel Technology

MAIN STREET ESSEX, CONN. 06426

203 767-0937 TWX 7104580271

zammmm......

## GEORGE G. SHARP, INC.

MARINE ENGINEERS NAVAL ARCHITECTS



SYSTEMS ANALYSTS

100 Church Street New York, N. Y. 10007 Arlington, Virginia 22202 (703) B92-4000

(804) 499-4125

Virginia Beoch, Va. 23462 National City, California 92050 (619) 426-6494

> Voorhees, N. J. 08043 (609) 772-0888/89



## R. A. STEARN INC.

NAVAL ARCHITECTS & MARINE ENGINEERS

253 N. 1st Avenue Sturgeon Bay, WI 54235 Phone (414) 743-8282 TWX 910-270-1375

(206) 282-1311

HULL, MACHINERY **TOWING** 

(24 hour phone)

M. A. STREAM ASSOCIATES, INC.

Marine Surveyors & Consultants 400 Second Ave. W. / Seattle, WA 98119

## J.F. STROSCHEIN ASSOCIATES

NAVAL ARCHITECTS MARINE ENGINEERS MARINE CONSULTANTS



666 OLD COUNTRY RD. GARDEN CITY, NY 11530 (516) 542-1070



Cherry Hill, NJ 08003 (609) 429-7050

SERVING AMERICA'S MARITIME NEEDS AT 14 NATIONWIDE LOCATIONS

Marine Engineering, Naval Architecture and Systems Support in Testing, Training, Repair and Overhaul,

SYSTEMS ENGINEERING ASSOCIATES CORPORATION A Subsidiary of Day & Zimmermann, Inc

## RICHARD R. TAUBLER, INC.

NAVAL ARCHITECTS & MARINE ENGINEERS 8 COLUMBIA ST. MILFORD, DEL. 19963

(302) 422-3371

OVER 25 YEARS EXPERIENCE

## Tracor Hydronautics

INTEGRATED ENGINEERING SERVICES FOR THE MARINE INDUSTRY

> RESEARCH ● DEVELOPMENT DESIGN . TESTING

HYDRONAUTICS SHIP MODEL BASIN

#### Tracor Hydronautics

7210 Pindell School Road Laurel, Maryland 20707 Telephone: (301) 776-7454 Telex: 8-7585

Trans-International Marine Services Corp.



MAINTENANCE MONITORING SYSTEMS INVENTORY CONTROL SYSTEMS 622 Azalea Road Mobile, Alabama 36609 205/666-7121 205/666-7121



LEARN SMALL CRAFT DESIGN VIA HOME STUDY OR IN A RESIDENTIAL SETTING

WRITE OR PHONE FOR OUR CATALOGUE

Maritime Reporter/Engineering News

## **Epoxo Safety Coating** Helps Prevent Slipping —Literature Available



A non-slip safety coating for ships and offshore rigs is available from American Abrasive Metals of Irvington, N.J. Called Epoxo, the abrasive coating helps protect personnel and equipment from accidents caused by slips and falls. Originally developed for use by the U.S. Navy, Epoxo has been used on flight decks of all aircraft carriers since 1962.

On ships, the safety coating could be used effectively on exposed weather decks, work areas, storage decks, walkways, passageways, and vehicular traffic areas to insure the protection of personnel and equipment from costly accidents. For offshore rigs, Epoxo's high-traction surface enables men and equipment to maintain traction even on wet, slippery, and oily decks. It also helps prevent injury to personnel and damage to aircraft on helicopter landing pads.

Epoxo's epoxy formulation resists wear with "locked in" abrasive granules that cannot be loosened. The heavy-duty liquid coating applies as easily as paint over almost any surface, is unaffected by water, oil, grease, and most chemicals, and is equally effective inside

For a free sample clip, literature, and prices on Epoxo,

Circle 37 on Reader Service Card

#### THOMAS B. WILSON ASSOCIATES

NAVAL ARCHITECTS & MARINE ENGINEERS 1258 N. AVALON BLVD. • WILMINGTON, CA. 90744 PHONE (213) 518 0940

## Uhlig & Associates, Inc.

## **DESIGN**

**SERVICES** 

- SHIPBOARD ELECTRICAL SYSTEMS
- POWER GENERATION & DISTRIBUTION
- SWITCHBOARDS
- ALARM & MONITORING SYSTEMS
- PROPULSION SYSTEMS
- PIPING SYSTEMS
- DESIGNS ONLY OR COMPLETE READY TO INSTALL SYSTEMS

MIAMI, FLORIDA — 8295 S. W. 188th Street, 33157 TELEX: 51-2479 51-2510 / TWX: 810 - 840-2430 PHONE: (305) 251-2451

January 1, 1984

## **Executive Changes Announced** By American Hoist & Derrick





Robert H. Nassau

Robert P. Fox

In accord with its succession plan, the board of directors of Amhoist, American Hoist & Derrick Company, recently announced its intention to elect Robert H. Nassau as chief executive officer effective April 7, 1984, the date of the annual board meeting. As part of the transition, the board intends for Robert P. Fox, current chief executive officer, to continue as chairman of the board and to remain active in the company's business. This is the next step in the orderly transition planned when the board recruited Mr. Nassau as president and chief operating officer in 1982

Mr. Fox joined Amhoist in 1959 and held a series of management positions before being named president in 1973. He was elected chief executive officer in December 1974, and in 1982 was named chairman and CEO.

## Mitsui Delivers First Of Four **Bulk Carriers To Egyptian Owner**



The 41,543-dwt bulk carrier Abydos shown above was delivered recently by the Chiba Works of Mitsui Engineering & Shipbuilding Company, Ltd. (MES) to Misr Shipping Company of Egypt. The new vessel has an overall length of about 617 feet, molded beam of 101.7 feet, molded depth of 49.8 feet, and full load draft of 35.2 feet.

The bulk carrier, first of four sister ships ordered from MES by the same owner, is equipped with five electro-hydraulic deck cranes for greater cargo-handling efficiency, and such fuel-conserving features as an energy-efficient, low-speed diesel engine and Mitsui Integrated Duct Propeller. The main engine is a Mitsui/B&W type 6L67GFCA diesel with a maximum continuous output of 11,400 bhp. Using 85 percent of the maximum rating, the ship's service speed under full load is 14.8 knots.

Other features include electro-hydraulic, single-pull type hatch covers, and a cargo stowage computer that permits rapid computation of the trim and stresses on the hull. Her electronic equipment includes a satellite navigation and position-finding system and a Loran C receiver. The Abydos has been built to Lloyd's Register of Shipping classification.



Thomas Marine Proudly Presents . . THE "EXPLORER"

Sea-Worthy! Spacious! Spirited! A Work Horse Our new 25' x 9' beam "EXPLORER" Work Boat is really rugged built of 3/16" Aluminum Plate, heli-arc welded, reinforced within

We offer an extensive Line of Aluminum Plate Work Boats. 23' to 39' overall We'd like to discuss your Work Boat requirements: (516) 289-0621



Circle 145 on Reader Service Card




VCR INPUTS

MARINE ENGINEERED

CMC Communications, Inc. 5479 JETPORT INDUSTRIAL BLVD. TAMPA, FLORIDA 33614 PHONE 813-885-3996

Circle 146 on Reader Service Card

## We'll build your barge your way.



Our design and construction flexibility, experienced craftsmanship, and advanced facilities produce competitively priced, quality barges built for each customer's shipping operation. Contact us, and we'll build one your way

Brownsville, Pennsylvania 15417 Phone: (412) 785-6100 **HBC Barge** 

Circle 147 on Reader Service Card



· Maintenance Free Deck Furniture o Maintenance Free Deck Equipment

Send for additional information & catalog

 Fabricators of Wood, Aluminum, Steel, Fiberglass & Formica

Complete Line of Maritime Interior Furniture

## COMFORT-MATE, INC.

P.O. BOX 160845 MIAMI, FLORIDA 33116 Tel: (305) 591-1973 • Cable: COMFRTMATE

Circle 148 on Reader Service Card

## CLASSIFIED AND EMPLOYMENT ADVERTISING

HOW TO PLACE CLASSIFIED ADVERTISING: Mail clearly written or typed copy to: MARITIME REPORTER, 107 East 31st Street, New York, N.Y. 10016. Include any photos, drawings or logos if required. Specify size of ad and number of insertions....Classified Advertising — Per Issue Rate: Classified advertising is sold at a rate of \$55 per column inch....MARITIME REPORTER'S classified section carries more advertising and sells more products than any other publication in the marine industry. MARITIME REPORTER is published the 1st and the 15th of each month. Closing date for classified advertising is 20 days prior to the date of the issue. For further details contact John C. O'Malley at (212) 689-3266. Send all advertising material to MARITIME REPORTER and Engineering News, 107 East 31st St., New York, N.Y. 10016.

## RECRUITERS OF PROFESSIONAL MARINE PERSONNEL

ENGINEERING, ADMINISTRATION, OPERATIONS & SALES SERVING THE MARINE & OFF5HORE INDUSTRIES SINCE 1973



2727 KIRBY, SUITE 411 HOUSTON, TEXAS 77098 713 / 528-3748 TELEX: 792333 ANSWERBACK: VIA TLX HOU



#### BROKERS OF MARINE TALENT

2200 6t.h Avenue Seattle, WA 98121 [206] 343-3307

## **MARINE SALES**

Marine Management Systems, a leader in the development of marine computer systems, is seeking sales persons to promote IBM-PC based products in one of the following

**Marine Business Systems** for Brokers, Agents, Freight Forwarders & NVOCC's in the area of voyage estimating, cargo documentation and marine accounting.

Ship Management Information Systems for ship owners/operators in the areas of spare parts inventory, planned maintenance, machinery performance, and trim stability and stress calculations.

Knowledge of marine applications necessary. Computer knowledge helpful but not required. Send resume in confidence to:

Marketing Manager Marine Management Systems, Inc. 102 Hamilton Avenue Stamford, CT 06902

#### SHIP REPAIR REPRESENTATIVE

Aggressive established Ship Repair Company is looking for Representative—Agent in New Orleans area. Interested parties can be Marine Consultants or Ship Agents and must be aware of ship traffic in area and have contacts with Marine Superintendants. Address replies to:

Box 1215 107 East 31 Street Maritime Reporter/Engineering News New York, NY 10016

## SENIOR MARINE ENGINEER DIESEL-GAS TURBINE-STEAM

Tacoma Boatbuilding Co., a major Puget Sound shipyard, is seeking a Senior Marine Engineer, experienced in diesel, gas turbine, and steam propulsion systems. The position will be responsible to the VP of Engineering for all propulsion and secondary system engineering and design in ships of all sizes built, overhauled, and repaired in the shipyard. Minimum prerequisites for consideration are.

- a. BS in either Marine or Mechanical Engineering
- b. At least ten years of shippard or design activity experience in marine engines.
- c. Familiarity and experience with entire propulsion train in at least two of the following: diesel, gas turbine, steam, CODAG, COSAG
  - d. Five years of supervisory experience

Applicants should send resume, salary history, and salary requirements to Tacoma Boatbuilding Co., ATTN: Employment Manager, 1840 Marine View Drive, Tacoma, WA 98422.

TBC — An Equal Opportunity Employer

## MANAGEMENT OPPORTUNITIES! SHIPBUILDING — SHIP REPAIR

SHIPBUILDING — SHIP REPAIR
SHIPYARD GENERAL MANAGER (MAJOR REPAIR FACILITY)
CHIEF ENGINEER (MAJOR YARD)
MANAGER OF PROCUREMENT (MAJOR YARD)
PIPE SUPERINTENDENT
MACHINERY SUPERINTENDENT
SENIOR REPAIR ESTIMATORS (2)
ELECTRICAL FOREMAN
HULL FOREMEN (SMALL VESSEL CONSTRUCTION)
DOCK MASTER (SYNCROLIFT)

DUCK MASTER (SYNCROLIFT)
WE SPECIALIZE IN RECRUITING KEY MANAGEMENT PERSONNEL
FOR THE SHIPBUILDING AND SHIP REPAIR INDUSTRY. ALL FEES
AND EXPENSES ARE COMPANY PAID. THE ABOVE POSITIONS.
AND MANY OTHERS, ARE NOW OPEN. CALL MR. M.A. WEEKS
AT (205) 661-2294 AS SOON AS POSSIBLE OR SEND RESUME
IMMEDIATELY!

WEEKS AND ASSOCIATES
Management Consultants
921 Cottage Hill Avenue, Mobile, Alabama 36609

## MARINE PERSONNEL

For corporate staff requirements and employment opportunities in:

- SHIPBUILDING TUG & BARGE •
- MARINE CONSTRUCTION OFFSHORE •
- TERMINAL STEAMSHIP LINE/AGENTS Contact ROSS WORDEN
  - All resumes & inquiries confidential •

All fees paid by client companies • Domestic & International company assignments welcome • No fee unless referral hired •

#### MCR AGENCY, INC. 415-444-7700

MARINE PERSONNEL CONSULTANTS 405 14th Street. #1600 MR Oakland, California 94612

## MARINE DIESEL SALES ENGINEER

Responsible for projecting, sales, and sales follow up. Degree in engineering or equivalent in experience (minimum 5 years) necessary as well as good contacts in the marine industry. Relocation to New Orleans area required and must be prepared to travel.

Box 101 107 East 31 Street

Maritime Reporter/Engineering News New York, NY 10016

## FOR SALE



### TWIN SCREW ICE BREAKING TUGBOAT HULL

BUILT IN 1943 FOR U.S.C.G. AND ALWAY IN FRESH WATER

110' x 26' x 12'

10" CHANNEL KEEL COOLERS

RUDDERS AND PROPELLER SHAFTS INSTALLED IN 1983

READY FOR ENGINES

CALL (312) 721-4138

## NAVAL ARCHITECTS MARINE ENGINEERS

ENGINEERING POSITIONS

Rapid growth of leading Naval Architecture & Marine Engineering Company has created immediate permanent openings for Senior Naval Architects, Marine

Mechanical, HVAC and Electrical Engineers. B.S. degree and 10 yrs. marine experience including 6 yrs. Naval experience required. Advanced degree and proven design management ability desired.

Salary commensurate with ability and experience. We offer excellent benefits and a pleasant working environment. Please send resume & salary requirements to:

CDI MARINE COMPANY 9951 Atlantic Blvd. Jacksonville, FL 32211 Attn: Terry McDonald

#### SHIPYARD PROCUREMENT MANAGER

Minimum 10 years experience, advance degree preferred; MBA or Procurement Management, shipyard procurement and military contract procurement required. West Coast location, \$50K +. Good Benefits and relocation.

McCutchan Recruiting, Marine and Transportation P.O. Box 19392, Seattle, WA 98109 — (206) 282-5056

## FOR SALE MODERN SHIPYARD

Shipbuilding and repair yard located in South Louisiana on 36 acres of land. Includes complete operational facility for new ship construction, (2) new 1800 ton drydocks, (1) 3500 ton drydock, metal building construction, marine hardware and supply store and related welding, carpentry, plumbing and electrical installations.

Box 102 107 East 31 Street

Maritime Reporter/Engineering News New York, N.Y. 10016

#### FOR SALE AMMCO DREDGE

Model PD-14S Portable Hydraulic Cutterhead Suction Dredge complete with standard equipment plus some additions. Year built — 1981.

Box 103 Maritime Reporter/Engineering News 107 East 31 Street New York, N.Y. 10016

## FOR SALE OR CHARTER TWO DRILLING BARGES

Formerly **WESTERN OFFSHORE III** 365' x 75' x 27' (Located Spain)

Formerly **WESTERN OFFSHORE IV** 360' x 82' x 28.4' (Located Singapore)

Barges are less most drilling machinery except are complete with Diesel Generators, Derrick, Mud Pumps, Mooring Winches, Anchors, Cranes, and Hotel Equipment. Ideal for Tender, Floating Supply Base, Diving Support Vessel, or Crane Barge.

American General

Levin Corporation



445 Littlefield Ave. P.O. Box 2445 So. San Francisco, CA 94083 Telephone (415) 761-0993 TWX 910-371-7248



Gross Registered Tons 1804 - Net Tons 1672

Length OA Beam Depth Draft (Sumr

Vessel Unloaded By

Quarters For Fully Equipped Galley 24 Mer Protane range, walk-in refrigerator

rticulars believed to be correct but not guaranteed Subject to prior sale or withdrawn by the owner ASKING PRICE: \$250,000.00



## **MOWBRAY'S**

TUG & BARGE SALES CORP.

West St. New York N.Y. 10006 TELEPHONE (212) 943-7070 TWX: 710-581-2827

## **75 STANDARD 20 FOOT** CONTAINERS FOR SALE


NEW — LOCATION: NEW ORLEANS PRICE: NEGOTIABLE

CALL (212) 980-0500, CAPTAIN MELLIS

#### ATTENTION MARINERS

PREPARE FOR YOU'R COAST GUARD LICENSE EXAMINATION

▶ MASTER/MATE'S/PILOT'S



MASTER/MATE Freight & Towing Vessels


Navigation . Inc. CAPTAIN'S LICENSE Motor Boat/Ocean Operato Suite 316 558 Pleasant Street New Bedford, MA 02740 Tel. (617) 992-4025

PLUS MANY MORE U.S. MERCHANI MARINE RECOGNIZED SHIPBOARD OCCUPATIONS

Licensed by Con m. of Mass. Department of Education VISA/M.C.

## FOR SALE 3 LEGGED JACK-UP BARGES FLEET OR INDIVIDUALLY

(1) 75' x 36' **Built 1981** (1) 65' x 28' Built 1982 (2) 65' x 26' Built 1982 Built 1981 (1) 65' x 28' Built 1982 (2) 60' x 24' Built 1981 (2) 60' x 24'



For Additional Information

Contact:

WESTBROOK

J.M. Westbrook & Co., Inc. P.O. Drawer I Lockport, LA 703

(504) 532-6651 TWX: 810-950 WESTBROOK LOCP Call the Barge People



## **McDONOUGH** MARINE SERVICE

Shippers use our rental hoppers to haul American coal in enormous quantities, and at rock bottom costs to all points on the inland river system and the Gulf

Parkersburg (304) 485-4494 Telex 86-9412 P.O. Box 1825 \*\* Parkersburg, WV 26101

#### SHIP FOR SALE—UNIQUE OPPORTUNITY

Rentals Sales Service

One of a kind passenger/cruise vessel seriously offered by owners. Presently trading in the Bahamas: LOA: 164.5 ft., Beam: 31.5 ft., Draft: 141/2 ft. (aft loaded), Displacement: 1106 tons. Constructed of steel by Spear Engineering, Norfolk, Va., 1930. Main drive, two Baldwin Hamilton diesel with Crocker Wheeler electric motor. Diesel electric 650 total horsepower. Two 125kw and one 75kw auxiliary generators. Fuel consumption (main drive) 5 gallons per mile at 11 knots. Fully outfitted with modern electronics, etc. Vessel offered where is, as is.

Please address serious inquiries to:

The Operations Manager 120 NE 27 Street Miami, Florida 33137 — U.S.A.





GLOBE ● ANGLE ● GATE ● CROSS ● AND MANIFOLD



Heavy

Free Phone 800-221-9672 In New York 212-361-2111 METROPOLITAN PLB. SUP.

5000 Second St. Long Island City, N.Y. 11101 ANCHOR


CHAIN

21/2" and 3" NACO used anchor chain for sale. Write or Call: Prolerized N.E. Co., P.O. Box 0048, Everett, MA 02149, (617) 389-8300.

## **MARINE** INDUSTRIAL & **AUTOMOTIVE DIESEL ENGINES** & SPARES

DOMESTIC AND FOREIGN TO 20,000 HP. WORLDWIDE SPARES AVAILABILITY FOR **ALL ENGINES LARGE OR SMALL** 





## Stork-Werkspoor Engines Will Power Exxon Tugboats

Stork-Werkspoor Diesel by (SWD) has thus far sold eight of the Dutch company's F240 engines for use by United States towing firms. Joop Zwart, U.S. sales manager, said that three tugs being built for the Exxon Corporation will each be equipped with a pair of 9-cylinder, F240, 2,000-bhp engines. Shaver Transportation Company of Portland, Ore., will replace two older SWD diesels in the firm's tug Columbia, with the newer 6-cylinder F240, 1,270-hp turbocharged engines for service on the Columbia/Snake river systems.

Morrison-Knudsen Company, the international construction firm that is supervising the project, placed the order for the Exxon engines. The tugs, which will be built in the Damen Shipyards, Gorinchem, Netherlands, will be used in Columbia, South America. The tugs were designed by The Glosten Associates, Seattle naval architects.

Charles Garman, recently appointed SWD sales manager on the U.S. West Coast, also said that a similar engine would be installed in the Ilduso Fisheries' trawler MAR-GUN.

#### **ATA TUG** 143' x 34' x 14'

Two 12-278A 1200HP, Two 6-71 Generators, 42,000 Fuel, 16,000 Mile Range, Excellent Condition

Call (804) 898-4537 or Telex 703235



## **MANUFACTURER SERVICE REPAIR PARTS**

CMH HELESHAW, INC.

201 HARRISON STREET HOBOKEN, NEW JERSEY 07030

NEW YORK: (212) 267-0328 HOBOKEN: (201) 792-0500 TWX: 710-730-5224 CMH HBKN

## HYDRAULICS

## **SERVICE • REPAIR • PARTS CONSULTING • DESIGN**

**CUNNINGHAM MARINE** HYDRAULICS CO., INC.

201 Harrison St. • Hoboken, N.J. 07030 (212) 267-0328 (201) 792-0500

2030 E. Adams St. • Jacksonville, FL 32202 (904) 354-0840

TWX 710-730-5224 CMH Hoboken, NJ



The vessel will be re-engined at Pacific Fish-

erman, Inc., in Ballard, Wash.

Meanwhile, SWD has begun deliveries of the first of ten 18-cylinder TM410 diesels to General Dynamic's Quincy Shipbuilding Division in Massachusetts. The engines will be used in five roll-on/roll-off prepositioning supply vessels for the U.S. Navy. A pair of TM410 engines will give each ship 27,600 bhp of propulsion power.

### Vincent Drummond Tibbetts 1913-1983

Vincent D. Tibbetts, president of Boston Fuel Transportation, Inc., died recently at the age of 70. Mr. Tibbetts was born in East Boothbay, Maine, in 1913 and moved to Boston in 1932. In 1937 he started his own fuel transportation business with a 3,000-gallon barge and a 100-hp towboat. In 1941 he became president of Esterhill Boat Service. When Esterhill was acquired by Boston Fuel Transportation in 1953 he became part owner and vice president. In 1969 he became president of Boston Fuel and a director of Reinauer Transportation Companies of New York.

At the time of his death Mr. Tibbetts was operating a fleet of 23 tankers, barges, and towboats. He was a member of the American Waterways Operators, Inc., Boston Marine Society, Maritime Association of Boston, and The Propeller Club of the United States.

## Barge-Mounted Nine-Story Hotel Proposed By NKK

A Japanese shipbuilder has unveiled a concept for constructing a nine-story, first-class hotel on a barge that could then be towed to any coastal area in the world. Nippon Kokan (NKK) reports it has solved all of the technical problems involved in the construction of the floating hotel, and has already completed a design model to use in worldwide marketing. The movable hotel, weighing some 15,000

SURPLUS IEEE-45 MARINE CABLE NEW --STORED INSIDE

Large quantity, various sizes Contact: Jim Kelly 206-593-8800



## tacoma boat

TACOMA BOATBUILDING CO

1840 Marine View Dr. / Tacoma, WA 98422

## LOWEST PRICES IN U. S. GULF SERVICE with QUALITY

GENERAL SERVICES:

- \* ROUTINE DRYDOCK WORK
- HULL CLEANING & PAINTING
- SHAFT AND RUDDER
- GENERAL STEEL WORK
- MACHINE WORK
- ELECTRICAL WORK \* OTHERS



DRYDOCK:

Lifting capacity, 5,000 L. T.

Could handle ships Under 450' L. O. A

TEH TUNG SHIPYARD ORANGE, TEXAS 77630 P. O. Box 1347

Tel. (409) 886-8620 Tix: (ITT) 4991740 TTUNG tons, involves a special barge that forms the foundation for the 360-room hotel, which also incorporates three conference rooms, public areas, restaurant and entertainment areas,

and outdoor swimming pool.

A spokesman for NKK America Inc. in New York said that inquiries have already been received, especially from developing countries where shortages of land, skilled workers, equipment, and material make first-class ho-

tel construction difficult.

The idea for the barge-mounted "export" hotel has been under study for two years by NKK and Tokyu Construction Company. According to NKK, construction at one of the company's shipyards insures high quality and labor skill, and the barge technology is already developed to permit towing of the structure to its final destination at a speed of five knots. A further benefit, NKK notes, is that the hotel could be moved to different locations to accommodate special expositions or summer and winter resort areas.

## New Design Cranes Installed On Navy's Auxiliary Drydocks



New type diesel-electric cranes have been installed on Navy's floating drydock USS Competent at Pearl Harbor

Vital to the nation's defense capability is the improvement of repair and maintenance procedures and the modernization of facilities. When the Naval Sea Systems Command called for improvement of the crane system on its medium auxiliary floating drydocks, Crane Con Products of Seattle responded with design and production of four wing wall cranes. According to a Crane Con spokesman, these cranes were the first of this type to be designed and manufactured to the revised miliary specification MIL-C-17949B, Electro-Mechanical Shipboard Cranes. The first two cranes of the contract were completed in early 1983, and the second pair around midyear, well ahead of schedule.

The \$6.6-million contract included design, manufacture, and delivery of the cranes to the drydock USS Competent (AFDM-6) at Pearl Harbor and the USS Sustain (AFDM-7) at Norfolk. The self-contained, diesel-electric cranes utilize a static, stepless electric control system providing infintely variable speed selection and load float control for precise, steady positioning. Each crane's rated capacity is 45,000 pounds at 25-foot radius; maximum outreach is 65 feet from center of rotation.

The cranes operate on 14-foot gauge track, traveling a distance of 460 feet, almost the full length of the dock. Total operating gross weight of each crane is 265,000 pounds. is the first major project completed in our new Seattle manufacturing plant," said Con Crane president Lyle Harlson. "It is a major step in the expansion into crane manufacturing, repair, and refurbishing, in addition to production of our automatic brakes, wheel chocks, and other crane safety equipment.

# AUCTION

(U.S. MARSHAL)

## 4 – 285' BARGES





Length	285'	Deck 3/4" plate
Breadth	78'	Side Shell3/4 & 5/8" plate
Depth	18'	Bottom 5/8 & 1/2" plate
Built	1982	
Class	Maltes	e Cross A-1 Ocean Service
	ABS C	ert. good thru '86/'87 on 3 barges

Flat deck cargo barge of all welded steel construction with raised forecastle and 6'4" breakwater. Shaped spoon bow, vertical sides, radiused bilge and square raked stern fitted with hydra-lift skegs. A centerline bulkhead combined with five transverse bulkheads divides the underbody into twelve watertight compartments. No. 1 and No. 4 compartments port and starboard are fitted with sea chests and are ballastable. The barges have a 6" wood wear deck and heavy tow pads on the bow.


For additional information, or to make an appointment to inspect, call or write:

## SEATTLE: FIRST NATIONAL BANK

Post Office Box 3977 Seattle, Washington 98124

Mary Coon or Marc Wright (206) 583-3252 (206) 583-2237

## 2 - 230' BARGES



Length	230'	Deck 5/8" plate
		Side Shell
Depth	15՝	Bottom 1/2" plate
Built		•
Class	Maltes	se Cross A-1 Ocean Service
ABS Certificate good thru 1986		

Flat deck cargo barge of all welded steel construction with a molded spoon bow, perpendicular sides, radiused sheer and bilge and raked stern fitted with anti-yaw skegs. The fore and after rakes are divided into three compartments and a centerline bulkhead from frame 6 to frame 26 combined with five transverse bulkheads divides the underbody into fourteen watertight compartments. A breakwater mounted on the raised forecastle extends across the bow and heavy towing pads are mounted port and starboard.

## SALE INFORMATION

The barges will be sold individually to the highest bidder at open auction at 10:00 a.m. on February 1, 1984 at:

The Cliff House 6300 Marine View Drive Tacoma, Washington 98422

Bidders must provide cash or a certified or cashier's check payable to the U.S. Marshal for 10% of bid at time of sale. Balance due three business days after sale

Barges will be sold "as is, where is" and should be picked up after complete settlement has been made.

## **BUYERS DIRECTORY**

This directory section is an editorial feature published in every issue for the convenience of the readers of MARITIME REPORTER/Engineering News. A quick-reference readers' guide, it includes the names and addresses of the world's leading manufacturers and suppliers of all types of marine machinery, equipment, supplies and services. A listing is provided, at no cost for one year in all 24 issues, only to companies with continuing advertising programs in this publication, whether an advertisement appears in every issue or not. Because it is an editorial service, unpaid and not part of the advertisers contract. MR EN assumes no responsibility for errors. If you are interested in having your company listed in this Buyers Directory Section, contact John C. O'Malley at (212) 689-3266.

```
Flexaust Company, 11 Chestnut St., Amesbury, MA 01913
Squire Cogswell Company, 3411 Commercial Ave., Northbrook, IL 60062
AIR CONDITIONING AND
      AIR CONDITIONING AND
REFRIGERATION—REPAIR & INSTALLATION
Bailey Refrigeration Co., Inc., 74 Sullivan St., Brooklyn, N.Y. 11231
Cospolich Refrigerator Co., Inc., 949 Industry Rd., Kenner, LA 70062
Marlo Coil/Nuclear Cooling, Inc., P.O. Box 171, High Ridge, MO 64049
Nance Industries, P.O. Box 1547, Beaumont, TX 77704-1547
United Technologies Carrier Transicold, P.O. Box 4805, Syracuse, NY 13221
   13221
Unitemp Inc., 3590 Kennedy Rd., So. Plainfield, NJ 07080
York Division, Borg-Warner Corp., P.O. Box 1592, York, PA 17405

ANCHORS AND CHAIN
Baldt Incorporated, P.O. Box 350, Chester, PA 19016
Neptunia, Via Giovanni da Verrozzano, 12, 16165 Genova, Italy

ANODES—Cathodic Protection
American United Marine Corp., 5 Broadway, Rte. 1, Saugus, MA 01906
Engelhard Industries Division, 2655 U.S. Route 22, Union, NJ 07083
Koiser Chemical, Div., of Kaiser Aluminum & Chemical Corp., 300 Lakeside
Dr., Rm. 1128 KB, Oakland, CA 94643
The Platt Bros. & Co., Box 1030, Waterbury, CT 06721
BASKET STRAINERS
North Star Marine & Industrial Products. Inc., 84 Wall Street, Farmingdale,
             North Star Marine & Industrial Products, Inc., 84 Wall Street, Farmingdale,
NY 11735
      Riley-Beaird, P.O. Box 31115, Shreveport, LA 71130

BEARINGS—Rubber, Metallic, Non-Metallic

Johnson Rubber Co., Duramax Marine Div., 16025 Johnson St., Middle-
field, OH 44062
              field, OH 44062
Lucian Q. Moffitt, Inc., P.O. Box 1415, Akron, Ohio 44309
Thomson-Gordon Limited, 3225 Mainway, Burlington, Ontario, Canada
     Waukesha Bearings Corp., P.O. Box 798, Waukesha, Wisc. 53186
BLASTING—Cleaning—Equipment
Apache Equipment, Inc., 10690 Shadow Wood Dr., Suite 112, Houston, TX
77043
             Atlantic Sandblasting & Coatings, Inc., 2700 Guy Verger Blvd., Tampa, FL 33605
                                         vorth Inc. (USA), 3721 Lapas Dr., P.O. Box 18312, Houston, TX
             77223-9989

Butterworth Systems (UK), 123 Beddington Lane, Croydon CR9 4NX,
             England
CLEMCO, P.O. Box 7680, San Francisco. CA 94120
Complete Abrasive Blasting Systems, 18250 68th Avenue South, Kent, WA
98031
              E.I. DuPont De Nemours & Co., Inc., Starblast Division, Room X39186, Wil-
            E.I. DuPont De Nemours & Co., Inc., Starblast Division, Room X39186, Wil-
mington, DE 19898
Rockwell International, Power Tool Division, 400 N. Lexington Ave.. Pitts-
burgh, PA 15208
Schmidt Mfg. Inc., P.O. Box 37, Fresno, TX 77545
   BROKERS

Copt. Astad Company, Inc., P.O. Box 53434, New Orleans, La. 70153
ECO Inc., 1036 Cape St. Claire Center, Annapolis, MD 21401
Hughes Bros., Inc., 17 Battery Pt., New York, N.Y. 10004
National Propeller Exchange, P.O. Box 1444, Grafton, VA 23692
BRONZES—COMMEMORATIVE
Duramax Metals, Inc., 2401 Wesley Street, Portsmouth, VA 23707
BUNKERING SERVICE
Belcher Company, Inc., 9700 Wesley Street
             Belcher Company, Inc., 8700 West Flagler, P.O. Box 525500, Miami, FL 33152
    Gulf Oil Trading Co., 535 Madison Ave., New York, NY 10022
National Marine Service Inc. (Transport Div.), 1750 Brentwood Blvd., St.
Louis, MO 63144
CARGO HANDLING EQUIPMENT
             MacGregor-Navire International, Box 8991, S-402 74 Goteborg, Sweden
MacGregor Navire U.S.A. Inc., 135 Dermody St., Cranford, NJ 07016
    CHOCKING SYSTEMS

Palmer Products Inc., P.O. Box 8, Worcester, PA 19490

Philadelphia Resins Corp., 20 Commerce Drive, Montgomeryville, Pa
   Band-It Company, P.O. Box 16307, Denver, CO 80216
CLOSURES—Marine
  CONTAINERS—Marine
Cornell-Corr Co. Inc., 63 Main St., Monroe, CT 06468
CONDENSERS
Riley-Beaird, P.O. Box 31115, Shreveport, LA 71130
CONTAINERS—Cargo Container Handling
Paceco Inc. (A division of Fruehauf). West Seaway Access Road. Gulfport
AS 39501

CONTROL SYSTEMS—Monitoring
American United Marine Corp., 5 Broadway, Rte. 1, Saugus, MA 01906
Argo Marine, 140 Franklin St., New York, NY 10013
ARMTEC Industries, Inc., Manchester, NH 03103
ASEA, Inc. 4 New King St., White Plains, NY 10604
Autronica Marine USA, 280 Industrial Pkwy., Northvale, NJ 07647
Avicon Corp., 7750 East Redfield Ra., Scottsdale, AZ 85260
Cooper Energy Services, Mount Vernon, OH 43050
Eldec Corp., P.O. Box 100, Lynwood, WA 98036
Ergon, Inc., P.O. Drawer 1639, Jackson, MS 39205
Foilsafe Motor/Generator Protector, Maiine Safe Electronics Ltd., 101 Jardin Dr., Unit 24/25. Concord. Ontario, Canada L4K 186
Fluidyne, a Div. of Electrodata Inc., P.O. Box 11366, Santa Rosa, CA 95406
Leslie Co., 401 Jefferson Rd., Parsippany, NJ 07054
Marine Moisture Control Co., 60 Inip Dr., Inwood, NY 11696
Megasystems, Inc., 1075 N.W. 58th Street, Boca Roton, FL 33431
Notional Control Systems, Inc., 827 Hanley Industrial Court, St. Louis, MO 63144
          Notional Control Systems, Inc., 827 maniey industrial 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 2001, 3. 200
  ville, CT 06062
Wesmar Marine Systems Div., 801 Dexter Ave. N., Box C19074, Seattle, WA 98109
COUPLINGS
Camlock Flange Sales Corp., 60 Inip Dr., Inwood, NY 11696
SKF Steel, 20 Tower Lane, P.O. Box 745, Avon, CT 06001
CRANES—HOISTS—DERRICKS—WHIRLEYS
          AMNES—HOISTS—DERRICKS—WHIRLEYS

American Hoist & Derrick Company (AMHoist), St. Paul, MN 55107

Appleton Marine, P.O. Box 2339, Appleton, WI 54913

ASEA Stal-Laval Inc., 525 Executive Blvd., Elmsford, NY 10523

Blohm & Voss Company, 55 Morris Avenue, Springfield, NJ 07081

Chester Hoist Division, Monogram Industries, P.O. Box 229, Lisbon, OH 44432
```

AIR COMPRESSORS

Grove Manufacturing Co., P.O. Box 21, Shady Grove, PA 17256
HIAB Cranes & Loaders Inc., R.D. 22 Interchange Place, York, PA 17404
Hertz Equipment Rental Corp., 7 Entin Rd., Bldg # 2, Parsippany, NJ 07054
Marine Travelift, Inc., 49 E. Yew St., Sturgeon Bay, WI 54235
National Crane Corp., 11200 North 148 St., Waverly, NE 68462
National Supply Company, 1455 West Loop South, Houston, TX 77027
Superior-Lidgerwood-Mundy Corp., 1101 John Ave., Superior, WI 54880
Washington Crane, Div. of Ederer, Inc., P.O. Box 24708, Seattle, WA 98124
DECK MACHINERY—Cargo Handling Equipment
Argo Marine, 140 Franklin St., New York, NY 10013
Marine Technical Associates, 195 Patterson Avenue, Little Falls, NJ 07424
Markey Machinery Co., Inc., 79 S. Horton St., Seattle, Wash 98134
DECKING—GRATING
International Grating, Inc., 7625 Porknurst, Houston, TX 77028
Selby, Battersby & Company, 5220 Whiby Ave., Philadelphia, PA 19143
J.E. Steigerwald Co., Inc., 5515 Belair Rd., Baltimore, MD 21206
DIESEL ACCESSORIES—CYLINDER LINERS
B & W Marine Service, 50 Broadway, New York, NY 10004 DIESEL ACCESSORIES—CYLINDER LINERS

B & W Marine Service, 50 Broadway, New York, NY 10004
General Thermodynamics Corporation, 210 South Meadow Road, P.O. Box
1105, Plymouth, Massachusetts 02360
Golten Marine Co., Inc., 160 Van Brunt St., Brooklyn, NY 11231
Haynes Corporation, P.O. Box 179, Jackson, MI 49204
Van der Horst Corp. of America, 314 Penn Ave., Olean, NY 14760
DIESEL ENGINE—Spare Ports & Repair
Golten Marine Co., Inc., 160 Van Brunt St., Brooklyn, NY 11231
ELECTRICAL EQUIPMENT
Argo Marine, 140 Franklin St., New York, NY 10013
Marine Electric RPD, Inc., 666 Pacific St., Brooklyn, NY 11217
Valad Electric Heating Corporation. 162 Wildey St., Tarrytown, NY 10591
Ward Leonard Electric Co., 31 South St., Mt. Vernon, NY 10550
Zidell Explorations, Inc., 3121 S.W. Moody St., Portland, Ore. 97201
EMULSIFICATION SYSTEMS
Cleonodan A/S, N. American Agents, American United Marine Corp., 5 EMULSIFICATION STSTEMS
Cleonodan A/S, N. American Agents, American United Marine Corp., 5
Broadway, Route 1, Saugus, MA 01906
EQUIPMENT—Marine
American General/Levin Corp., 445 Littlefield Ave., So. San Francisco, CA 94080 Argo Marine, 140 Franklin St., New York, NY 10013 ASEA Stal-Laval Inc., 525 Executive Blvd., Elmsford, NY 10523 Band-It Division, Houdaille Industries, Inc., P.O. Box 16307, Denver, CO Thomas Coudon Associates, 6655 Amberton Dr., Baltimore, MD 21227 b.v. Holmatro Industrial Equipment, P.O. Box 33, 4940 aa Raamsdonksveer, b v. Holmatro Industrial Equipment, P.O. Box 33, 4940 aa Raamsdonksveer, Holland
Juniper Industries Inc., 72-15 Metropolitan Ave., Middle Village, NY 11379
Kearfott Marine Products, 550 South Fulton Ave., Mount Vernan, N.Y. 10550
Marittme Power Corp., 200 Henderson Street, Jersey City, NJ 07302
John P. Nissen, Jr. Company, Glenside, PA 19038
Stal-Laval Turbin AB, S-612 20 Finspong, Sweden
EVAPORATORS
Alfa-Laval, Inc., Dept. MR-2. 2115 Linwood Ave., Fart Lee, NJ 07024
Aqua-Chem Inc., P.O. Box 421, Milwaukee, WI 53201
Riley-Beaird, P.O. Box 31115, Shreveport, LA 71130
FANS—VENTILATORS—BLOWERS
American United Marine Corp., 5 Broadway, Rte. 1, Saugus, MA 01906
Argo Marine, 140 Franklin St., New York, NY 10013
Hartzell Fan, Division of Castle Hills Corp., 901 S. Downing St., P.O. Box 919, Piqua, OH 45356
Zidell Explorations, 3121 S.W. Moody St., Portland, Ore. 97201
FENDERING SYSTEMS—Dock & Vessel
Hughes Bros., Inc., 17 Battery Place, New York, N.Y. 10004
InterTrade Industries. 15301 Transistor Lane, Huntington Beacn, CA 92649
Johnson Rubber Co., Duramax Marine Div., 16025 Johnson St., Middle-field, OH 44062
Samson Ocean Systems, Inc., 99 High St., Boston, MA 02110
Seeward International, Inc., 6269 Leesburg Ave., Falls Church, Vo., 22044 Samson Ocean Systems, Inc., 99 High St., Boston, MA 02110 Seaward International, Inc., 6269 Leesburg Ave., Falls Church, Va. 22044 FILTERS FILTERS
Dahl Manufacturing, Inc., 2521 Raitroad Ave., Ceres, CA 95307
Wm. W. Nugent & Co., P.O. Box 948. Skokie. IL 60076
FINANCING—Leasing
A.G. Becker Paribus Inc., 2 First National Plaza. Chicago, IL 60670
Yegen Marine, P.O. Box 25504, Ft. Lauderdale, FL 33320
FIRE PROTECTION, DETECTION, & ALARM SYSTEMS
FEV. J. WOOLSTEED Plans | Electrical National Plaza | Chicago | Land | Chicago | Land | Chicago | Land | Chicago | Land | Chicago EEV. Inc. 7 Westchester Plaza. Elmsford, NY 10523
Walter Kidde, Walter Kidde Dr.. Wake Forest, NC 27586
Wormald Fire Systems, One Stanton St., Marinette, WI 54143
FUEL OIL/ADDITIVES—Analysis & Combustion Testing
Ferrous Corporation, 910-108th N.E., P.O. Box 1764, Bellevue, WA
Fuji Trading (America) Ltd., 17 Battery Place, New York, NY 10004
Rolfite Products Inc., 300 Broad Street, Stamford, CT 06901
FURNITUEE FURNITURE
Bailey Carpenter & Insulation Co.. 34 Sullivan Street, Brooklyn, N.Y. 11231
Comfort-Mate, Inc., 7988 NW 56th Street, Miami, FL 33166
GALLEY EQUIPMENT
Argo Marine, 140 Franklin St., New York, NY 10013
Insinger Machine Company, 6245 State Rd., Philadelphia, PA 19135
Kiefer Corporation, W227 N546 Westmound Dr., Waukesha, WI 53186
GANGWAYS GANGWAYS
Rampmaster Inc., 9825 Osceola Blvd., Vero Beach, FL 32960
HATCH & DECK COVERS—Chain Pipe
Camlock Flange Sales Corp., 60 Imp Dr., Inwood, NY 11696
Hayward Marine Products, 900 Fairmount Avenue, Elizabeth, NJ 07207
Marine Moisture Control Co., 60 Imp Dr., Inwood, NY, 11696
MacGregor-Navire International, Box 8991, S. 402 74 Goteborg, Sweden
MacGregor-Novire U.S.A. Inc., 135 Dermody St., Cranford, NJ 07016
Julius Mock & Sons, Inc., 20 Vesey Street, New York, NY 10007
J.E. Steigerwald Co., Inc., 5515 Belair Rd., Baltimore, MD 21206
HEAT EXCHANGERS
Alfo-Laval, Inc., Dept. MR-2, 2115 Linwood Ave., Fort Lee, NJ 07024
American Standard Inc., Heat Transfer Div., Buffalo, NY 14240
Riley-Beard, P.O., Box 31115, Shrevepon, LA 71130
HULL CLEANING

**HULL CLEANING** 

Butterworth Inc. (USA), 3721 Lapas Dr., P.O. Box 18312, Hauston, TX 77223-9989 Butterworth Systems (UK), 123 Beddington Lane, Craydon CR9 4NX England Gulf International Divers, P.O. Box 1342, Gretna, LA 70052
Performance Hull Cleaning Services, Inc., P.O. Box 655, New Orleans, LA 70059-0655 /0059-0655
Phosmarin Equipment, 21, Boulevard de Paris, 13002 Marseille, France
Seaward Marine Services, Inc., 6269 Leesburg Pike, Falls Church, VA 22044
Stork Services B.V., P.O. Box 2013, 7750 CA Hengelo, Holland
HYDRAULICS HYDRAULICS
Aeroquip Corp., 1130 Maynard Roaa, Jackson, MI 49202
HRS, Inc., 3334 Victor Court, Santo Clara, CA 95050
Hydronautics, 6338 Lindmar Drive, Goleta, CA 93017
INERT GAS—Generators—Systems
Foster Wheeler Bailer Corp., 110 Sa. Orange Ave., Livingston, N.J. 07039
Maritime Protection A/S, N. American Agents, American United Marine
Corp., 5 Broadway, Rte. 1, Saugus, MA 01906
Salwico Inc., 5 Marine View Plaza, Hoboken, NJ 07030
INSULATION—Cloth, Fiberglass

Bailey Carpenter & Insulation Co., Inc., 74 Sullivan St., Brooklyn, N.Y. 11231 Insurance
Adams & Porter, 1819 St. James Place, Houston, Texas 77027
Adams & Porter, 1819 St. James Place, Houston, Texas 77027
Adams & Porter, 1 World Trade Center, Suite 8433, New York, N.Y. 10048
Assurance Foreningen Skuld, P.O. Box 1376 Vika, Stortingagaten 18,
N-OSLO 1, Norway
R.A. Fullon & Company Insurance Services, 100 California St., San Francisco, CA 94111
Midland Insurance Co., 160 Water St., New York, N.Y. 10038
United States P&I Agency, Inc., 80 Marden Lane, New York, NY 10038
JOINER—Watertight Doors—Paneling
Bailey Distributors, Inc., 74 Sullivan St., Brooklyn, NY 11231
Isolamin Panels, c/o Consafe, Inc., P.O. Box 40339, Houston, TX 77040
Mosonite Commercial Division, Dover, OH 44622
Megadoor Inc., 441 Lexington Ave., Suite 903, New York, NY 10017
Walz & Krenzer, Inc., 400 Trobold Road, Rochester, NY 14624
KEEL COOLERS
R.W. Fernstrum & Co., 1716 Eleventh Ave., Menominee, MI 49858
Johnson Rubber Co., Duramax Marine Div., 16025 Johnson St., Middle-field, OH 44062
LIGHTING EQUIPMENT—Lamps, Fixtures, Searchlights
ACR Electronics, Inc., P.O. Box 2148, Hollywood, FL 33022
Browning Marine Inc., (Aqua Signal) 33W 480 Fabyan Parkway, Ste 105,
West Chicago, IL 60185
Keuffel & Esser/Kratos, 20 Whippany Rd., Morristown, NJ 07960
Midland-Ross Corp., Russellstoll Division, 530 W. Mt. Pleasant Ave., Livingston, NJ 07039
Oceanic Electrical Mfg. Co., 157 Perry St., New York, NY 10014
Oreck Corp., 100 Plantation Rd., New Orleans, LA 70123
Perko Inc., P.O. Box 6400D, Miami, Florida 33164
Phoenix Products Company, Inc., 4769 North 27th Street, Milwaukee, WI 53209
Port Electric Supply Corp., 157 Perry St., New York, NY 10014
SSAC Inc., P.O. Box 395, Liverpool, NY 13088 Superior Energies, Inc., P.O. Drawer 386, Groves, TX 77619 INSURANCE Port Electric Supply Corp., 157 Perry St., New York, NY 10014 SSAC Inc., P.O. Box 395, Liverpool, NY 13088 LINE BLINDS LINE BLINDS
Stacey Fetterolf Corp., P.O. Box 103, Skippack, PA 19474
MACHINE TOOLS
Republic-Lagun Machine Tool Co., 1000 E. Carson St., Carson, CA 90749
MACHINERY MAINTENANCE, REPAIR, OVERHAUL, AND TESTING
AMT Inc., 2400 N.W. 39th Ave., Miami. FL 33142
Amermorine USA Inc., P.O. Box 9205, Baltimore, MD 21222
American General/Levin Corp., 445 Littlefield Ave., So. San Francisco, CA 94080 94080 Essex Machine Works, Essex. CT 06426 Jered Brown Brothers Inc.. 1300 Coolidge, P.O. Box 2006, Troy, MI 48007-2006 Scotchman Industries, Inc., P.O. Box 850, Philip, SD 57567-0850 METALS Boyou Steel Corp., P.O. Box 5000, Laplace, LA 70068
Inland Steel Company, 30 West Monroe Street, Chicago, IL 60603
International Grating, Inc., 7625 Parkhurst, Houston, TX 77028
MOQRING SYSTEMS Samson Ocean Systems, Inc., 99 High Street, Boston, Mass. 02110
NAME PLATES—BRONZE—ALUMINUM
Duramax Metals, Inc., 2401 Wesley Street, Portsmouth, VA 23707
NAVAL ARCHITECTS, MARINE ENGINEERS, SURVEYORS 23454
Amirikian Engineering Co., Chevy Chase Center Bldg., Suite 505, 35 Wisconsin Circle, Chevy Chase, Md. 20015
Art Anderson Associates, 148 First St., Bremerton, WA 98310
B C. Research, 3650 Wesbrook Mall, Vancouver, B C., Canada V6S 2L2
Del Breit Inc., 326 Picayune Place (Suite 2011, New Orleans, LA 70130
Bretagne ACB Corp., 344 Camp St., Suite 1000, New Orleans, LA 70130
C.D.I. Marine Co., Regency East. Ste 222, 9951 Atlantic Blvd., Jacksonville, FL 32211 FL 32211
C.T. Marine, 18 Church Street, Georgetown, CT 06829
CADCOM, 107 Ridgely Ave., Annapolis, MD 21401
Phillips Cartner & Co., Inc., 203 So. Union St., Alexandria, VA 22314
Century Engineering, Inc., 32 West Rd., Towson, MD 21204
Childs Engineering Corp., Box 333, Medfield, Mass. 02052
John P. Colletti & Associates, P.O. Box 13378, Piltspurgh, PA 15243
Crandall Dry Dock Engrs., Inc., 21 Pottery Lane, Dednam. Mass. 02026
Crane Consultants Inc., 15301 1st Ave., So. Seattle, Woshington 98148
C.R. Cushing & Co., Inc., One World Trade Center, New York, N.Y. 10048
Design Associates Inc., 14360 Chef Menteur Highway, New Orleans, LA 70129 Designers & Planners, Inc., 1725 Jefferson Davis Highway, Suite 700, Ar-lington, VA 22202 Donhaiser Marine, Inc., 11511 Katy Freeway, Houston, TX 77079
ECO Inc., 1036 Cape St. Claire Center, Annapolis, MD 21401
Parker C. Emerson & Associates, 17935 Cardinal Drive, Lake Oswego, Oregon 97034
Encon Management & Engineering Consultant Services, P.O. Box 7760, Beaumont, TX 77706
Express Engineering Inc., 4122, 97th American Consultant Services, P.O. Box 7760, Box press Engineering Inc., 4122, 97th American Consultant Services, P.O. Box 7760, Box press Engineering Inc., 4122, 97th American Consultant Services, P.O. Box 7760, Box press Engineering Inc., 4122, 97th American Consultant Services, P.O. Box 7760, Box press Engineering Inc., 4122, 97th American Consultant Services, P.O. Box 7760, B Express Engineering Inc., 4122 87th Ave. N.W., Gig Horbor, WA 98335 Christopher J. Foster, Inc., 16 Sintsink Drive East, Port Washington, NY 11050 Friede and Goldman Ltd., 935 Gravier St., New Orleans, LA 70112 GEOD Corporation, 73 Oak Ridge Road, NJ 07438 Giannotti & Associates, Inc., 703 Giddings Ave., Suite U-3, Annapolis, MD 21401 21401 Gibbs & Cox, Inc. 119 West 31st Street, New York, NY 10001 John W. Gilbert Associates, Inc.. 66 Long Wharf, Boston, MA 02110 The Glosten Associates, Inc., 610 Colman Bldg., 811 First Ave.. Seattle, WA Phillip Gresser Associates, Ltd.: 3250 South Ocean Blvd., Palm Beach, FL 33480 Morris Guralnick Associates, Inc., 620 Folsom Street, Suite 300, San Francisco, CA 94107
J.J. Henry Co., Inc., Two World Trade Center—Suite 9528, New York, N.Y. 10048 10048

Hi-Test Laboratories, Inc., P.O. Box 226, Buckingham C.H., VA 23921
Hoffman Maritime Consultants Inc., P.O. Box 186, Glen Head, NY 11545
Intramarine, Inc., P.O. Box 53043, Jacksonville, FL 32201
R.D. Jacobs & Associates, 11405 Main St.. Roscoe, IL 61073
Capt. Ernest James, 2849 Beavercrest Dr.. Lorain. OH 44053
Jantzen Engineering Co., 6655-H Amberton Drive, Baltimore, Md. 21227
James S. Kragen & Co., Inc.. 3333 Rice St., Miami, Fla. 33133
Rodney E. Lay & Associates, 13891 Atlantic Blvd. Jacksonville, FL 32225
Alan C. McClure Associates, Inc., 2600 South Gessner, Houston, TX 77063
John J. McMullen Associates, Inc., 1 World Trade Center, New York, N.Y. 10048

MacLear & Harris, Inc., 28 West 44 Street, New York, N.Y. 10036 Mampaey Marine Engineering B.V., P.O. Box 667, 3300 AR Dordrecht, Holland

Edison, N.J. 08817 Palmer Products Inc., P.O. Box 8, Worcester, PA 19490 Products Research & Chemical Corp., 5454 San Fernando Rd., Glendale, CA 91203 EG&G Seotol, Engineered Products Div., Marine Products Group, Warwick, R1 U2888
Electric Tochometer Corp., 68th & Upland St., Philadelphia, Pa. 19142
Penco Division/Hudson Engineering Co., P.O. Box 68, Bayonne, NJ 07002
SHIPBREAKING—Salvage
The Boston Metals Co., 313 E. Baltimore St., Baltimore, Md. 21202
Fred Devine Diving & Salvage, Inc., 6211 N. Ensign, Swan Island, Portland, OR 97217 Products Research & Chemical Corp., 3407 56.... CA 91203 Salwico Glassflake, Inc., 5 Marine View Plaza, Hoboken, NJ 07030 Seaguard, 4030 Seaguard Ave., Portsmouth, VA 23705 Selby, Battersby & Company, 5220 Whiby Avenue, Philadelphia, PA 19143 SermeTel, Inc., 4401 SermeTel Dr., Moss Point, MS 39563 Teledyne Metal Finishers, 1725 East 27th St., Cleveland, OH 44114 92109
Marine Technical Associates, Inc., 95 River Rd., Hoboken, NJ 07030
George E. Meese, 194 Acton Rd., Annapolis, Md. 21403
Metritape Inc., P.O. Box 2366, Littleton, MA 01460
R. Carter Morrell, 715 S. Cherokee, Bartlesville, OK 74003
NKF Engineering Assoc., Inc., 8150 Leesburg Pike, Vienna, VA 22202
Nelson & Associates, Inc., 1405 N.W. 167th Street, Miami, FL 33169
Nickum & Spaulding Associates, Inc., 2701 First Ave., Seattle, WA 98121
Northern Marine, P.O. Box 1169, Traverse City, Ml 49685
Ocean-Oil International Engineering Corporation, 3019 Mercedes Blvd., New Orleans, La. 70114 7 Zidell Explorations, Inc., 3121 S.W. Moody St., Portland, Ore. 9720 PETROLEUM SUPPLIES
Shell Oil Co., 1 Shell Plaza, Houston, Texas 77002 SHPBUILDING EQUIPMENT
Peorlson Engineering Co., P.O. Box 8, Kendall Branch, Miami, FL 33156
Total Transportation System Inc., 813 Forest Dr., Newport News, VA 32606
Total Transportation Systems (International) A/S, Bjørnegarden, P.O. Box Acquatic Marine Systems, Inc., P.O. Box 326, Williamsville, NY 14221 PIPE-HOSE—Cargo Transfer, Clamps, Couplings, Coatings Camlock Flange Sales Corp., 60 Inip Dr., Inwood, NY 11696 Hydro-Craft, Inc., 1821 Rochester Industrial Dr., Rochester, Mt 48063 Knights Piping Inc., 5309 Industrial Rd., Pascagoula, MS 39567 Kubota Ltd., 2-47, Shikit Suhigashi 1-Chome, Naniwa-Ku, Osaka 556-91, 28, N5201, Oslo, Norway SHIPBUILDING STEEL SHIPBÜILDING STEEL

Armoo Steel Corp., 703 Curtis St., Middletown, Ohio 45042
Bethlehem Steel Corp., Martin Tower, Bethlehem, PA 18018
Tiline, P.O. Box 729, Albany OR 97321
Welded Beam Company, P.O. Box 280, Perry OH 44081
SHIPBUILDING—Repairs, Maintenance, Drydacking
Alabama Maritime Corp., P.O. Box 3026, Mobile, AL 36652
Amsterdam Drydock Company, Post Box 3006, 1003 AA, Amsterdam, Halland Ocean-Oil International Engineering Corporation, 3019 Mercedes Blvd., New Orleans, La. 70114
Offshore Power Systems, 8000 Arlington Expressway, Jacksonville, FL 32211
PRC Guralnick, 5252 Balbaa Ave., San Diego, CA 92117
Pearlson Engineering Co., Inc., 8970 S.W. 87th Ct., Miami, Florida 33156
S.L. Petchul, Inc., 1380 S.W. 57th Avenue, Fort Lauderdale, FL 33317
M. Rosenblatt & Son, Inc., 350 Broadway, New York, NY 10013 and 667
Missian St., San Francisco, CA 94105
Schmahl and Schmahl, Inc., 1209 S.E. Third Ave., Fort Lauderdale, Florida 33316 Japan Metropolitan Plumbing Supply Corp., 5000 Second St., Long Island City, NY Penco Division/Hudson Engineering Co., P.O. Box 68, Bayonne, NJ 07002 Selkirk Metalbestos, Box 19000, Greensboro, NC 27419 Stauff Corporation, 21-31 Industrial Park, Waldwick, NJ 07463 Holland
Asmar Shipyards Co., Astilleros y Maestranzs de la Armada, Prat 856, Piso
14, Casilla 1,50-V, Valpariso, Chile, S.A.
Astilleros Balboa, S.A., c/o Jackson Marine Corp., 17 Battery Place, New
York, NY 10004
Atleliers et Chantiers de Bretagne—ACB, 44040 Nantes Cedex, France
Atlantic Dry Dock, P.O. Box 276, Ft. George Island, Jacksonville, FL 32226
Atlantic Marine Inc., P.O. Box 138, Ft. George Island, Jacksonville, FL 32226 PLASTICS—Marine Applications Hubeva Marine Plastics, Inc., 390 Hamilton Ave., Bklyn, N.Y. 11231 33316 SEACOR Systems Engineering Associates Corp., 19 Perina Blvd., Cherry Hill, NJ 08003 (Publications Division at Cherry Hill location) STV/Sanders & Thomas, Inc., 1745 Jefferson Davis Hwy., Arlington, VA PROPULSION EQUIPMENT—Bowthrusters, Diesel Engines, Gears, Propellers, Shafts, Turbines
American Lohmann Corp., 1415 Chestnut Ave., Hillside, NJ 07205
Armco Steel/Advanced Materials Div., 703 Curtis St., Middletown, OH 22202
Seaworthy Engine Systems, 36 Main Street, Essex, CT 06426
Seaworthy Engine Systems, 17 Battery Place, New York, NY 10004
George G. Sharp, Inc., 100 Church St., New York, NY. 10007
Simmons Associates, P.O. Box 760, Sarasota, FL 33578
R.A. Stearn, Inc., 253 N. 1st Ave., Sturgeon Bay, WI 54235
J.F. Stroschein Associates, 666 Old Country Rd., Garden City, NY 11530
Richard R. Taubler Inc., 8 Columbia St., Milford, Del. 19963
Timsco, 622 Azalea Road, Mobile, AL 36609
Tracor Hydronautics, Inc., 7210 Pindell School Rd., Laurel, MD 20707
Uhlig & Associates, Inc., 8295 SW 188th St., Miami, FL 33157
VeVeY Engineering Works Ltd. U.S. Rep: Carl G. Brimmekamp & Co., Inc., 102 Hamilton Ave., Stamford, CT 06902
Thomas B. Wilson, Associates, 1258 North Avalon Blvd., Wilmington, CA 90744 32226
Avondale Shipyards, Inc., P.O. Box 52080, New Orleans, La. 70150
Bath Iron Works Corp., 700 Washington St., Bath, ME 04530
Bay Shipbuilding Corp., 605 North 3rd Ave., Sturgeon Bay, WI 54235
BFC Marine Services, Inc., 25 Fifth St., Brooklyn, NY 11231
Bender Shipbuilding & Repair Co., Inc., P.O. Box 42, Mobile, AL 36601
Bethlehem Steel Corp., Martin Tower, Bethlehem, PA 18018
Blohm & Voss Company, 55 Morris Avenue, Springfield, NJ 07081
Burmerister & Wain Skibsvaerft A/S, P.O. Box 2122, Refshaleoen-1015 Copenhagen K-Denmark
Burrard Yarrows Corporation, P.O. Box 86099, North Vancouver, B.C., Canada 45043
Avondale Shipyards, Inc., P.O. Box 52080, New Orleans, La. 70150
Bird Johnson Company, 110 Norfolk St., Walpole, Mass 02081
Bombardier, 1051 Dickson, Montreal, Quebec, Canada H1N 2H7
Burmeister & Wain Alpha Diesel AS, DK-1400 Copenhagen K, Denmark
Caterpillar Engine Division, 100 N E. Adams, Peoria, IL 61629
Colt Industries Inc. (Fairbanks Morse Engine Div.), 701 Lawton Aven
Beloit, WI 53511
Calumbian Broaze Corporation, 214 No. Main Start Formack National Columbian Bronze Corporation, 216 No. Main Street, Freeport, NY 11520 Combustion Engineering, Inc., Windsor, Connecticut 06095
Daihatsu Diesel (USA) Inc., 1211 Ave. of the Americas, New York, NY 10036
Deutz Corp., 7585 Ponce de Leon Circle, Atlanta, GA 30340
Diesel Marine International, Ltd., c/o NORSHIPCO, P.O. Box 2100, Norfolk, VA 23501 Canada Caneco Shipyard, Rua Carlos Seidl, 714, Caju, 20.931, Rio de Janeiro, RJ, Yacht Design Institute, 9 Main St., Blue Hill, ME 04614 Brazil
Cantieri Navali Riuniti, Via Cipro, 11, 16100 Genova, Italy
Carrington Slipways Pty. Ltd., Old Punt Rd., Tomago NSW Australia 2322
China Shipbuilding Corp., 3 Chung Kong Rd., Hsia Kang, Kaohsiung, Taiwan, Republic of China
Conrad Industries, P.O. Box 790, Morgan City, La. 70380
Curacao Drydock Company Inc., 26 Broadway, Suite 741, New York, NY 10004 NAVIGATION & COMMUNICATIONS EQUIPMENT NAVIGATION & COMMUNICATIONS EQUIPMENT
Alden Electronics, 1145 Washington St., Westborough, MA 01581
American Hydromath Co., Buckwheat Bridge Rd., Germantown, N.Y. 12526
Anschutz & Co. GmbH, Postfach 6040, D-2300 Kiel 14, West Germany
Alkinson Dynamics, Section 6, 10 West Orange Ave., South San Francisco.
CA 94080
CMC Communications Inc., 5479 Jetport Industrial Blvd., Tompa, FL 33614
Cybernet International, Inc., 7 Powder Horn Dr., Warren, NJ 07060
A/S Elektrisk Bureau, P.O. Box 98, N-1360 Nesbru, Norway
Electro-Nav Inc., 840 Bond Street, Elizabeth, NJ 07201
EPSCO Marine, 580 Wholesalers Parkway, Harahan, LA 70123
Fleet Marine, 1820 N.E. 146th Street, North Miami, FL 33181
Furuno U.S.A., 271 Harbor Way, S. San Francisco, CA 94080
Harris Communications (RF Communications), 1680 University Avenue,
Rochester, NY 14610
Hose McCann Telephone Company, Inc., 9 Smith Street, Englewood, NJ
07631 tolk, VA 23301 Ellioit Company, 1809 Sheridan Ave., Springfield, OH 45505 Escher Wyss GmbH, (Member Sulzer Group), Ravensburg, Germany General Electric Co., Diesel Power Products, 2901 E. Lake Rd., Erie, PA 16531
General Motors, Electro-Motive Division, LaGrange, IL 60525
George Engine Company, Inc., Lafayette, LA
Golten Marine Co., Inc., 160 Van Brunt St., Brooklyn, NY 11231
Harbormoster, 36 Hancock St., Quincy, MA 02171
Krupp Mak Diesels, Inc., 4329-33 Di Paolo Center, Glenview, IL 60025
Lips Propellers, 3617 Koppens Way, Chesapeake, VA 23323
M.A.N.-B&W Diesel, 2, Ostervei, DK-4960 Holeby, Denmark
MTU of North America, One E. Putnam Ave., Greenwich, CT 06830, 10450
Corporate Dr., Sugarland, TX 77478; 2945 Railroad Ave., Morgan City
LA 70203; 180 Nickerson St., Seattle, WA 98109; 1730 Lynn St., Arlington, VA 22209 Daewoo International (America) Corp., 437 Madison Ave., New York, NY 10022 Daewoo Shipbuilding & Heavy Machinery Ltd., Ayangri, Changsung-PO, Koje-Kun, Kyungnam, Korea

Dorbyl Ltd., Military Road, 1 Industrial Sites, West Bank, 5201 East London, Republic of South Africa

Dravo Marine Equipment Company, Neville Island, Pittsburgh, PA 15225

Eastern Marine, Inc., P.O. Box 1009, Panama City, FL 32401

FMC Corp., Marine & Rail Equipment Div., 4700 N.W. Front Ave., Portland, Oregon 97208

Far Fast Leyinoston Shipbuilding Ltd., 31 Shipvard Rd., Jurana Town, Sin-MWM-Murphy Diesel, 12 Greenway Plaza, Suite 1100, Houston, TX 77046 Mapeco Products, Inc., 20 Vesey St., New York, NY 10007 Michigan Wheel, 1501 Buchanan Ave., S.W., Grand Rapids, MI 49507 National Marine Service Louisiana, Inc., 222 Bayou Rd., Belle Chasse, LA 70037 Gregori 77200 Far East Levingston Shipbuilding Ltd., 31 Shipyard Rd., Jurang Town, Singapore 2262 07631 Japan Radio Co., Ltd., Akasaka Twin Tower (Main), 17-22 Akasaka 2-chome, Minato-ku, Tokyo 107, Japan King Radio Carporation, 400 North Rodgers Rd., Olathe, KS 66062 Kongsberg North America Inc., 135 Fort Lee Road, Leonia, NJ 07605 Kongsberg Vapenfabrikk, Norcontrol Division, P.O. Box 145, Horten 3191, apore 2202 istar Marine, 10 Pemberton Ave., No. Vancouver, B.C., Canada V7P 2R1
Gladding-Heorn Shipbuilding Corp., 1 Riverside Ave., Somerset, MA 02725
HBC Barge, Inc., Grant Building, Pittsburgh, PA 15219
Halter Marine, Inc., P.O. Box 29266, New Orleans, LA 70189
Hoboken Shipyards, Inc., 1301 Hudson St., Hoboken, NJ 07030
Hong Kong United Dockyards Ltd., P.O. Box 534, Kowloon Central Post
Office, Kowloon, Hong Kong
Hyundai Mipo Dockyard Ltd., 456 Cheonha-Dong, Ulsan, Korea
I.N.M.A. S.p.A., 19100 La Spezla, v. le S. Bartolameo 362, Italy
Jakobson Shipyard Inc., P.O. Box 329, Oyster Bay, NY 11771
Jeffboat, Inc., Jeffersonville, Ind. 47130
Keppel Shipyard Limited, 325 Telok Blangah Road, P.O. Box 2169, Singapore 0409
Koch Ellis Barge & Ship Service, P.O. Box 9130, Westwood, LA 70044 Kongsberg North America Inc., 135 Fort Lee Roda, Leonid, INJ U7003
Kongsberg Vapenfabrikk, Norcontrol Division, P.O. Box 145, Horten 3191,
Norway
Krupp Allas-Elektronik, 1453 Pinewood St., Rahway, NJ 07065
Lorain Electronics Corp., 2307 Leovitl Rd., Lorain, OH 44052
Magnavox Navigalion Systems, 2829 Maricapa Street, Torrance, CA 90503
Nav-Com, Inc., 9 Brandywine Drive, Deer Park, NY 11729
Navidyne Corp., 11824 Fishing Point Drive, Newport News, VA 23606
Perko Inc. (Lights), P.O. Box 6400D, Miami, FL 33164
Racal-Decca Marine, Inc., 4200 23rd Avenue West, Seattle, WA 98199
Radar Devices, Inc., 2955 Merced Street, San Leandro, CA 94577
Radio-Holland USA, Inc., 6033 South Loop East, Houston, TX 77033
Raytheon Marine Co., 676 Island Pond Raod, Manchester, N.H. 03103,
Raytheon Ocean Systems Company, Westminster Park, Risho Avenue, East
Providence, RI 02914
Raytheon Service Co., 103 Roesler Rd., Glen Burnie, MD 21061
Rivertronics, P.O. Box 247, Godfrey, IL 62035
Robertson Auto Pilot, 135 Fort Lee Road, Leonia, NJ 07605
Selesmar S.p.A., Casella Postale 9, 50020 Montagnana Val Di Pesa,
Firenze, Italy
Servo Corporation of America, 111 New South Road, Hicksville, NY 11802
Simrad, Inc., 2215 NW Market St., Seattle, WA 98107
Sperry Corporation, Great Neck, NY 11020
Simrad, Inc., 2215 NW Market St., Seattle, WA 98107
Sperry Corporation, Great Neck, NY 11020
Simrad, Inc., 2215 NW Market St., Seattle, WA 98107
Sperry Corporation, Great Neck, NY 11020
Simrad, Inc., P.O. Box 405, 3438, Lewisville, TX 75067
DILS—Marine—Additives Omnithruster Inc., 9515 Sorensen Ave., Santa Fe Springs, CA 90670 Omnithruster Inc., 9515 Sorensen Ave., Santa Fe Springs, CA 90670
Penske GM Power, Inc., 600 Parsippany Road, Parsippany, NJ 07054
Propulsion Systems, Inc., 21213 76 Ave. So., Kent, WA 98032
SACM (Societe Alsacienne De Constructions Mechaniques De Mulhouse) 1,
Rue De La Fonderie, Boite Postale 1210, 68054 Mulhouse Cedex, France
Schottel of America, Inc., 8375 N.W. 56 St., Miomi, FL 33166
Karl Senner, Inc., P.O. Box 10055, New Orleans, LA 70181
Skinner Engine Company, P.O. Box 1149, Erie, PA 16512
Sulzer Brothers, Dept. Diesel Engines, CH-8401 Winterthur, Switzerland
Transamerica Delaval Inc., Engine & Compressor Div., 550 85th Ave.,
Oakland, CA 94621
Transamerica Delaval, Inc., Turbine & Compressor Div., P.O. Box 8788 Transamerica Delaval, Inc., Turbine & Compressor Div., P.O. Box 8788. Trenton, N.J. 08650 Turbine Specialties, Inc., P.O. Box 207, West State Street Road, Solina, KS 67401 pore 0409
Koch Ellis Barge & Ship Service, P.O. Box 9130, Westwego, LA 70094
Kone Corp., P.O. Box 6, SF-05801, Hyvinkaa, Finland
Leevac Corporation, P.O. Box 2607, Morgan City, LA 70381
Lockheed Shipbuilding and Construction Co., 2929 16th Avenue, S.W., Seattle, Wash. 98134
M.A.N. GHH Sterkrade, P.O.B. 110240, D-4200 Oberhausen 11, West
Germany Turbine Specialties/Gulf Coast, Inc., 1900 Industrial Blvd., Harvey, LA 70058 M.A.N. GHH Sterkrade, P.O.B. 110240, D-4200 Obernausen 11, West Germany
McDermott, Incorporated, 1010 Common Street, New Orleans, LA 77227
Main Iron Works, Inc. P.O. Box 1918, Houma, LA 70361
Marinette Marine Corporation, Marinette, WI 54143
Marystown Shipyard Limited, P.O. Box 262, Marystown, Newfoundland, Canada AOE 2MO
Jos L. Meyer GmbH & Co., P.O. Box 2990 Papenburg 1, West Germany
Misener Industries, Inc., 5353 Tyson Avenue, P.O. Box 13625, Tampo, Fla.
33681 Voith Schneider America, 159 Great Neck Rd., .Ste 200, Great Neck, NY WaBCO Fluid Power, an American-Standard Company, 1953 Mercer Rd., Lexington, KY 40505
Wartsila Power Inc., 5132 Taravella Rd., P.O. Box 868, Marrero, LA 70072
Waukesha Engine Division, Waukesha, WI 53187
Welco Industries, Inc., 9027 Shell Rd., Cincinnati, OH 45236
ZF of North America, Inc., 3225 Commercial Avenue, Northbrook, IL 60062
ZF of North America, Inc. IMotive Power Corporation, P.O. Box 365, Mineola, NY 11501)
PUMPS—Repairs—Drives
Argo Marine, 140 Franklin St., New York, NY 10013
Jim's Pump Repair, 48-55 36th St., Long Island City, NY 11101
Megator Corporation, 562 Alpha Drive, Pittsburgh, PA 15238
Penco Division/Hudson Engineering Co., P.O. Box 68, Bayonne, NJ 07002
Sims Pump Valve Co., Inc., 1314 Park Ave., Hoboken, NJ 07030
Transamerica Delaval, IMO Pump Division, P.O. Box 447, Monroe, NC 28110
Vila Motivator Company, 200 West 20th St., New York, NY 10011 OILS—Marine—Additives
Gulf Oil Company—U.S. (Domestic Oils), 909 Fannin Street, Houston, TX Mitsubishi Heavy Industries, Ltd., 5-1, Marunochi 2-chome, Chiyoda-ku, To-Gulf Oil, New York District Sales Office (Domestic), 433 Hackensack Ave Milsubishi Teday Industries, Ltd., 3-1, Marunochi 2-chome, Chiyoda-Ru, 18-kyo, 100 Japan
Monark Boat Co., P.O. Box 210, Monticello, Ark. 71655
Moron Shipping Agencies, 10 Jefferson Blvd., Warwick, Rl 02888
Moss Point Marine Inc., P.O. Box 1310, Escatawpa, MS 39552
Nashville Bridge Company, P.O. Box 239, Nashville, TN 37202
National Marine Service (Shipyard Division), P.O. Box 38, Hartford, IL Out Oil, New York District Sales Office Domestic), 433 Hackensack Anue, Hackensack, NJ 07601
Gulf Oil Trading Co., 535 Madison Ave., New York, NY 10022
Mobil Oil Corp., 150 East 42 Street, New York, NY 10017
Shell Oil Co., 1 Shell Plaza, Houston, Texas 77002
Texaco, Inc. (International Marine), 135 East 42nd St., N.Y., N.Y. 10017 Alfa Laval, Inc., Dept. MR-2, 2115 Linwood Ave., Fort Lee, NJ 07024 Biospherics Incorporated, 5001 Forbes Blvd., Lanham, MD 20801 Butterworth Inc. (USA), 3721 Lapas Dr., P.O. Box 18312, Houston, TX 77223-9989 Notional Steel & Shipbuilding Corp., San Diego, Calif. 92112
Newport News Shipbuilding & Dry Dock Co., 4101 Washington Ave., Newport News, Va. 23607
North Florida Shippards, P.O. Box 3863, Jacksonville, FL 32206
O.A.R.N. (Officine Allestimento-Riprazioni Navi), P.O. Box 1395, Genoa, Italy 16100
Oversees Shippards, Inc. 2014, 476, 476 OIL/WATER SEPARATORS Vita Motivator Company, 200 West 20th St., New York, NY 10011 Warren Pumps Division, Bridges Avenue, Warren, MA 01083 Wilden Pump & Engineering Co., 22060 Van Buren St., P.O. Box 845, Colton, CA 92324 REFRIGERATION—Refrigerant Valves
Bailey Refrigeration Co., Inc., 74 Sullivan St., Brooklyn, N.Y. 11231
Port Refrigeration Div., 157 Perry St., New York, NY 10014
ROLLING SYSTEMS
Hilman, Inc., 2604 Atlantic Ave., Wall (Belmar), NJ 07719
ROPE—Manila—Nylon—Hawsers—Fibers
American Mfg. Co., Inc., Willow Avenue, Honesdale, Pa. 18431
Atlantic Cardage Corp., 60 Grant Avenue, Carteret, NJ 07008
DuPont Co., KEVLAR Aramid Fiber, Room G-15465, Wilmington, DE 19898
Norton Chemplast, 309-150 Dey Rd., Wayne, NJ 07470
Samson Ocean Systems, Inc., 99 High Street, Boston, Mass. 02110
Tubbs Cardage Company, P.O. Box 709, Orange, CA 92666
Wall Industries, Inc., P.O. Box 560, Elkin, NC 28621
RUDDER ANGLE INDICATORS—STEERING
Hy-Drive America Corp., 3629 Vernon Blvd., Long Island City, NY 11106
Marine Drive Systems, S19 Raritan Center, Edison, NJ 08817
Robertson, 135 Fort Lee Rd., Leonia, NJ 07605
SAFETY EQUIPMENT Butterworth Systems (UK), 123 Beddington Lane, Croydon CR9 4NX, Butterworth Systems (UK), 123 beautington Catte, Crayland Cendrico, Inc. (Westfalia Separators), 100 Fairway Court, Northvale, NJ 07647
Dahl Manufacturing, Inc., 2521 Railroad Ave., Ceres, CA 95307
Microphor, Inc., P.O. Box 490, Willits, CA 95490
Marine Moisture Control Co., 60 Inip Dr., Inwood, NY 11696
National Fluid Separators, Inc., 1239 Hanley Industrial Court, St. Louis, MO 43144 Overseas Shippards, Inc., 21 West St., New York, NY 10006
Patti Industries Inc., South B St., Pensacola, FL 32573
Progressive Shipbuilders & Fabricators, Inc., P.O. Box 9130, Houma, LA 70361 70361
Promet (PTE) Ltd., 27 Pandam Rd., Jurong Industrial Estate, Singapore 22
Promet Marine Services Corp., 242 Allens Ave., Providence, Rl 02906
Puerto Rico Drydock & Marine Terminals, Inc., P.O. Box 2209, Son Juan, Puerto Rico 00903
Rauma-Repola, 26100 Rauma 10, Finland
Samsung Shipbuilding & Heavy Industries Co., Ltd., Samsung Main Bldg.
250, 2Ka, Taepyong-ro, Chung-ku, Seoul, Korea
St. Louis Ship, 611 East Marceau St., St. Louis, MO 63111
Savannah Shippard Co., P.O. Box 787, Savannah, GA 31402
Schiess Defries, Postfach 111146, Schiess-Str. 61, D-4000 Dusseldorf 11,
West Germany Phoenix Oil Refiner Co., Inc., 330 Hill Ave., Nashville, TN 37210

PAINTS—COATINGS—CORROSION CONTROL

American Abrasive Metals, 460 Coit Street, Irvington, NJ 07111

Ameron, 4700 Ramona Blvd., Monler ey Park, CA 91754

Argo Marine, 140 Franklin St., New York, NY 10013

Bareco, 6910 East 14th St., Tulsa, OK 74112

CLEMCO, P.O. Box 7680, San Francisco, CA 94120

"CONSOL" manufactured by Contact Paint & Chemical Co. Inc., 200 S. Franklintown Rd., Baltimore, MD 21223

Devoe Marine Cootings Co., P.O. Box 7600, Louisville, KY 40207

E.I. Dupont De Nemours & Co., Inc., Nemours Bldg. Rm. N-2504-2. Wilmington, DE 19898

Esgard, Box 2698, Lafayette, LA 70502

Eureka Chemical Company, 234 Lawrence Avenue, So. San Francisco, CA 94080

Grow Group, Inc., 200 Park Ave., New York, NY 10037 Phoenix Oil Refiner Co., Inc., 330 Hill Ave., Nashville, TN 37210 West Germany
Service Machine Group, Inc., P.O. Box 2664, Morgan City, LA 70381
Southbay Boat Inc., P.O. Box 13308, San Diego, CA 92113
Southern Oregon Marine Engineering and Construction. P.O. Box 1220,
Coos Bay, OR 97420
Southwest Marine, Inc., P.O. Box 13308, San Diego, Ca 92113
Swiftships Inc., P.O. Box 1908, Morgan City, LA 70380
Thomas Marine, 37 Bransford St., Patchogue, NY 11772
Todd Shipyards Carp., 1 State St. Plaza, New York, N.Y. 10004
Tracor Marine, P.O. Box 13107, Port Everglades, Fla. 33316
Union Dry Dock & Repair Co., Foot of Pershing Rood, Weehawken, N.J. 07087
Veroline Estoleiras Pennidas De Part S. S. S. S. Kobertson, 139 Fort Lee Rd., Leonia, N.J. 07605
SAFETY EQUIPMENT
Elkhart Brass Manufacturing Co., Inc., P.O. Box 1127, Elkhart, IN 46515
Wormald Fire Systems, One Stanton St., Marinette, WI 54143
SANITATION DEVICES—Pollution Control
Argo Marine, 140 Franklin St., New York, NY 10013
Envirovac Inc., 1260 Turret Dr., Rockford, IL 61111
Marine Moisture Control Co., Leg., 60 Leg. Dr., Lawood L.L., N.Y. 11696 94080
Grow Graup, Inc. 200 Park Ave., New York, NY 10017
Hempel Marine Paints, Inc., 65 Broadway, New York, NY 10006, 2425
Fountainview, Suite 340, Houston, TX 77057, P.O. Box 10265, New Orleans, LA 70181
International Paint Cornpany, Inc., 2270 Marris Avenue, Union, NJ 07083
Jaegle Paint Co., Inc., 1912 Darby Rd., Havertown, PA 19083
Jotun-Baltimore Copper Paint Co., 840 Key Highway, Baltimore, MD 21230
Magnus Maritec International Inc., 150 Roosevelt Pl., P.O. Box 150, Palisades Park, NJ 07650 Marine Maisture Control Co., Inc., 60 Inip Dr., Inwood, L.I., N.Y. 11696 National Sanitation Foundation, P.O. Box 1468, Ann Arbor, Mt 48105 SCAFFOLDING EQUIPMENT—Work Platforms McCausey Lumber Co., 7751 Lyndon, Detroit, MI 48238 Patent Scaffolding Co., One Bridge Ploza, Fort Lee, NJ 07024 Trus-Joist Corp., P.O. Box 60 Boise, ID 83704 U7087
Verolme Estoleiros Reunidos Do Brosil S.A., Rua Buenos Aires, 68, Rio de Janeiro—R1.—Brazil
Vickers Cockatoo Dockyard Pty. Ltd., P.O. Box 162 Milsons Point, N.S.W 2061, Australia SHAFT SEALS, REVOLUTION INDICATOR EQUIPMENT Bird-Johnson Co., 100 Norfolk St., Walpole, MA 02081 Crane Packing Company, 435 Regina Dr., Clarksburg, MD 20734 Zidell Explorations, Inc., 3121 S.W. Moody Street, Portland, OR 97201

## **BUYERS DIRECTORY**

SHIPPING-PACKING

Pilotage Consultants, Inc., P.O. Box 2046, New Hyde Park, NY 11040 SILENCERS

eaird, P.O. Box 31115, Shreveport, LA 71130 SMOKE INDICATORS

Robert H. Wager Co., Inc., Passaic Avenue, Chalham, N.J. 07928 STUFFING BOXES

Johnson Rubber Co., Duramax Marine Div. 16025 Johnson St., Middle-field, OH 44062

rieta, UT 44062
Smith-Meeker Engineering Co., 157 Chambers Street, New York, NY 10007
SURVEYORS AND CONSULTANTS
Francis B. Crocco, Inc., P.O. Box 1411, San Juan, Puerto Rico 00903
Frank Jeffrey & Assoc, 5201 Westbank Exp., Suite 206. Marrero, LA 70073
M.A. Stream Associates, Inc., 400 Second Ave. W., Seattle, WA 98119
TANK CLEANING
Butterwith Inc. (IISA) 3721 Janes Dr., P.O. Box 18212 House, TV. Butterworth Inc. (USA), 3721 Lapas Dr., P.O. Box 18312. Houston, TX 77223-9989

Butterworth Systems (UK), 123 Beddington Lane, Croydon CR9 4NX England
Penco Division/Hudson Engineering Co. P.O. Box 68 Boxpage, NJ 07002

Penco Division/Hudson Engineering Co., P.O. Box 68, Bayonne, NJ 07002 TANK LEVELING INDICATORS

ANN LEVELING INDICATORS

ARMTEC Industries, Inc., Manchester, NJ 03103

Kockumation AB, Box 1044, S-212 10 Malmo, Sweden

Morine Moisture Control Co., 60 Inip Dr., Inwood. NY 11696

Norcontrol, 135 Fort Lee Rd., Leonia, NJ 07605

Salwico Inc., 5 Marine View Ploza, Hoboken, NJ 07030

Transamerica Delaval, Inc., Gems Sensors Division, Cowles Road, Plainville, CT 06062

DWING—Rarges Vessal Chartering, Marine View Ploza, Plainville, CT 06062

ville, CT 06062

TOWING—Barges, Vessel Chartering, Lighterage, Salvage, etc.

Allantic Towing Ltd., 300 Union Pl., St. John, N.B., Canada E2L 186

Bay-Houston Towing Co., 805 World Trade Bldg., Houston. Texas 77002

Bulkfleet Marine Corporation, 1800 West Loop So., Houston TX 77027

Curtis Bay Towing Co., Mercantile Bldg., Baltimore, Md. 21202

Henry Gillen's Sons Lighterage, 21 West Main St., Oyster Bay, N.Y. 11771

James Hughes, Inc., 17 Battery Pl., New York, NY 10004

International Transport Contractors Holland B.V., 5 Kenaupark, P.O. Box

21. Hagelem Holland

21, Haarlem, Holland
McAllister Bros., Inc., 17 Battery PL. New York, N.Y. 10004
McDonough Marine Service, P.O. Box 26206. New Orleans, La
Midland Affiliated Co., 580 Walnut St., Cincinnati, OH 45201
Moran Towing & Transportation Co., Inc., One World Trade Center, Suite
5335, New York, N.Y. 10048
National Marine Service, Transport Div., 1750 Brentwood Blvd., St. Louis,
MO 63144

MO 63144 Suderman & Young Co., Inc., 918 World Trade Bldg., Houston, Texas 77002
Turecomo Coastal & Harbor Towing Corp., One Edgewoter St., Clifton, Staten Island, N.Y. 10305

rurecamo Coastal & Harbor Towing Corp., One Edgewoter St., Cliffon, Staten Island, N.Y. 10305

VALVES AND FITTINGS
Camlock Flange Sales Corp., 60 Inip Dr., Inwood, N.Y. 11696
Clow Corporation, 1211 West 22nd St., Oak Brook, IL 60521
The Crosby Group, Inc., P.O. Box 3128, Tulso, O.K. 74101
Dover Corporation, Norris Division, P.O. Box 1739, Tulso, O.K. 74101
Hayward Marine Products, 900 Fairmount Avenue, Elizabeth, N.J. 07207
Jamesbury Corp., 640 Lincoln Street, Worcester, MA 01605
Marine Moisture Control Co., 60 Inip Dr., Inwood, N.Y. 11696
Metropolitan Plumbing Supply Corp., 50-09 Second Street, Long Island
City, NY 11101
Newmans Inc., 9 Joanna Court, East Brunswick, NJ 08816
Pittsburgh Brass Manufacturing, Sandy Hill Rd., R.D., 6 Box 387-A, Irwin, PA
15642
Stacey Fetterolf Corp., P.O. Box 103, States In 2010

1564Ž Stacey Fetterolf Corp., P.O. Box 103, Skippack. PA 19474 Stockham Valves & Fittings, Box 10326. Birmingham, AL 35202 Tate Temco, Inc., 1941 Lansdowne Road, Baltimore, MD 21227 Union Floneflics, P.O. Box 459, Clinton, PA 15026 Robert H. Wager Co., Inc., Passaic Avenue, Chatham. N.J. 07928 Woukesha Bearings Corp., 405 Commerce St., P.O. Box 798, Waukesha WI 53186

Westron Corporation, Valve Components Group, 4025 Rememberance Rd. N.W., Grand Rapids, MI 49504
William E Williams Valve Corporation, 38-52 Review Avenue, Long Island
City, NY 11101

Winel, Inc., 34655 Mills Road, North Ridgeville, OH 44039
Zidell Explorations, Inc., (Valve Division), 3121 S.W. Moody Avenue, Portland, OR 97201

VIBRATION ANALYSIS
DLI Engineering Corp., 253 Winslow Way West, Bainbridge Island, WA 98110

WATER PURIFIERS
Alfa Laval, Inc., Dept. MR-2, 2115 Linwood Ave., Fort Lee, NJ 07024
AquaGlobal, 50/60 Inip Dr., Inwood, NY 11696
Bull & Roberts, Inc., 785 Central Ave., Murray Hill, NJ 07974
Drew Chemical Corporation, One Drew Chemical Plaza, Boonton, NJ 07005

Everpure, Inc., 660 N. Blackhowk Dr., Westmont, IL Riley-Beaird, P.O. Box 31115, Shreveport, LA 71130 WELDING

WELDING
CRC Automatic Welding, P.O. Box 3227. Hauston, TX 77253-3227.
Metallizing Co. of America, Inc., 321 So. Hamilton, Sullivan, IL 61951.
Oerlikon Welding Industries, Inc., P.O. Box 40964. Hauston, TX 77240.
WINCHES AND FAIRLEADS.
Braden Winch Co., 800 East Dallas, Broken Arrow, OK 74012.
CONMACO, Inc., 820 Kansas Ave., P.O. Box 5097. Kansas City, KS 66119.
Fritz Culver, Inc., P.O. Box 569, Covington, La 70434.
Markey Machinery Co., 79 South Horton St., Seattle, Washington 98134.
McElroy Machine & Mfg. Co., Inc., P.O. Box 4454, W. Biloxi, MS 39531.
Reel-O-Matic Systems, Inc., 418 Hellam Street, Wrightsville, PA 17368.
Smith Berger Marine Inc., 516 So. Chicago St., Seattle, WA 98108.
Stanspec Corp., 13600 Deise Ave., Cleveland OH 44110.
Superior-Lidgerwood-Mundy Corp., 1101 John Avenue, Superior, WI 54880.
WINDOWS.

WINDOWS

Kearfolt Marine Products, A Singer Co., 550 South Fulton Avenue, Mt. Ver

WIRE AND CABLE

naconda Ericsson Inc., Continental Wire and Cable, P.O. Box 1863, York PA 17405

Anixter Bros., Inc., 4711 Golf Road, One Concourse Plaza, Skokie. Illinois 60076

Atlantic Cordage Corp., 60 Grant Ave., Carteret. NJ 07008

Delco Wire & Cable, Inc., 257 Rittenhouse Circle, Keystone Industrial Park

Bristol, PA 19007

Bristol, PA 19007
Seacoast Electric Supply Corp., 225 Passaic St., Passaic, NJ 07055
Seacoast Electric Supply Corp., 1505 Oliver St., Houston, TX 77007
Tri-Mark, Inc., 8585 Industry Park Drive, Piqua, OH 45356
WIRE ROPE—Slings
AISCO, 60 Grant Ave., Carteret, NJ 07008
Allonlic Cordage Corp., 60 Grant Ave., Carteret, NJ 07008
Bethlehem Steel Corp., Marlin Tower, Bethlehem, PA 18018
A.L. Don Company, Foot of Dock Street, Matawan, NJ 07747
1 & 1 Sling Company, 2626 Market Street, Dept. D. Aston. PA 19014
LINC

TINC
The Platt Bros. & Co., Box 1030, Waterbury, CT 06721
Smith & McCroken, 153 Franklin St., New York, N.Y. 10013

## **Avco Lycoming Delivers** First Production Engines For Navy's New LCACs



At Avco delivery ceremony were (L to R): John J. Kelly, vice president and general manager, New Orleans Operations, Bell Aerospace Textron; Capt. Charles Piersall, USN, project manager, Amphibious Ship Acquisition Project; and Donald K. Farrar, president, Avco Corporation.

In a recent ceremony held at Avco Lycoming's Stratford (Connecticut) Division, the company marked the initiation of production deliveries of TF40B marine gas turbine engines for the U.S. Navy's Landing Craft Air Cushion (LCAC) amphibious assault vehicle program. Officials of the Navy, LCAC prime contractor Bell Aerospace Textron, and Avco were on hand for the initial shipments of production engines.

The LCAC is an amphibious air cushion vehicle that can travel at speeds up to 50 knots and can quickly transport troops, equipment, and weapons from support ships located over the horizon to dry ground beyond the beach.

LCACs are expected to replace the Navy's current fleet of landing craft, which are of World War II design, dramatically improving the ship-to-shore capability of the Navy and Marine Corps.


## Calumet Tug 'Curly B' Repowered With Cummins Diesel Engines

Calumet Marine Towing Corporation of Chicago recently overhauled and repowered the renamed 90-foot tug Curly B, ex Waverly formerly owned by Souix City New Orleans Barge Line. A pair of Cummins KTA-2300-M provide the refurbished boat with a total of 1,880 bhp with which to tow barges and dock ships in Great Lakes harbors. Other new equipment includes two Twin Disc MG-540 6.18:1 reduction gears, twin Kalhenberg propellers and shafts, Mathers engine controls, and Wagner steering system.

## Hackenberger Appointed **Marketing Director For Tacoma Boat Division**

In a move aimed at strengthening marketing and sales efforts in its Northern Line Division, Tacoma Boatbuilding Company of Tacoma, Wash., has announced the appointment of Claus Hackenberger as director of marketing for that Division. Northern Line is a leading manufacturer of marine equipment, including winches, cranes, capstans, gearboxes, and propellers, and provides a full range of machine shop services to the industry.

Mr. Hackenberger has held various engineering management positions at both Tacoma Boat and Northern Line Machine, and holds master's degrees in mechanical, structural, and civil engineering from the University of Darmstadt in Germany.



## KOCH ELLIS BARGE & SHIP SERVICE

(504) 436-3766

P.O. Box 9130 Westwego, LA 70094

## **Heath Named Coal Sales** Manager For Pott's **Inland Waterways Division**



Geoffrey A. Heath

The Inland Waterways Division of Pott Industries Inc. of St. Louis, a Houston Natural Gas Corporation company, has named Geoffrey A. Heath manager-coal sales, it was announced by C.M. Jones **Jr.** vice president-coal sales. Pott Industries Inc. is the parent company of Federal Barge Lines, Inc., United Barge Company and Cora Coal Terminal.

Mr. Heath will be responsible for the marketing of barge services for coal shipments in the Upper Ohio River area, as well as in West Virginia, Ohio, Kentucky, and Tennessee. Prior to joining the Inland Waterways Division. he was sales manager/field representative for Derby Coal Company, after previously working as a coal development representative for C&O Railway.

## MarAd Approves Title XI To Aid In Refinancing Of ACL's \$3.7-Million Cruise Vessel

The Maritime Administration has approved in principle an application by American Cruise Line, Inc. of Haddam, Conn., for a Title XI guarantee to aid in refinancing the construction cost of the 96-passenger cruise vessel M/V America. The vessel has an overall length of 165 feet, molded beam of 36 feet, and is powered by a 900-bhp diesel engine.

The America has operated between ports along the inland and coastal waterways on the U.S. East Coast since her delivery in February 1982. The vessel was built by Chesapeake Shipbuilding, Inc. of Salisbury, Md.

The Title XI guarantee covers \$2,622,000, or 75 percent of the \$3,775,966 cost of the vessel.

## **New Fuel Management** System From Pandel —Literature Available

A computer-based fuel management system, the FMS-3, was introduced recently by Pandel Instruments, Inc. of Grand Prairie, Texas. This system compares the

fuel burned versus the speed made known efficiency levels. The sysfor vessels in the 4,000-bhp range and up. It consists of two major components: flow and temperature sensing devices, and the main computer unit with the system display.

The system monitors individual engine fuel burns and vessel speed, and the computer calculates the fuel burned per mile of operation. Performance charts for the individual vessel may then be con-

tem is configured to function with marine diesel engines using lowpressure fuel supply pumps and return fuel circuits. The FMS-3 has hardware and software correction factors for fuel heating during recycling, aeration of the return fuel, and flowmeter calibration.

Speed inputs to the FMS-3 come from either the vessel's on-board knot log or from the Pandel Channel-Scan™ remote depth sounder. structed to allow operation at System outputs are displayed on a

12-inch CRT that is equipped with an amber display format, which presents no degradation of night

Display formats are readily changed in system software to meet any particular fleet requirements. Several of these systems are now operating successfully on the Inland Waterways.

For more information and free literature on the FMS-3,

Circle 31 on Reader Service Card

## LEASE OR SALE

Deck

180' to 400'

## Tank and/or Deck

230' to 400'

## **Dump Scow**

D.W.T. 1600 L.T.

## **Drydocks**

1000 and 2000 T.

Deck

150' and 180' Series

## **Self-Unloading** Aggregate

D.W.T. 4000 S.T.

## Water Cranes

25, 100 and 150 T.

## Floating Docks

420' x 58' with or without crane


For additional information contact Tom Sherwood or Andy Canulette

> 3121 S.W. Moody Avenue Portland, Oregon 97201

Phone: 503-228-8691 Toll Free 1-800-547-9259 Telex 36-0503 • Cable "Zidell"

The 1984 Annual

# CATALOG



The World's Most Complete Annual Marine & Naval Equipment Catalog For Vessel Owners, Shipbuilders, Marine Designers, Naval Architects and Purchasing Agents.


> **DETACH AND MAIL**

Mail to: Marine Equipment Catalog c/o Maritime Reporter 107 East 31st Street New York, New York 10016

Yes, I wish to take advantage of this Special Pre-Publication Offer. Please reserve \_\_\_ of Marine Equipment Catalog.

Name	
Position	
Company	
Business	
Address	
,100,000	

- ☐ Enclosed is my remittance of \$45.00 per copy for copies of the Marine Equipment Catalog.
- ☐ Please bill me
- ☐ Please bill my company



t's true, we build a lot of supply boats. In fact, we build more supply boats than anyone else in the world. But we also build more than thirty different types of other vessels ranging from small pilot boats to giant 18,000 HP CATUGS." We build everything from crewboats, tugs, fishing boats, patrol boats, lift boats, utility boats and ferries to surface effect ships and amphibious landing craft with Bell Aerospace-Textron. And we have more dieselelectric shipbuilding experience than anyone in our field.

We offer complete in-house services from cost-free design and engineering to global warranty assistance. Should your vessel need modification or repairs, it can be done at our large dry dock. We even have a subsidiary to handle all of your spare parts requirements—promptly and accurately.

Our six shippards are staffed by shipbuilding experts who are supported by the latest technology including computer directed metal cutting robots.

We have been designing and building vessels for more than a quarter of a century and have delivered over 1,100 boats to some of the largest and smallest operators in the world.

This unequaled experience pays dividends in every boat we build and is one of the reasons for our success. Chances are we have already designed and built the kind of vessel you need. So—if you need a boat to transport something on or above the water, we can and want to build it for you. Ask us. Halter Marine, Inc., Box 29266, New Orleans, LA 70189 U.S.A., (504) 246-8900, Telex 58-4200, Cable HALMAR.



The Total Shipbuilding Group

# Season after season, Simrad earns the maritime fleet's trust at sea.

The maritime business is no piece of cake. Especially when it comes to electronics. Why, you don't even begin to earn trust until at least five of the seven seas have passed under your keel. Which is reason enough to build every piece of our maritime gear to withstand the rigors of non-stop, whirlwind passages.

SEE SEE COL SOL SEE

ADF TD-C328

\*Complies with SOLAS and IMCO recommendations

Like our Navigation Sounder, the ED 161\* Its powerful transmitter insures flawless recording. And its depth alarm is loud enough to crank the heads of a few mates in the event it should ever go off.

In the Shortwave Marine Band ADF department, the TD-C328H ATS is our recommendation, plus a few others.\* Reliability is critical and therefore inherent. In addition, its distance indicator will remind you of just how far you've come and how far you've yet to go.

Distress-wise, our

FCC approved RW-105 Watch Alarm Receiver carries out the dutiful job of monitoring 2182 kHz impeccably. A built-in digital watch automatically lifts the mute during long periods of silence and also kicks-in when receiving two-tone alarm signals.

And of course, there are many other products we'd like to have shown you but can only talk about. Like our NL Doppler Speed Log. One of, if not, the least expensive doppler log systems to install. Or our TF series FAX machines — the 753 and 788 are as state-of-the-art as money can buy. And the last line for your consideration: our Loran C's. They are, without question, the most accurate and simpliest Loran C's available today.



So whether you're taking your electronics back to square one or just yanking a single piece of gear, consider one of the most trusted names on any sea.

Ours.



## **SIMRAD**

A trusted name at sea.
2215 Northwest Market Street
Seattle, Washington 98107
(206) 789-6482
New York
New Orleans
San Diego



See us at Work Boat Show, Booth #212 & 213.

Circle 154 on Reader Service Card

# Days away from the nearest port. A fire breaks out in the engine room. What happens?



All too often, the fire turns into a major disaster. Why? Because poorly designed and maintained fire protection systems fail to operate the way they were supposed to. Whether the reason is neglect or unqualified personnel performing maintenance, the result is the same. A small fire becomes a big headline

Wormald Fire Systems can help prevent that from happening.

We're part of the world's largest fire protection company. And coincidentally, the company most experienced in marine fire protection. With makine professionals at or near all the world's major shipping ports, we can respond quickly to your needs... wherever your ships are being built or serviced.

We'll work closely with naval architects to design, fabricate and install effective fire alarm, detection

and suppression systems. Or we'll meet your ships at a particular port and conduct a thorough inspection of on-board fire protection systems. In some cases, we can service those systems at the same time. Or arrange for more extensive servicing to be performed at the ship's next port of call.

For a free booklet on how we can help protect your ships from disasterous fires, contact John Goudreau, Wormald Fire Systems, One Stanton St., Marinette, WI 54143. Phone (715) 732-4423 or telex Wormald 26-3440.

W WORMALD FIRE SYSTEMS

Ask Wormald about fire protection.